



**OFFICE OF THE PANCHAYAT SAMITI, JODA
KEONJHAR, ODISHA-758038**

Letter No: 2134 Date: 18.06.2018

e-mail- ori-joda@nic.in
Mob- 8280405210

DETAIL TENDER CALL NOTICE 01/BDO-JODA OF 2018-19

1. Sealed tenders in conformity with detail tender call notice are invited from the eligible class of contractor registered with State PWD/Irrigation/CPWD/MES/Railway and other Govt. Organizations for the works as given below. The sale and receipt of the Bid document shall start from 20.06.2018 during office hours and close on Dt. 04.07.2018 at 5.00P.M. in the office of the Block Development Officer, Joda Dist-Keonjhar. The bids will be opened by the Tender committee of Panchayat Samiti, Joda i.e. at 02.30 P.M. on dated 05.07.2018 in presence of the bidders or their authorized representatives who wish to attend. If the office happens to be closed on the date of opening, the bid will be opened on the next working day at the same time and venue.

Further details terms & conditions & other eligibility criteria can be obtained from the Panchayat Samiti, Joda during the office hours up to 04.07.2018 or from District website www.kendujhar.nic.in. The sealed bid document can be sent by Registered Post/Speed Post only.

The bidders interested to can be downloaded the Tender Paper from the website www.kendujhar.nic.in has to deposit the cost of Tender paper in shape of demand draft to be pledged in favour of Block Development Officer, Joda.

S L N o	Name of the G.P.	Name of the work(Scheme)	Tender value in (Rs.)	Cost. Of Tender Documents (Non-refundable (Rs)	EMD in Rs. As @ of applicable	Time of Completion	Class of Contractors
1	2	3	4	5	6	7	8
1	PALASA	Construction of AWC Building at Uchabali , DMF	611724	4000.00	6200	"04" months	D" & "C"
2	Block H Qr	Const. of staff Quarter (ABDO) at Joda Block	719665	4000.00	7200	"04" months	D" & "C"
3	Block H.Qr..	Construction of Staff quarter(Accounts Officer) at Joda Block	719665	4000.00	7200	"04" months	D" & "C"

Sd/-

-Block Development Officer, Joda

TERMS & CONDITIONS

1. Cost of tender: Tender documents for the individual works may be obtained from the Block office Joda as per annexure on payment towards cost of tender paper in shape of Bank draft drawn in any nationalized bank in favour of BDO, Joda payable in Axis Bank, Joda of Keonjhar District.
2. Sale of tender paper: Tender documents will be sold from 20.06.2018 to 04.07.2018 from 10.00A.M. to 05.00P.M.(working days only).
3. Date of receipt of tender paper: Tender paper in complete in all respect will be received from 20.06.2018 from 10.00A.M. to 05.00P.M working days only in the office of the Block Development Officer, Joda through REGISTERED POST/SPEED POST only. Tender received by post after the stipulated date and time mentioned above will not be considered .
4. Date of opening of tender paper: The tender shall be opened on 05.07.2018 at 02.30P.M. in the office of the Block Development Officer, Joda in presence of the Bidders or their authorized representatives having written authorization for the purpose along with all relevant original documents.
5. Earnest money deposit:-01% (one percent) of the Bid value in shape of post office term deposit/short term deposit/N.S.C./K.V.P./Deposit receipts of any nationalized Bank duly pledged in favour of Block Development officer, Joda .
6. The following documents should be furnished with the tender paper failing which the tender is liable for rejection.
 - a) Earnest money deposit pledge in favour of BDO, Joda.
 - b) Attested copy of valid contractor Registration Certificate.
 - c) Attested copy of valid PAN card/VAT clearance certificates.
 - d) Attested copy of valid labour license for the above project only(During Agreement for successful contractor).
 - e) Xerox copy of Bank Draft towards cost of tender paper.
 - f) The bidders have to produce an original affidavit in support of the authenticity of documents including EMD etc, attached with the tender paper.
 - g) The Engineer Contractors desirous of availing exemption of EMD should submit an original affidavit as regards the fact of availing award of work without submission of EMD/ISD during the current financial year, otherwise their tender paper will be liable for rejection.
 - h) The SC/ST Contractors desirous of availing preference should submit an original affidavit in support of caste certificate and attested copy of caste certificate, otherwise their tender paper will be liable for rejection.
 - i) Joint venture consortium agreements are not allowed to participate in tender.
 - j) A critical analysis and working procedure should be submitted along with bid paper if the quoted amount is less than the estimate cost by more than 10% for examination by the committee.
 - k) The name of the project for which tender paper is filled should be written in CAPITAL LETTERS on the cover in which all the required papers are kept and sealed .


7. **Additional performance security deposit:** As per Office Memorandum of Works Deptt. File No. 07556900052014 16/W Dt. 01.01.2015 of EIC-cum- Secy. to Govt. communicated vide Memo No.. 5077 dt. 28.11.2017 of DRDA, Keonjhar , Additional performance security shall be obtained from the bidder when the bid amount is less than estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price/rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost i.e. estimated cost put to tender minus the quoted amount as Additional Performance Security(APS) in shape of Demand Draft/Term Deposit Receipt pledged in favour of the Divisional Officer within seven days, otherwise the bid shall be cancelled and the security deposit shall be forfeited. Further, proceeding for blacklisting shall be initiated against bidder".
8. Shortfall of any required document(s), draft(s) and EMD, tender paper is liable for rejection.
9. If the date of sale, receipt and opening of the tender as specified above happens to be holiday(s), then the process of the sale, receipt and opening whatsoever will be shifted to immediate next date of tender paper opening may be postponed as per the convenience of the authority by intimating all the concerned tenders through notice affixing to notice board at Panchayat Samiti, Joda only.
10. The details of successful bidders against each work will be displayed in the notice board. The successful bidders will collect the letter of acceptance from the office of the undersigned within 07 days from the date of declaration of list of successful bidders on the notice board in order to avoid postal delay for early execution of the work. No further claim will be entertained for non receipt of acceptance letter.
11. The EMD amount is to be forfeited if the tender backs out from the offer acceptance of tender by the competent authority.
12. The authority reserves the right to reject any or all the tenders without assigning any reason thereof.
13. The successful bidder shall sign an agreement with BDO, Joda in the non-judicial paper of worth Rs.200/-(Rupees Two hundred)only for executing the work.
14. The detail plan & estimate may be checked and the work shall be executed or done by ;the successful bidder as per the plan & estimate of this office.


Block Development Officer,
Joda

Memo No 2135 Date: 18/06/2018


Copy submitted to the Collector & District Magistrate, Keonjhar/P.D. DRDA, Keonjhar/P.A. ITDA, Keonjhar/ Champua /All Sub-Collector of Keonjhar Dist./Deputy Director(Planning & Statistics)Keonjhar for favour of kind information and necessary action with a request to kindly display the same in their office notice Board for wide publication.

Copy submitted to the D.I.O. NIC, Keonjhar to host the tender Notice in the Dist. Website.


18/06/18
Block Development Officer
Joda


Memo No 2136 Date: 18/06/2018

Copy to the Executive Officer, Joda Municipality/Barbil Municipality/Office Notice Board/All Sarpanches of Joda Block for information with request to display the same in their office Notice Board for wide publication.


18/06/18
Block Development Officer
Joda

Memo No 2137 Date: 18/06/2018

Copy submitted to the Chief Editor the Sambad Edition to arrange publication in one issue of the daily newspaper within Rs. 8000/- limit.


18/06/18
Block Development Officer
Joda

APPROVED TENDER SCHEDULE

Name of the work: -Const. of AWC building at Unchabali village under Palasa G.P. *E/C RS 7,00,000/-*

Amount put to tender: 611724/-
 Class of contractor: D & C
 Cost of Tender Paper : Rs.4000/-
 Earnest money Deposit 1% : Rs.6200/-
 Time of Completion: 04 months

Sl.	Discription of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	24.76	134.43	3328.00
2	Supplying and Filling in foundation and plinth with sand, well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials, cost of labour, T & P, dewatering, shoring and shuttering required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	16.63	732.37	12179.00
3	Cement concrete of proportion (1:3:6) with using 40 MM size HCB metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc. complete & as per direction of Engineer in charge	Cum	7.91	4079.09	32265.00
4	Flyash brick masonry in CM(1:6) in foundation and plinth with using good quality flyash brick of 9" size having a crushing strength of not less than 35 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, convenience, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	6.51	3847.29	25045.00
5	R.C.C. M20 in plinth bend, chajja, etc. including a minimum compressive strength (in the work test) of 150 KG/sqcm in 15 CM cubes at 28 days with IS 456 & 516 using 12MM to 20MM size (20 MM not to exceed 25%) HCB granite stone chips of approved quality and from approved quarry including hoisting, lowering, laying and compaction concrete watering and curing four weeks including centering and shuttering and finishing the exposed surface smooth with cost, conveyance, royalty and taxes of all materials and labour with T & P required except cost of labour for reinforcement for the work etc complete as direction by the engineering-in-charge.	Cum	22.07	4648.65	102595.00
6	Suppling, fitting and placing on quoted HYSD bar reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specificaiton as directed by the engineering-in-charge.	Qti.	23.17	5545.83	128516.00

7	Rigid Smooth centering and shuttering for RCC works including false works and dismantling them after casting including cost of materials complete as per the direction of the engineering -in-charge.				
	(a) Beam & Column	Sqm	50.57	573.39	28996.00
	(b) Fndn & Plinth bend	Sqm	17.68	97.51	1723.00
	(c) Lintel bend	Sqm	14.41	241.82	3484.00
	(d) Slab & Chajjas	Sqm	48.80	365.99	17860.00
8	Flyash brick masonry in CM(1:6) in super structure with using good quality flyash brick of 9" size having a crushing strength of not less than 35 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, convenience, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	20.96	3880.29	81330.00
9	Flyash brick masonry in CM(1:4) in super structure with using good quality flyash brick of 9" size having a crushing strength of not less than 35 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, convenience, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	1.14	4075.68	4646.00
10	20mm thick Plaster with CM 1:4 finished smooth over stone masonry after ranking out joints including watering and curing with cost, conveyance, royalty of all materials, labour with T & P required for the work including all taxes, etc. complete in all respect in all floors as directed by engineer-in-charge.	Sqm	59.42	170.86	10152.00
11	6mm thick ceiling plaster in cement mortar 1: 4 to RCC surface including all cost conveyance, royalty etc complete as per the direction of the engineering in charge.	Sqm	59.66	114.76	6847.00
12	16 mm thick cement plaster in C.M. (1:6) finishing smooth to inner side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	78.74	150.03	11813.00
13	12 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	97.76	102.96	10065.00
14	Supplying , fitting and fixing MS Grill , window & door etc of approved quality and make including cost of all materials and labour for fixing in position,conveyance,taxes and all respect as directed by the enginnering in-charge.	Kg.	863.00	94.50	81553.00

15	2.5CM thick A.S.flooring with c.c. 1:2:4 using 12 MM size HGCB chips including neat cement punning and curing and cost of all materials etc. complete as directed by engineering-in-charge.	Sqm	39.96	238.96	9547.00
16	12 mm thick cement plaster in C.M. (1:4) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	6.18	123.56	764.00
17	Fixing the vetrified tiles in floor,treads or steps and landing of on 25 mm thick C.P. (1:1) jointed with neat cement slurry including all cost of materials etc complete as directed by the engineering-in-charge.	Sqm	4.54	1005.54	4565.00
18	Fixing Vetrified tiles in in wall on 12 mm thick cement plaster(1:3) jointed with neat cement slurry mixed with pigments to matche shade of the tiles including polishing complete as per direction of EIC...	Sqm	13.38	1283.73	17176.00
19	Cement washing 1 coat with shell lime on slacked & cement including all cost, taxes etc complete as per direction of Engineer in charge.	Sqm	242.34	13.37	3240.00
20	Finshing wall with water proofing enamel paint of approved shade on new work two coats to give an even shade including cost of cement paint complete as per the direction of the engineer-in-charge.	Sqm	242.34	28.34	6868.00
21	Labour charges for painting two coats enamel painting over one coat of primer over doors, Windows & Grills including cost of paint and primer of approved make & shade,etc. complete as directed by the engineering in charge.	Sqm	45.22	103.22	4667.00
22	Const. of worksite signboard as per approved drawing including painting & writing as per direction of engineering in-charge.(Size 5' X 4')	No.	1	2500	2500.00
				Rs.	611724.00
				SAY Rs.	6,11,724/-

Tender schedule for the project:-Const. of AWC building at Unchabali under Palasa G.P. Joda Block is approved for Rs. 6,11,724/--(Rupees Six Lakh Eleven thousand Seven hundred twenty four)only excluding 12% GST with 22(Twenty two) items only .GST 12% will be added at the time of Aggrement.

Block Development Officer
Joda

[Handwritten Signature]
15/10

Approved by
[Handwritten Signature]
19/10/18
Addl.P.D. (Technical)
DRDA,Keonjhar

Approved Tender Schedule


Name of the Work : Construction of Staff Quarter (ABDO) at Joda Block.		Estimated cost : Rs.9,00,000/-			
		Amount put to Tender : Rs.7,19,665/-			
		Class of Contractor : "D & C"			
		Cost of Tender Paper : Rs.4,000.00			
		Earnest Money Deposit 1% : Rs.7200.00			
		Time of completion : 06(Six) months			
Sl.	Discription of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with initial lead & lift as per direction of Engineer in charge	Cum	34.37	127.96	4397.00
2	Filling sand in foundation with well watered and rammed for base with all cost complete.	Cum	49.48	490.26	24258.00
3	Cement Concrete(1:4:8) with 40 mm size HB metal	Cum	9.42	3338.10	31445.00
4	1st class Flyash Brick in (1:6) Cement mortar for foundation & Plinth.....	Cum	10.14	3471.78	35200.00
5	R.C.C. M20 with 12 mm size hard broken granite chips for RCC works including laying and moisting.	Cum	23.47	4478.32	105106.00
GROUND FLOOR					
6	Suppling, cutting, bending, binding & taying the grills in position including cost of binding wires 18mm to 20mm guage.	Qti.	23.00	5518.39	126922.00
7	Rigid Smooth centering and shuttering for RCC works including false works and dismentalling them after casting including cost of materials complete.				
	(a) COLUMN BASE	Sqm	19.30	96.26	1857.00
	(b) plnth bend	Sqm	27.60	96.26	2656.00
	comumn	Sqm	42.60	556.96	23726.00
	Beam	Sqm	30.43	556.96	16948.00
	(c) Lintel bend				
	GROUND FLOOR	Sqm	21.70	237.80	5160.00
	(d) Slab & Chajjas				
	chajja	Sqm	21.00	358.33	7524.00
	Roof slab	Sqm	57.30	358.33	20532.00
8	1st class Flyash Brick in (1:6) Cement mortar for super structure.....				
	Quantity of Item no-(5+6) of estimate	Cum	24.14	3504.78	84605.00
9	20mm thick Plaster with CM 1:4....	Sqm	71.10	159.88	11367.00
10	6mm thick plaster with 1:4CM over R.C.C. with close deep chiping including cost.....				
	GROUND FLOOR	Sqm	89.50	108.62	9721.00
11	16 mm thick with CM1:6.....				
	GROUND FLOOR	Sqm	199.50	140.10	27950.00
12	12mm thick plaster 1:6.....				
	GROUND FLOOR	Sqm	124.50	95.66	11910.00
13	Providing and fixing MS Grill in window & door including cost, conveyance, taxes and all labour charges etc. complete....	Kg.	218.00	92.52	20169.00

14	Supplying, fitting and fixing in position welldressed & well seasoned sal wood work fram and fixed(wrought & put up) in choukaths for doors & windows & vent.includingcost of materials & labour charges etc. complete as per direction of engineer-in-charge.	Cum	0.51	48190.49	24577.00
15	Supplying ,fitting, fixing of FRP doorshutter of approved quality with cost of all fittings including cost of materials & labour charges etc. complete as per direction of Engineer-incharge.	Sqm	22.00	2310.36	50828.00
16	2.5 Cm A.S. flooring with C.C.(12:4) including punning using 12mm size hard broken granite chips				
	GROUND FLOOR	Sqm	50.10	229.48	11496.00
17	Fixing the Vetrified tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement slurry				
	GROUND FLOOR(TOILET INSIDE)	Sqm	19.92	1260.72	25114.00
18	Cement washing 1 coat with shell lime on slacked & cement including all cost, taxes etc complete as per direction of Engineer in charge.				
	GROUND FLOOR	Sqm	413.50	13.37	5528.00
19	Painting wall surface with two coats of weather coats including cost of material & labour charges.....	Sqm	124.50	77.10	9598.00
20	Distempering to inside wall surface with two coats of Distemper including cost of material & labour charges..	Sqm	277.30	51.06	14158.00
21	Painting to door & windows with two coats of enamel paint including cost of material & labour charges.....	Sqm	10.13	100.05	1013.00
22	Suppling fitting fixing sky light	No.	9.00	100.00	900.00
23	DISPLAY BOARD	No.	1	5000.00	5000.00
	23(TWENTY THREE)ITEMS (EXCLUDING GST)			SUB-TOTAL	719665.00

(RUPEES SEVEN LAKH NINETEEN THOUSAND SIX HUNDRED SIXTY FIVE)ONLY

Tender schedule for the project "Construction of Staff Quarter(ABDO) under Joda Block is approved for Rs.7,19,665.00(Rupees Seven lakh Nineteen thousand Six hundred Sixty Five)only excluding GST 12% with 23(Twenty-Three) items only. GST 12% will be added at the time of Aggrement.


Block Development Officer
Joda




APD (Tech)
Distt. P.D. (Tech.)
D.R.D.A. Keonjhar

Approved Tender Schedule

Name of the Work : Construction of Staff Quarter (ACCOUNTS OFFICER) at Joda Block.		Estimated cost : Rs.9,00,000/-			
		Amount put to Tender : Rs.7,19,665/-			
		Class of Contractor : "D & C"			
		Cost of Tender Papeer :Rs.4,000.00			
		Earnest Money Deposit 1% : Rs.7200.00			
		Time of completion : 06(Six) months			
Sl.	Discription of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with initial lead & lift as per direction of Engineer in charge	Cum	34.37	127.96	4397.00
2	Filling sand in foundation with well watered and rammed for base with all cost complete.	Cum	49.48	490.26	24258.00
3	Cement Concrete(1:4:8) with 40 mm size HB metal	Cum	9.42	3338.10	31445.00
4	1st class Flyash Brick in (1:6) Cement mortar for foundation & Plinth.....	Cum	10.14	3471.78	35200.00
5	R.C.C. M20 with 12 mm size hard broken granite chips for RCC works including laying and moisting.				
	GROUND FLOOR	Cum	23.47	4478.32	105106.00
6	Suppling, cutting, bending, binding & taying the grills in position including cost of binding wires 18mm to 20mm guage.	Qti.	23.00	5518.39	126922.00
7	Rigid Smooth centering and shuttering for RCC works including false works and dismentalling them after casting inluding cost of materials complete.				
	(a) COLUMN BASE	Sqm	19.30	96.26	1857.00
	(b) plnth bend	Sqm	27.60	96.26	2656.00
	comumn	Sqm	42.60	556.96	23726.00
	Beam	Sqm	30.43	556.96	16948.00
	(c) Lintel bend				
	GROUND FLOOR	Sqm	21.70	237.80	5160.00
	(d) Slab & Chajjas				
	chajja	Sqm	21.00	358.33	7524.00
	Roof slab	Sqm	57.30	358.33	20532.00
8	1st class Flyash Brick in (1:6) Cement mortar for super structure.....				
	Quantity of Item no-(5+6) of estimate	Cum	24.14	3504.78	84605.00
9	20mm thick Plaster with CM 1:4....	Sqm	71.10	159.88	11367.00
10	6mm thick plaster with 1:4CM over R.C.C. with close deep chiping including cost.....				
	GROUND FLOOR	Sqm	89.50	108.62	9721.00
11	16 mm thick with CM1:6.....				
	GROUND FLOOR	Sqm	199.50	140.10	27950.00
12	12mm thick plaster 1:6.....				
	GROUND FLOOR	Sqm	124.50	95.66	11910.00
13	Providing and fixing MS Grill in window & door including cost, conveyance, taxes and all labour charges etc. complete....	Kg.	218.00	92.52	20169.00

14	Supplying, fitting and fixing in position well dressed & well seasoned sal wood work frame and fixed (wrought & put up) in chookaths for doors & windows & vent. including cost of materials & labour charges etc. complete as per direction of engineer-in-charge.	Cum	0.51	48190.49	24577.00
15	Supplying, fitting, fixing of FRP door shutter of approved quality with cost of all fittings including cost of materials & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	22.00	2310.36	50828.00
16	2.5 Cm A.S. flooring with C.C.(12:4) including punning using 12mm size hard broken granite chips	Sqm	50.10	229.48	11496.00
	GROUND FLOOR				
17	Fixing the Vetrified tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement slurry	Sqm	19.92	1260.72	25114.00
	GROUND FLOOR(TOILET INSIDE)				
18	Cement washing 1 coat with shell lime on slacked & cement including all cost, taxes etc complete as per direction of Engineer in charge.	Sqm	413.50	13.37	5528.00
	GROUND FLOOR				
19	Painting wall surface with two coats of weather coats including cost of material & labour charges.....	Sqm	124.50	77.10	9598.00
20	Distemping to inside wall surface with two coats of Distemper including cost of material & labour charges..	Sqm	277.30	51.06	14158.00
21	Painting to door & windows with two coats of enamel paint including cost of material & labour charges.....	Sqm	10.13	100.05	1013.00
22	Suppling fitting fixing sky light	No.	9.00	100.00	900.00
23	DISPLAY BOARD	No.	1	5000.00	5000.00
	23(TWENTY THREE)ITEMS (EXCLUDING GST)			SUB-TOTAL	719665.00

(RUPEES SEVEN LAKH NINETEEN THOUSAND SIX HUNDRED SIXTY FIVE) ONLY

Tender schedule for the project "Construction of Staff Quarter (ACCOUNTS OFFICER) under Joda Block is approved for Rs.7,19,665.00 (Rupees Seven lakh Nineteen thousand Six hundred Sixty Five) only excluding GST 12% with 23 (Twenty-Three) items only. GST 12% will be added at the time of Agreement.

Block Development Officer
Joda

[Signature]
AO

[Signature]
12/3/18
APD (Tech)
DRDA, Keonjhar (Tech.)
Addl. Keonjhar
D.R.D.A. Keonjhar

My quoted rate is% Excess.....% Less or Schedule rate
(Both in figure and words) over the above amount put to tender.

Note

- 1 The Contractor should not write anything except quoting or percentage and in any case anything else regarding tender rate is mentioned, the tenderer is liable for rejection
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figures and words, so that there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractors in words shall be taken as correct.
- 5 The percentage quoted in the tender with out mentioning excess or less will be treated as excess.
- 6 The Contractor should write percentage excess or less up to Two decimal point only. If he writes the percentage excess or less up two decimal points the first decimal point shall only be considered with out rounding off.