

**Construction of proposed new HWC Building at  
Bnunshagada SC under Anandapur Block for  
the year 2019-20**

Tender schedule for the Work:

Amount put to Tender : RS 535537.00  
 Class of Contractor : D' & C' class only  
 EMD @ 1% : Rs 5356.00  
 Time required for completion : 3(Three) calender Month

SCHEDULE OF WORKS					
Sl No	Description of item of works	Qty	Unit	Estimate Rate	Amount
				Figure	
1	Earth work in excavation of foundation in Hard soil with all leads and lifts including dressing and levelling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour T&P and dewatering if required for the work etc. complete as per the specification and direction of the Engineer-in-charge.	17.83	One Cum	184.79	3294.81
2	Providing Filling Foundation & plinth with approved quality sand in layers not exceeding 150mm thick well watered and rammed with cost, conveyance, royalties, taxes for finished item complete in all respect as per the direction of Engineer-in-charge.	22.41	One Cum	410.92	9210.21
3	Providing & Laying C.C (1:3:6) using 4 cm size B.H.G.Metal of approved quality including hoisting, lowering, laying, watering & curing, dewatering, shoring, shuttering if necessary with cost, conveyance, royalty & taxes of all other materials etc. complete as per the direction of Engineer-In-charge.	6.50	One Cum	4163.70	27069.71
4	1st Class Fly Ash Brick Masonry in C. M. (1:6) in substructure including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete. as per the direction of Engineer in Charge.	7.09	One Cum	4000.40	28351.48
5	1st Class Fly Ash Brick Masonry in C. M. (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete. as per the direction of Engineer in Charge.	14.13	One Cum	4033.40	57000.63
6	R.C.C. M. 20 using 12 mm & down graded size b.h.g.c.b. chips including centering & shuttering, watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete as per the direction of Engineer in Charge.				0.00
	A. Column Base	2.29	One Cum	5548.14	12705.24
	B. Plinth Beam	2.71	One Cum	5548.14	15062.20
	C. Column & Beam	3.40	One Cum	11869.15	40397.32
	D. Lintel	1.64	One Cum	8598.22	14062.02
	E. Chazza/ Shelves	5.53	One sqm	773.97	4280.05
	F. Slab	4.93	One sqm	9103.73	44900.70
7	Cutting, bending and binding of M.S. rod and tor steel from SAIL / RINL / TISCON including cutting, bending, binding and tying the grills placing in position for R.C.C. work with cost, conveyance, taxes of all the materials & labour (T&P) etc. complete. as per the direction of Engineer-in-charge.	16.54	One Qtl	6234.54	103119.29
8	16mm thick cement plaster (1:6) in finished smooth over brick work after racking out joints including watering and curing with cost, conveyance taxes and royalties of all materials and cost of all labour with T&P required for the work complete as per the direction of Engineer in Charge.	114.62	One Sqm	181.89	20847.72
9	12 mm thick Cement Plaster (1:6) finished smooth over brick work with punning including watering and curing with cost, conveyance, royalty and taxes of all materials etc. complete as per the direction of Engineer-in-charge.	87.98	One Sqm	128.40	11296.59
10	Providing, supplying, fitting, fixing of Vetrified tiles on floors on 20mm bed of cement mortar (1:4) jointed with neat cement slurry mixed with pigment to match the shade including cost, conveyance, royalty and taxes of all materials and labour etc. complete as per the specification and direction of the Engineer-in-charge.	37.25	One Sqm	1053.78	39251.43

Signature of Tenderer with seal

**Construction of proposed new HWC Building at  
Baunshagada SC under Anandapur Block for  
the year 2019-20**

Tender schedule for the Work:

Amount put to Tender : RS 535537.00  
 Class of Contractor : D' & C' class only  
 EMD @ 1% : Rs 5356.00  
 Time required for completion : 3(Three) calender Month

SCHEDULE OF WORKS					
11	Providing, supplying, fitting, fixing of Vetrified tiles on Daccos & Skitting on 12mm bed of cement mortar (1:3) jointed with neat cement slurry mixed with pigment to match the shade including cost, conveyance, royalty and taxes of all materials and labour etc. complete. as per the specification and direction of the Engineer-in-charge.	3.02	One Sqm	972.17	2935.22
12	6mm thick C.P. (1:4) as ceiling plaster finished smooth including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	37.68	One Sqm	142.72	5377.72
13	Providing, fitting, fixing of M.S. Door / Window / Grill gates made out of M.S. Angle, flat, sheet etc. including cost, conveyance, taxes of all materials and labour (T&P) etc. complete. as per the direction of Engineer-in- charge.	5.44	One Qtl	11668.07	63474.30
14	WC painting two coat with approved paint over a coat Priming over wall surface including cost of all materials and labour (T&P) etc. complete. as per the direction of Engineer-in- charge.	87.98	One Sqm	125.91	11077.57
15	Plastic paint two coats with priming over wall surface with any approved shade including cost of all materials and labour (T&P) etc. complete.	114.62	One Sqm	132.42	15178.16
16	Enamel Painting two coats over a coat of primer including cost of paint and primer with cost, conveyance, taxes of all materials and labour (T&P) etc. complete.as per the direction of Engineer-in-Charge.	37.25	One Sqm	178.37	6644.70
					<b>535537.06</b>

TOTAL 16 (Sixteen) NOS ITEM ONLY

Approved for 16(Sixteen) items only

CDM & PHO  
Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
 Excess in Percentage  
 Less in Percentage

	In Figure	In words
	%	
	%	
	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken ir,to consideration.

**OFFICE USE ONLY**

Construction of proposed new HWC Building at Baunshagada SC under Anandapur Block for the year 2019-20

Sold for above work on payment of RS.....only per set vide money  
 receipt No..... Book No..... Dt.....

EMD: Rs..... In shape of  
 Regisration certificate furnished / not furnished  
 STCC (GSTIN) furnished / not furnished  
 ITCC (Pan Card) furnished / not furnished  
 No of Correction .....  
 No of over writing .....  
 No of Interpolation.....

Signature of Tenderer with seal