

BILL OF QUANTITY

**Construction of proposed HWC building at
Badamasinabila under Ghatgaon block for the
year 2019-20**

Name of the work

CLASS OF CONTRACTOR

: "D" & "C" Class

APPROXIMATED COST

Rs 535682.00

COST OF TENDER PAPER

Rs 4000.00

TIME OF COMPLETION

: 2 (two months)

E.M.D @ 1%

Rs 5357.00

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	AMOUNT Rs. P
1	Earth work in excavation of foundation in Hard soil with all leads and lifts including dressing and levelling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour T&P and dewatering if required for the work etc. complete as per the specification and direction of the	18.48	One Cum	184.80	3415.10
2	Providing Filling Foundation & plinth with approved quality sand in layers not exceeding 150mm thick well watered and rammed with cost conveyance, royalties, taxes for finished item complete in all respect as per the direction of Engineer-in-charge.	22.25	One Cum	455.35	10131.75
3	Providing & Laying C.C (1:3:6) using 4 cm size B.H.G. Metal of approved quality including hoisting, lowering, laying, watering & curing, dewatering, shoring, shuttering if necessary with cost conveyance, royalty & taxes of all other materials etc. complete as per the direction of Engineer-in-charge.	7.29	One Cum	4008.77	29223.93
4	Brick masonry in cement mortar (1:6) in Super Structure using Fly Ash Bricks having crushing strength not less than 75 Kg/cm ² in super structure after immersing the bricks for six hours in water before use in all floors with all necessary projection, cutting, minding, corbelling, chamfering, watering and curing including cost	23.23	One Cum	4051.16	94106.45
5	RCC M 20 concrete using 12mm & down graded size C.B.H.G chips of approved quality including hoisting, lowering, laying, watering, curing & shuttering if necessary with cost conveyance, royalties & taxes of all other materials etc. complete in all respect as per the direction of Engineer-in-charge. (a) Column Base				
A	Column base	3.31	One Cum	4564.79	15109.45
B	Plinth beam	2.29	One Cum	4910.58	11245.23
C	Column & beam	4.17	One Cum	9858.56	41151.98
D	Lintel	0.72	One Cum	7950.66	5731.68
E	Chara	5.36	One Sqm	732.95	3928.61
F	Roof slab	5.06	One Cum	8469.97	42858.05
6	Cutting, bending and binding of M.S. rod and tor steel from SAIL / RINL / TISCOON including cutting, bending, binding and tying the grills placing in position for R.C.C work with cost, conveyance, taxes of all the materials & labour (T&P) etc. complete	17.95	One QM	6375.57	114559.12
7	16mm thick cement plaster (1:6) in finished smooth over brick work after racking out joints including watering and curing with cost conveyance taxes and royalties of all materials and cost of all labour with T&P required for the work complete as per the direction of Engineer in Charge.	119.46	One Cum	180.19	21525.50
8	12mm thick cement plaster (1:6) in finished smooth over brick work after racking out joints including watering and curing with cost conveyance taxes and royalties of all materials and cost of all labour with T&P required for the work complete as per the direction of Engineer in Charge.	120.14	One Sqm	127.02	15260.18
9	6mm thick cement plaster (1:4) in finished smooth over brick work after racking out joints including watering and curing with cost conveyance taxes and royalties of all materials and cost of all labour with T&P required for the work complete as per the direction of Engineer in Charge.	40.84	One Sqm	134.41	5486.30
10	Providing and supplying for fitting & fixing of M.S. Grills to Windows, M.S. Door, M.S. Windows and openings made out of approved size angle frame and square bar of approved design etc complete in all respect as per the Engineer in Charge.	681.50	One kg	116.78	79585.57
11	Providing and applying weather coat paint of two coats of approved shade including cost conveyance and taxes of cement paint, cost of all labour, T&P required for the work etc. complete as per direction of Engineer In Charge	120.14	One Sqm	125.90	15126.63

Signature of Tenderer with seal

12	Painting two coats with Plastic emulsion paint over a coat of priming in all floors to new iron work including sand papering, polishing the surface, including cost conveyance taxes of all materials, cost of all labour. T&P required for the work including cost of paint & primer etc complete as per the direction of Engineer in Charge	163.33	One Sqm	132.41	21225.32
13	Painting two coats with Synthetic enamel paint over a coat of priming in all floors to new iron work including sand papering, polishing the surface, including cost conveyance taxes of all materials, cost of all labour. T&P required for the work including cost of paint & primer etc complete as per the direction of Engineer in Charge	33.68	One Sqm	172.37	6637.50
					535682.36
				Say	535682.00
Rupees five Lakh thirty five thousand six hundred eighty two only					

APPROVED

[Handwritten Signature]
22/10/19

CDM & PHO
Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words):

Equal to Est mate Cost

in Figure

in words

Excess - % Percentage

%

Less - % Percentage

%

Notes -

1) The Tenderer should quote the percentage up to one decimal point only

2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering

3) The Tenderers should quote their percentage only inside the space provided for the purpose

4) The percentage quoted at any other place will not be taken into consideration.

OFFICE USE ONLY

Construction of proposed HWC building at Banamahuldiha under Patna block for the year 2019-20

Sold for above work on payment of RS only per set vide money receipt No Book No Dt

EMD: Rs. In shape of
Registration certificate furnished / not furnished
STOC (GSTIN): furnished / not furnished

Signature of Tenderer with seal