

DISTRICT PROJECT OFFICE

SAMAGRA SHIKSHA, KEONJHAR - 758001

Email: - dpckeonjharssa.oepa@nic.in

PH: - 06766-254103 FAX: - 06766-256420



No. 3325 /C.W. Date 12.12.19.

File No. 111-4/2019-20

To

The D.I.O.
N.I.C., Keonjhar
Asst. Director (MIS),
OSEPA, Shiksha Soudha, Unit-V, BBSR

Sub: - **Hoisting of Quotation Call Notice in the Website of NIC, Keonjhar & OSEPA, Bhubaneswar.**

Sir,

With reference to the subject cited above, I am to enclose herewith the Draft Quotation Call Notice alongwith enclosures and request you to hoist the same in the Website of NIC, Keonjhar & OSEPA, BBSR for information of general public.

Yours faithfully,

Encl.:
Draft Quotation Call Notice &
enclosures


District Project Co-ordinator,
Samagra Shiksha, Keonjhar

**DISTRICT PROJECT OFFICE,
SS, KEONJHAR**
NO. 3324/CIVIL/19 DATED: 12.12.19

SHORT QUOTATION CALL NOTICE

Sealed quotations are invited from the registered/approved Soil Testing Lab/Institutions etc. for Soil Test for construction of 10 nos. upgraded KGBV hostel buildings (100 seated) at Dhakotha Nodal UPS of Anandapur, Harichandanpur Govt. UPS of Harichandanpur, Rutisila UPS of Ghatagaon, Billa UPS of Saharapada, Padampur UPS of Sadar, Khajurimundi UGUPS of Banspal, Sirigida UGUPS of Telkoi, Bhaluka UGUPS of Jhumpura, Champua UGUPS of Champua and Kamarjoda UGUPS of Joda Block under Keonjhar District. The details of the advertisement, specification, terms & conditions can be downloaded from the website www.osepa.in & www.keonjhar.nic.in. The applicant must apply only in the prescribed format and through Speed Post/Regd. Post only **latest by 24.12.2019 up to 01.00 P.M.** & the tender paper is to be **opened at 04.00 P.M of the same day**. The authority reserves the right to cancel any or all quotations without assigning any reason thereof.


**District Project Co-ordinator,
Samagra Shiksha, Keonjhar**



QUOTATION CALL NOTICE NO.		/Civil Dated	of District Project Office,
		Samaagra Sikshya, Keonjhar.	
SCHEDULE			
NAME OF THE WORK-SOIL INVESTIGATION/TESTING FOR CONSTRUCTION OF 10 NOS OF 100 SEATED KGBV (UPGRADED HOSTEL) BUILDINGS IN KEONJHAR DISTRICT.			
Sl. No.	Description	Quantity	Unit
1	Mobilisation of machanaries and trained personals to the destination site to and fro as per the direction of Engineer-in-charge	10	Each
2	Boring the soil hard/soft of 150 mm dia and conducting SPT/DCPT and collecting UDS and DS at 1.5 mt. Interval or at the junction of change of layers as per the direction of the Engineer-in-charge as mentioned in IS-1892-1979 upto a depth of 10 mt. And above.	10	Rm
3	Laboratory testing of UDS and DS samples as per direction of the Engineer-in-charge (15 Nos site) as per physical requirement		
	a. Grain sieve analysis	30	No
	b. Atterberg's limits (Cone Penetro meter)	30	No
	c. Moisture Content	30	No
	d. Specific Gravity	30	No
	e. Shear test including Bulk density	30	No
	f. Defferential Free Swell (DES)	30	No
4	Preparation of report recomending type of foundation alongwith SBC calculation in the booklet form in triplicate as per the direction of the Engineer-in-charge. (10 sites/ 30 booklets)	30	Sets
Cost for above activities per site in Rupees=			
In words=			
Total cost for 10 nos of sites in Rupees=			
In words=			

Note:- The soil test is to be conducted in Govt. Approved Laboratory.
GSTN & PAN details are to be submitted along with quotation.
Payment will be made only after submission of reports triplicate along with bills.


 District Project Co-ordinator,
 SS, Keonjhar.