

BILL OF QUANTITY (BOQ)

**NAME OF THE WORK: - Construction of Block Level Mini Stadium at Banspal.**

Amount put to Tender	:	Rs.17,31,824.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date of sale of Tender Paper	:	05.11.2020 to 19.11.2020 up to 1.00P.M.
Last Date of Receipt of Tender Paper	:	19.11.2020 up to 5.00 P.M.
Date of Opening of Tender	:	20.11.2020 at 11.00 A.M.
Date required for completion	:	3(Three) calender Month

Sl No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6.00
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	210.80	Each cum	183.64	38711.00
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	41.22	Each cum	637.68	26285.00
3	Cement Concrete (1:4:8) using 4 cm size bhg metal including watering, curing with cost, conveyance, royalty and taxes of all materials and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	1.49	Each cum	3899.42	5810.00
4	Cement Concrete (1:3:6) using 4 cm size bhg metal including watering, curing with cost, conveyance, royalty and taxes of all materials and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	39.73	Each cum	5180.65	205827.00
5	R.R.H.G. stone masonry with CM (1:6) in F & P. including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	103.29	Each cum	3328.52	343803.00
6	2.5cm. Thick D.P.C. with C.C.(1:2:4) using 12mm. Size cbg. Chips including cost, carriage and royalty complete.	171.05	Each Sqmt	274.42	46940.00
7	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	110.21	Each cum	4289.44	472739.00
8	P.C.C. (1:2:4) using 12 mm & down size b.h.g.c.b chips including watering, curing with cost, direction of Engineer-in-Charge.	5.54	Each Cum	5775.63	31997.00
9	20mm thick cement plaster in cm (1:6) with cost, carriage & royalty etc complete.	136.84	Each Sqmt	211.40	28928.00
10	12mm thick cement plaster in cm (1:6) with cost, carriage & royalty etc complete.	410.53	Each Sqmt	134.87	55368.00
11	16mm thick cement plaster in cm (1:6) with cost, carriage & royalty etc complete.	410.53	Each Sqmt	200.10	82147.00
12	Cement washing one coat over plastered surface with cost, carriage etc.complete.	957.90	Each Sqmt	13.64	13066.00


13	Finishing walls with water proofing cement paint with cost & carriage etc. complete.	957.90	Each Sqmt	31.69	30356.00
14	R.C.C.(1:1.5:3) with 12mm. C.B.G.Chips with all cost of labour, material, carriage & royalty etc. complete.	12.58	Each cum	6390.20	80389.00
15	Rigid smooth centring and shuttering for R.C.C.Works including false works and dismantling then after casting including cost of materials complete.	19.23	Each Sqmt	100.51	1933.00
16	Supplying, fitting and placing uncoated HYSD bar reinforcement as per drawing and technical specification including all cost complete.	15.10	Qntl	6345.04	95810.00
17	Fixing of Granite tiles in Pillars and top beam on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shade of the tile including rubbing and polishing complete.	43.85	Each Sqmt	2684.49	117715.00
18	Cost of MS. Grill Gate with fitting & fixing in proper position	720	Kg	75.00	54000.00
				Total Rs	1731824.00

TOTAL 18 (Eiahteen) NOS ITEM ONLY

Approved for 18(Eighteen) items only

  
23/9/2020  
Asst.Exe. Engineer  
Banspal Block

  
21/10/2020  
B.D.O.  
Banspal.

  
29/10/2020  
Executive Engineer  
DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
Excess in Percentage  
Less in Percentage

in Figure	In words
%	
%	
%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**OFFICE USE ONLY**

Sold for the work : Construction of Block Level Mini Stadium at Banspal Block. on payment of  
RS.....only per set vide money receipt No..... Book  
No..... Dt.....

EMD: Rs..... In shape of  
Regisration certificate furnished / not furnished  
STCC (GSTIN) furnished / not furnished  
ITCC (Pan Card) furnished / not furnished  
No of Correction .....

No of over writing .....

No of Interpolation.....

  
Block Development Officer  
Banspal Block