

## APPROVED TENDER SCHEDULE

Name of the work: -Construction AWC Building at Ghodabuda under Karadangi G.P under OMBADC	Amount put to tender:Rs 11,08,645/-			
	Class of contractor: D&C			
	Cost of Tender Paper : Rs.6,000/-			
	Earnest money Deposit 1% :Rs.11,086.00			
	Time of Completion: 04months			
Description of Item	Unit	Quantity	Rate	Amount
1. Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	40.96	180.00	7373.00
2. Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	43.48	454.20	19749.00
3. Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	12.74	3860.90	49188.00
4. Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	10.82	4116.45	44540.00
5. Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	36.77	4149.45	152575.00

6	Reinforcement cement concrete M - 20 grade with 20mm nominal size down graded nominal size aggregate mechanically mixed and Vibrated in foundation and bed protection of specification for road and Bridge works & direction of the Eng. In Charge.				
	a) Column Base	One cum	8.23	5099.90	41972.00
	b) Plinth bend	One cum	4.16	5440.80	22634.00
	c) Lintel Band	One cum	2.51	8533.60	21419.00
	d) Chajja	One Sqmt	16.32	775.20	12651.00
	e) Column & Roof beam	One cum	6.93	11993.80	83117.00
	f) Slab & Chajja	One cum	10.82	9073.80	98179.00
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specificaiton as directed by the engineering-in-charge.	Qtl	34.03	6471.40	220222.00
8	25mm thick A.S. flooring in Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips including punning with all cost conveyancy Royalty etc.	One Sqmt	2.18	300.40	655.00
9	Fixing tiles in floors, treads and landings on 25mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade	One Sqmt	76.09	931.30	70863.00
10	Fixing tiles in dados, skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles	One Sqmt	37.67	990.10	37297.00
11	16mm(5/8") thick cement plaster (1:6)in finished smooth to inside rough surface of 10" thick brick walls after racking out the joints including watering and curing with cost,	One Sqmt	239.36	191.10	45742.00
12	12mm(1/2") thick cement plaster (1:6)in finished smooth to outside smooth surface of brick walls afrer racking out joints including watering and curing etc.complete with	One Sqmt	139.87	135.10	18896.00
13	12mm thick cement plaster in cm (1:4) including cement punning and skirting with all cost conveyancy Royalty etc. complete.	One Sqmt	12.38	153.60	1902.00
14	Supplying Fitting & fixing of M.S shutter including cost of all materials etc. complete as per the direction of Engineer in Charge.	One Kg	940.35	75.00	70526.00
15	Painting two coats in all Doors and windows (Two coats with paints of approved shade and base coat with primer) to	One Sqmt	68.37	130.40	8915.00
16	Provision for fitting and fixing and cost of Ventilator etc. complete.				
	a) Ventilator	Nos	14.00	120.00	1680.00

b) Ventilator- 1	Nos	2.00	500.00	1000.00
17. Distemping two coat to walls with distemper of approved shade on new work to give an even shade including cost of Distemping	One Sqmt	330.62	61.70	20399.00
18. Providing and applying paint over external plastered surfaces with 2 coats of whether seal coat of approved quality and shade, using the required quantity of paint as	One Sqmt	139.87	114.80	16057.00
19. Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips with all cost conveyancy Royalty etc. complete.	One cum	0.19	6011.50	1142.00
20. 10cm thick dry brick Khoa well watered & rammed to receive A.S. flooring including all cost etc. complete.	One Sqmt	0.40	222.10	89.00
21. 6mm thick cement plaster in cm (1:4) as ceiling Plaster with all cost conveyancy Royalty etc. complete.	One Sqmt	75.42	143.00	10785.00
22. 20mm thick c.p. in cm (1:4) on roof slab for slab grading	One Sqmt	100.20	290.20	29078.00
		<b>Grand</b>	<b>Total Rs</b>	<b>1108645.00</b>


**(Rupees Eleven lakhs eight thousand six hundred forty five )only**

Tender schedule for the project:-Construction AWC Building at Ghodabuda under Karadangi G.P under OMBADC under Karadangi G.P. Telkoi Block is approved for Rs. 11,08,645.00/- (Rupees Eleven lakhs eight thousand six hundred forty five )only with 22(Twenty two) items only.

G.S.T cost is 12%(CGST6%+SGST%) & with Labour welfare cess 1% will be added at the time of of agreement.

  
Asst. Executive Engineer  
Telkoi

  
Block Development Officer  
Telkoi

  
Executive Engineer  
DRDA,Keonjhar

My /Our quoted rate is ----- % Excess/Less/Equal  
to the corresponding estimate rate  
(Write both in words and Figures)

**NOTES:-**

1. The Contractor should not write anything except quoting of percentage, excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned, the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only. If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.

## APPROVED TENDER SCHEDULE

Name of the work: -Construction AWC Building at Kamalabani under Karadangi G.P under OMBADC		Amount put to tender:Rs 11,08,645/-			
		Class of contractor: D&C			
		Cost of Tender Paper : Rs.6,000/-			
		Earnest money Deposit 1% :Rs.11,086.00			
		Time of Completion: 04months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	40.96	180.00	7373.00
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	43.48	454.20	19749.00
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	12.74	3860.90	49188.00
4	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	10.82	4116.45	44540.00
5	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	36.77	4149.45	152575.00

6	Reinforcement cement concrete M - 20 grade with 20mm nominal size down graded nominal size aggregate mechanically mixed and Vibrated in foundation and bed protection of specification for road and Bridge works & direction of the Eng. In Charge.				
	a) Column Base	One cum	8.23	5099.90	41972.00
	b) Plinth bend	One cum	4.16	5440.80	22634.00
	c) Lintel Band	One cum	2.51	8533.60	21419.00
	d) Chajja	One Sqmt	16.32	775.20	12651.00
	e) Column & Roof beam	One cum	6.93	11993.80	83117.00
	f) Slab & Chajja	One cum	10.82	9073.80	98179.00
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specifaicaton as directed by the engineering-in-charge.	Qtl	34.03	6471.40	220222.00
8	25mm thick A.S. flooring in Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips including punning with all cost conveyancy Royalty etc.	One Sqmt	2.18	300.40	655.00
9	Fixing tiles in floors, treads and landings on 25mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade	One Sqmt	76.09	931.30	70863.00
10	Fixing tiles in dados, skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles	One Sqmt	37.67	990.10	37297.00
11	16mm(5/8") thick cement plaster (1:6)in finished smooth to inside rough surface of 10" thick brick walls after racking out the joints including watering and curing with cost,	One Sqmt	239.36	191.10	45742.00
12	12mm(1/2") thick cement plaster (1:6)in finished smooth to outside smooth surface of brick walls afrer racking out joints including watering and curing etc.complete with	One Sqmt	139.87	135.10	18896.00
13	12mm thick cement plaster in cm (1:4) including cement punning and skirting with all cost conveyancy Royalty etc. complete.	One Sqmt	12.38	153.60	1902.00
14	Supplying Fitting & fixing of M.S shutter including cost of all materials etc. complete as per the direction of Engineer in Charge.	One Kg	940.35	75.00	70526.00
15	Painting two coats in all Doors and windows (Two coats with paints of approved shade and base coat with primer) to	One Sqmt	68.37	130.40	8915.00
16	Provision for fitting and fixing and cost of Ventilator etc. complete.				
	a) Ventilator	Nos	14.00	120.00	1680.00

	b) Ventilator- 1	Nos	2.00	500.00	1000.00
17	Distempering two coat to walls with distemper of approved shade on new work to give an even shade including cost of Distempering	One Sqmt	330.62	61.70	20399.00
18	Providing and applying paint over external plastered surfaces with 2 coats of whether seal coat of approved quality and shade, using the required quantity of paint as	One Sqmt	139.87	114.80	16057.00
19	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips with all cost conveyancy Royalty etc. complete.	One cum	0.19	6011.50	1142.00
20	10cm thick dry brick Khoa well watered & rammed to receive A.S. flooring including all cost etc. complete.	One Sqmt	0.40	222.10	89.00
21	6mm thick cement plaster in cm (1:4) as ceiling Plaster with all cost conveyancy Royalty etc. complete.	One Sqmt	75.42	143.00	10785.00
22	20mm thick c.p. in cm (1:4) on roof slab for slab grading	One Sqmt	100.20	290.20	29078.00
			Grand	Total Rs	1108645.00

**(Rupees Eleven lakhs eight thousand six hundred forty five )only**

Tender schedule for the project:-Construction AWC Building at Kamalabani under Karadangi G.P under OMBADC , Telkoi Block is approved for Rs. 11,08,645.00/-(Rupees Eleven lakhs eight thousand six hundred forty five )only with 22(Twenty two) items only.

G.S.T cost is 12%(CGST6%+SGST%) & with Labour welfare cess 1% will be added at the time of of agreement.

*(Signature)*  
Asst. Executive Engineer  
Telkoi

*(Signature)*  
Block Development Officer  
Telkoi

*(Signature)*  
Executive Engineer  
DRDA,Keonjhar

My /Our quoted rate is ----- % Excess/Less/Equal  
to the corresponding estimate rate  
(Write both in words and Figures)

**NOTES:-**

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.

## APPROVED TENDER SCHEDULE

Name of the work: -Construction AWC Building at Nuagarh under Deuladiha G.P under OMBADC		Amount put to tender:Rs 11,08,645/-			
		Class of contractor: D&C			
		Cost of Tender Paper : Rs.6,000/-			
		Earnest money Deposit 1% :Rs.11,086.00			
		Time of Completion: 04months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering,shorring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	40.96	180.00	7373.00
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	43.48	454.20	19749.00
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	12.74	3860.90	49188.00
4	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	10.82	4116.45	44540.00
5	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	36.77	4149.45	152575.00


6	Reinforcement cement concrete M - 20 grade with 20mm nominal size down graded nominal size aggregate mechanically mixed and Vibrated in foundation and bed protection of specification for road and Bridge works & direction of the Eng. In Charge.				
	a) Column Base	One cum	8.23	5099.90	41972.00
	b) Plinth bend	One cum	4.16	5440.80	22634.00
	c) Lintel Band	One cum	2.51	8533.60	21419.00
	d) Chajja	One Sqmt	16.32	775.20	12651.00
	e) Column & Roof beam	One cum	6.93	11993.80	83117.00
	f) Slab & Chajja	One cum	10.82	9073.80	98179.00
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specificaion as directed by the engineering-in-charge.	Qtl	34.03	6471.40	220222.00
8	25mm thick A.S. flooring in Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips including punning with all cost conveyancy Royalty etc.	One Sqmt	2.18	300.40	655.00
9	Fixing tiles in floors, treads and landings on 25mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade	One Sqmt	76.09	931.30	70863.00
10	Fixing tiles in dados, skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles	One Sqmt	37.67	990.10	37297.00
11	16mm(5/8") thick cement plaster (1:6)in finished smooth to inside rough surface of 10" thick brick walls after racking out the joints including watering and curing with cost,	One Sqmt	239.36	191.10	45742.00
12	12mm(1/2") thick cement plaster (1:6)in finished smooth to outside smooth surface of brick walls afrer racking out joints including watering and curing etc.complete with	One Sqmt	139.87	135.10	18896.00
13	12mm thick cement plaster in cm (1:4) including cement punning and skirting with all cost conveyancy Royalty etc. complete.	One Sqmt	12.38	153.60	1902.00
14	Supplying Fitting & fixing of M.S shutter including cost of all materials etc. complete as per the direction of Engineer in Charge.	One Kg	940.35	75.00	70526.00
15	Painting two coats in all Doors and windows (Two coats with paints of approved shade and base coat with primer) to	One Sqmt	68.37	130.40	8915.00
16	Provision for fitting and fixing and cost of Ventilator etc. complete.				
	a) Ventilator	Nos	14.00	120.00	1680.00
	b) Ventilator- 1	Nos	2.00	500.00	1000.00

17	Distemping two coat to walls with distemper of approved shade on new work to give an even shade including cost of Distemping	One Sqmt	330.62	61.70	20399.00
18	Providing and applying paint over external plastered surfaces with 2 coats of whether seal coat of approved quality and shade, using the required quantity of paint as	One Sqmt	139.87	114.80	16057.00
19	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips with all cost conveyancy Royalty etc. complete.	One cum	0.19	6011.50	1142.00
20	10cm thick dry brick Khoa well watered & rammed to receive A.S. flooring including all cost etc. complete.	One Sqmt	0.40	222.10	89.00
21	6mm thick cement plaster in cm (1:4) as ceilling Plaster with all cost conveyancy Royalty etc. complete.	One Sqmt	75.42	143.00	10785.00
22	20mm thick c.p. in cm (1:4) on roof slab for slab grading	One Sqmt	100.20	290.20	29078.00
			Grand	Total Rs	1108645.00


(Rupees Eleven lakhs eight thousand six hundred forty five )only

Tender schedule for the project:-Construction AWC Building at Nuagarh under Deuladiha G.P under OMBADC ,Telkoi Block is approved for Rs. 11,08,645.00/- (Rupees Eleven lakhs eight thousand six hundred forty five )only with 22(Twenty two) items only.

G.S.T cost is 12%(CGST6%+SGST%) & with Labour welfare cess 1% will be added at the time of of agreement.

  
Asst. Executive Engineer  
Telkoi

  
Block Development Officer  
Telkoi

  
Executive Engineer  
DRDA,Keonjhar

My /Our quoted rate is \_\_\_\_\_ % Excess/Less/Equal  
to the corresponding estimate rate  
(Write both in words and Figures)

NOTES:-

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.

## APPROVED TENDER SCHEDULE

Name of the work: -Construction AWC Building at Deuladiha-III under Deuladiha G.P under OMBADC		Amount put to tender:Rs 11,08,645/-			
		Class of contractor: D&C			
		Cost of Tender Paper : Rs.6,000/-			
		Earnest money Deposit 1% :Rs.11,086.00			
		Time of Completion: 04months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	40.96	180.00	7373.00
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	43.48	454.20	19749.00
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	12.74	3860.90	49188.00
4	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	10.82	4116.45	44540.00
5	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	36.77	4149.45	152575.00

	Reinforcement cement concrete M - 20 grade with 20mm nominal size down graded nominal size aggregate mechanically mixed and Vibrated in foundation and bed protection of specification for road and Bridge works & direction of the Eng. In Charge.				
	a) Column Base	One cum	8.23	5099.90	41972.00
	b) Plinth bend	One cum	4.16	5440.80	22634.00
	c) Lintel Band	One cum	2.51	8533.60	21419.00
	d) Chajja	One Sqmt	16.32	775.20	12651.00
	e) Column & Roof beam	One cum	6.93	11993.80	83117.00
	f) Slab & Chajja	One cum	10.82	9073.80	98179.00
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specificaion as directed by the engineering-in-charge.	Qtl	34.03	6471.40	220222.00
8	25mm thick A.S. flooring in Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips including punning with all cost conveyancy Royalty etc.	One Sqmt	2.18	300.40	655.00
9	Fixing tiles in floors, treads and landings on 25mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade	One Sqmt	76.09	931.30	70863.00
10	Fixing tiles in dados, skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles	One Sqmt	37.67	990.10	37297.00
11	16mm(5/8") thick cement plaster (1:6)in finished smooth to inside rough surface of 10" thick brick walls after racking out the joints including watering and curing with cost,	One Sqmt	239.36	191.10	45742.00
12	12mm(1/2") thick cement plaster (1:6)in finished smooth to outside smooth surface of brick walls afrer racking out joints including watering and curing etc.complete with	One Sqmt	139.87	135.10	18896.00
13	12mm thick cement plaster in cm (1:4) including cement punning and skirting with all cost conveyancy Royalty etc. complete.	One Sqmt	12.38	153.60	1902.00
14	Supplying Fitting & fixing of M.S shutter including cost of all materials etc. complete as per the direction of Engineer in Charge.	One Kg	940.35	75.00	70526.00
15	Painting two coats in all Doors and windows (Two coats with paints of approved shade and base coat with primer) to	One Sqmt	68.37	130.40	8915.00
16	Provision for fitting and fixing and cost of Ventilator etc. complete.				
	a) Ventilator	Nos	14.00	120.00	1680.00
	b) Ventilator- 1	Nos	2.00	500.00	1000.00

	Distempering two coat to walls with distemper of approved shade on new work to give an even shade including cost of Distempering	One Sqmt	330.62	61.70	20399.00
18	Providing and applying paint over external plastered surfaces with 2 coats of whether seal coat of approved quality and shade, using the required quantity of paint as	One Sqmt	139.87	114.80	16057.00
19	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips with all cost conveyancy Royalty etc. complete.	One cum	0.19	6011.50	1142.00
20	10cm thick dry brick Khoa well watered & rammed to receive A.S. flooring including all cost etc. complete.	One Sqmt	0.40	222.10	89.00
21	6mm thick cement plaster in cm (1:4) as ceiling Plaster with all cost conveyancy Royalty etc. complete.	One Sqmt	75.42	143.00	10785.00
22	20mm thick c.p. in cm (1:4) on roof slab for slab grading	One Sqmt	100.20	290.20	29078.00
			<b>Grand</b>	<b>Total Rs</b>	<b>1108645.00</b>


**(Rupees Eleven lakhs eight thousand six hundred forty five )only**

Tender schedule for the project:-Construction AWC Building at Deuladiha-III under Deuladiha G.P under OMBADC , Telkoi Block is approved for Rs. 11,08,645.00/-(Rupees Eleven lakhs eight thousand six hundred forty five )only with 22(Twenty two) items only.

G.S.T cost is 12%(CGST6%+SGST%) & with Labour welfare cess 1% will be added at the time of of agreement.

  
Asst. Executive Engineer  
Telkoi

  
Block Development Officer  
Telkoi

  
Executive Engineer  
DRDA,Keonjhar

My /Our quoted rate is \_\_\_\_\_ % Excess/Less/Equal  
to the corresponding estimate rate  
(Write both in words and Figures)

**NOTES:-**

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.

## APPROVED TENDER SCHEDULE

Name of the work: -Construction AWC Building at Kadapada under Deuladiha G.P under OMBADC		Amount put to tender:Rs 11,08,645/-			
		Class of contractor: D&C			
		Cost of Tender Paper : Rs.6,000/-			
		Earnest money Deposit 1% :Rs.11,086.00			
		Time of Completion: 04months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	40.96	180.00	7373.00
2	Supplying and Filling in foundation and plinth with sand, well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials, cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	43.48	454.20	19749.00
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	12.74	3860.90	49188.00
4	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	10.82	4116.45	44540.00
5	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	36.77	4149.45	152575.00


6	Reinforcement cement concrete M - 20 grade with 20mm nominal size down graded nominal size aggregate mechanically mixed and Vibrated in foundation and bed protection of specification for road and Bridge works & direction of the Eng. In Charge.				
	a) Column Base	One cum	8.23	5099.90	41972.00
	b) Plinth bend	One cum	4.16	5440.80	22634.00
	c) Lintel Band	One cum	2.51	8533.60	21419.00
	d) Chajja	One Sqmt	16.32	775.20	12651.00
	e) Column & Roof beam	One cum	6.93	11993.80	83117.00
	f) Slab & Chajja	One cum	10.82	9073.80	98179.00
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specifaicon as directed by the engineering-in-charge.	Qtl	34.03	6471.40	220222.00
8	25mm thick A.S. flooring in Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips including punning with all cost conveyancy Royalty etc.	One Sqmt	2.18	300.40	655.00
9	Fixing tiles in floors, treads and landings on 25mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade	One Sqmt	76.09	931.30	70863.00
10	Fixing tiles in dados, skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles	One Sqmt	37.67	990.10	37297.00
11	16mm(5/8") thick cement plaster (1:6)in finished smooth to inside rough surface of 10" thick brick walls after racking out the joints including watering and curing with cost,	One Sqmt	239.36	191.10	45742.00
12	12mm(1/2") thick cement plaster (1:6)in finished smooth to outside smooth surface of brick walls afrer racking out joints including watering and curing etc.complete with	One Sqmt	139.87	135.10	18896.00
13	12mm thick cement plaster in cm (1:4) including cement punning and skirting with all cost conveyancy Royalty etc. complete.	One Sqmt	12.38	153.60	1902.00
14	Supplying Fitting & fixing of M.S shutter including cost of all materials etc. complete as per the direction of Engineer in Charge.	One Kg	940.35	75.00	70526.00
15	Painting two coats in all Doors and windows (Two coats with paints of approved shade and base coat with primer) to	One Sqmt	68.37	130.40	8915.00
16	Provision for fitting and fixing and cost of Ventilator etc. complete.				
	a) Ventilator	Nos	14.00	120.00	1680.00


	b) Ventilator- 1	Nos	2.00	500.00	1000.00
17	Distemping two coat to walls with distemper of approved shade on new work to give an even shade including cost of Distemping	One Sqmt	330.62	61.70	20399.00
18	Providing and applying paint over external plastered surfaces with 2 coats of whether seal coat of approved quality and shade, using the required quantity of paint as	One Sqmt	139.87	114.80	16057.00
19	Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips with all cost conveyancy Royalty etc. complete.	One cum	0.19	6011.50	1142.00
20	10cm thick dry brick Khoa well watered & rammed to receive A.S. flooring including all cost etc. complete.	One Sqmt	0.40	222.10	89.00
21	6mm thick cement plaster in cm (1:4) as ceiling Plaster with all cost conveyancy Royalty etc. complete.	One Sqmt	75.42	143.00	10785.00
22	20mmm thick c.p. in cm (1:4)on roof slab for slab grading	One Sqmt	100.20	290.20	29078.00
			Grand	Total Rs	1108645.00


**(Rupees Eleven lakhs eight thousand six hundred forty five )only**

Tender schedule for the project:-Construction AWC Building at Kadapada under Deuladiha G.P under OMBADC , Telkoi Block is approved for Rs. 11,08,645.00/-(Rupees Eleven lakhs eight thousand six hundred forty five )only with 22(Twenty two) items only.

G.S.T cost is 12%(CGST6%+SGST%) & with Labour welfare cess 1% will be added at the time of of agreement.

  
Asst. Executive Engineer  
Telkoi

  
Block Development Officer  
Telkoi

  
Executive Engineer  
DRDA,Keonjhar

My /Our quoted rate is ----- % Excess/Less/Equal  
to the corresponding estimate rate  
(Write both in words and Figures)

**NOTES:-**

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.