

APPROVED TENDER SCHEDULE

Name of the work: -Upgradation of Infrastructure in Elementary School at Balijodi U.G.U.P School, Purujoda G.P

Amount put to tender: Rs. 13,89,236/-

Class of contractor: D&C

Cost of Tender Paper : Rs.6,000/-

Time of Completion: 04months

Sl No	ITEM OF WORK	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and breaking clods etc. complete.	148.50	One cum	Rs. 182.80	Rs. 27,146.00
2	Sand filling in foundation and plinth with well watered and rammed etc. complete.	29.70	One cum	Rs. 322.80	Rs. 9,587.00
3	Cement concrete (1:4:8) with 4cm size hard granite metal of approved quality and approved quarry in foundation including hoisting laying concrete with cost conveyance of materials including watering, curing, royalty all T & P required for the work etc. complete as per direction of the Er. in charge.	29.70	One cum	Rs. 3,904.30	Rs. 1,15,958.00
4	Flyash Bricks (25cm x 12cm x 8cm) masonry in cm (1:6) for Superstructure in foundation and plinth with all cost conveyancy Royalty etc. complete.				
	a) In foundation	102.96	One cum	Rs. 4,172.20	Rs. 4,29,570.00
	b) In Superstructure	94.47	One cum	Rs. 4,205.20	Rs. 3,97,265.00
5	25mm thick D.P.C. with Cement concrete in cm (1:2:4) using 12mm size h.g.c.b. chips with all cost etc. complete.	105.60	One Sqmt	Rs. 266.76	Rs. 28,170.00
6	16mm(5/8") thick cement plaster (1:6)in finished smooth to inside rough surface of 10" thick brick walls after racking out the joints including watering and curing with cost conveyance royalty all tax of all materials and cost	467.19	One Sqmt	Rs. 190.90	Rs. 89,187.00
7	12mm(1/2") thick cement plaster (1:6)in finished smooth to outside smooth surface of brick walls after racking out joints including watering and curing etc.complete with cost conveyance royalties all taxes and cost of all	567.51	One Sqmt	Rs. 134.80	Rs. 76,500.00
8	Painting one coats with wall cement primer(water bound) over new plastered surface	1245.90	One Sqmt	Rs. 57.55	Rs. 71,702.00
9	Providing and applying paint over external plastered surfaces with 2 coats of whether seal coat of approved quality and shade, using the required quantity of paint as specified by the manufacturer to give an even shade	1245.90	One Sqmt	Rs. 115.70	Rs. 1,44,151.00
	Total				Rs. 13,89,236.00

(Rupees Thirteen lakhs Eighty Nine thousand Two hundred Thirty Six) only

Tender schedule for the project:-Upgradation of Infrastructure in Elementary School at Balijodi U.G.U.P School,Purujoda G.P under OMBADC under ,Telkoi Block is approved for Rs. 13,89,236.00(Rupees Thirteen lakhs Eighty Nine thousand Two hundred Thirty Six) only with 9(Nine) items only.

G.S.T cost is 12%(CGST6%+SGST%) & with Labour welfare cess 1% will be added at the time of of agreement.

Asst. Executive Engineer
Telkoi

Block Development Officer
Telkoi

Executive Engineer
DRDA,Keonjhar

My /Our quoted rate is _____
to the corresponding estimate rate
(Write both in words and Figures)

% Excess/Less/Equal

NOTES:-

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor
with address.