

Approved Tender Schedule


Name of the Work : Construction of Boundary Wall At Elementary School Name of the School: UDAYAGIRI UGUPS TELKOI G.P. : DEOULADIHA Block : Telkoi		Amount put to Tender :		1002642/-	
		Class of Contractor		C&D	
		Cost of Tender Papeer		6000/-	
		Time of completion		4 Months	
		Qty.	Unit	Rate	Amount
1	Earth work excavation in hard soil or gravel within 50 mtr initial lead & 1.5 mtr initial lift including rough dressing the trench etc complete as per the direction of the Engineer in charge.	= 105.34	cum @ Rs	182.80	Rs 19256.15
2	Filling foundation & plinth with coarse sand well watered and rammed as per the direction of Engineer in charge etc complete as per direction of Engineer in charge.	= 16.33	cum @ Rs	561.57	Rs 9170.44
3	P.C.C (1:3:6) in foundation and plinth using 40mm H.G.H.B metal including cost, conveyance, royalty etc complete as per the direction of Engineer incharge.	16.33	cum @ Rs	4683.34	Rs 76478.94
4	R.C.C M-20 using 20mm H.G.C.B chips including centering & shuttering cost, conveyance, royalty etc complete as per the direction of Engineer incharge.				
a	Footing				
	a+b =	20.80	cum @ Rs	5224.35	Rs 108666.48
b	Plinth beam				
5	Straightening, cutting, bending, binding of M.S rod or Tor steel, tying up the grills and placing in position including cost of binding wire with all cost conveyance, taxes etc completed in all respect as per the direction of Engineer in charge.	Total		16.64	qntl @ Rs 7566.82 Rs 125911.88
6	Fly ash brick masonry with cement mortar (1:6) in foundation and plinth including cost, conveyance, royalty, taxes of all materials, all labour T & P sundries etc complete as per direction of Engineer in charge.	26.25	cum @ Rs	4139.19	Rs 108653.74
7	Brick work with fly ash brick with cement mortar (1:6) in superstructure including cost, conveyance, royalty, taxes of all materials, all labour T & P sundries etc complete as per direction of Engineer in charge.	72.30	cum @ Rs	4177.14	Rs 302007.22

9	Finishing walls with weather coat of approved shade on new work 2 coats to give an even shade including cost of paint, including all cost, taxes etc complete as per direction of Engineer in charge.	TOTAL	735.00	sqm @ Rs	72.85	Rs	53544.75
10	Supplying, fitting and fixing MS Grills, Doors and Windows made out of structural steel flat etc as per direction of Engineer in charge.	TOTAL	394.20	Kg @ Rs	132.29	Rs	52148.72
11	Painting two coat with any approved on new wood work / iron work cost, of materials and labour, T&P etc completed as per direction of Engineer in charge.	TOTAL	14.78	sqm @ Rs	138.36	Rs	2044.96

TOTAL Rs 1002641.53
Total Money Put to tender in Rs 1002641.53
Say Rs 1002642/-

Tender schedule for the project construction of Boundary wall at Udayagiri UGP School under Deouladiha G.P is approved for Rs.1002642.00 (Rupees Ten Lakh two thousand six hundred forty two) only excluding GST 12% with provisional items only and GST12% will be added at the time of Agreement


Asistant EX. Engineer
Telkoi Block, Keonjhar


Block Development Officer,
Telkoi block, Keonjhar


Addl. PD (Tech)
DRDA, Keonjhar

My/Our quoted rate is _____ % Excess/Less/Equal to the corresponding estimate rate (write both in words and figures)

NOTES:-

1. The Contractor should not write any thing except quoting percentage, excess/less/equal to the amount to tender and in any case any thing else regarding tender rate is mentioned, the Tender is liable for rejection.
2. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
3. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
4. The Contractor should write percentage excess of less up to two decimal point only. If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor
With Address