

BILL OF QUANTITY (BOQ)

NAME OF THE WORK: -CONSTRUCTION OF TOILET & BOUNDRY WALL AT JHARABEDA U G U P SCHOOL.

Amount put to Tender : Rs. 13,41,708.00
 Class of Contractor : D' & C' class only
 Cost of Tender Paper : Rs.6000.00
 Date required for completion : 4(four) calender Month

Sl. no.	Item of Work	Quantity	Unit	Rate	Amount
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads,lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth . as per direction of Engineer-in-charge	136.94	cum	203.30	27839.00
2	Supplying, filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty and all taxces of materials cost of all labour with T&P etc. complete. as per direction of Engineer-in-charge	29.23	cum	414.91	12127.00
3	C.C (1:3:6) using 40 mm hg metal in foundation with 40 mm size hand Broken metal including cost, conveyance, royalty etc complete as per direction of Engineer-in-charge	20.83	Cum	4458.98	92895.00
4	Fly ash.Brick masonry in cement mortar (1;6) in foundation and plinth including cost ,conveyance etcas per direction of Engineer-in-charge .	37.65	Cum	4293.30	161629.00
5	Fly ash.Brick masonry in cement mortar (1;6) in Superstructure including cost ,conveyance etcas per direction of Engineer-in-charge .	90.18	Cum	4326.30	390157.00
6	RCC M20 grade with 20mm and down graded black hard granite crusher broken chips including hosting and laying etc complete as per direction of Engineer-in-charge.	27.09	Cum	4833.77	130946.00
7	Rigid & smooth centring and shuttering				
a	Column base	51.08	Sqm	102.10	5215.00
b	Plinth band	58.20	Sqm	102.10	5942.00
c	Column	66.00	Sqm	724.09	47790.00
d	Roof slab	18.20	Sqm	425.21	7739.00
8	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification as per the direction of Engineer -in -charge.	21.85	Qntl	6481.80	141660.00

9	Supplying fitting & fixing of M.S.Grill for Window including all cost of material & Laour charges as per direction of Engineer-in-	481.50	Kg	80.00	38520.00
10	6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chiping including cost ,conveyance etc as per direction of Engineer-in-charge	36.50	Sqm	154.70	5647.00
11	12 mm thick cement plaster in C.M.(1:6) in external surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	39.00	Sqm	141.20	5507.00
12	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	853.80	Sqm	200.10	170845.00
13	painting two coats of enamel paint over one coat of primer to doors and windows including all cost of paint and primer and labour charges etc complete as per direction	25.32	Sqm	167.20	4233.00
14	Distemping 2-coat to walls with distemper of approved shade on old work to give on even shade excluding cost of distemper.	59.60	Sqm	61.07	3640.00
15	Finishing out side wall surface with Weather Coat (I.S.I) two coats with any approved shade overhead coat of priming including cost of all materials and labour (T&P) etc. complete as per the direction of Engineer-in-	853.80	Sqm	73.57	62817.00
16	Supplying fitting & fixing of tiles in floors, treads or steps and landing on 25 mm thick bed of C.M(1:1) (1cement :1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing	9.99	Sqm	991.14	9898.00
17	Fixing the tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials labour, T&p etc completeas per direction of	15.89	Sqm	1048.88	16662.00

Total

1341708.00

TOTAL 17 (SEVENTEEN) NOS ITEM

Assistant Executive Engineer
Ghatgaon Block

Block Development Officer
Ghatgaon Block

Approved for 17 (Seventeen) items only

Executive Engineer
DRDA Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The Tenderer should quote the percentage up to two decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer
DRDA Keonjhar**

**Block Development Officer
Ghatgaon Block**