

TENDER SCHEDULE

20

NAME OF THE WORK: - CONSTRUCTION OF ADDITIONAL CLASS ROOM AND TOILET AT GHATAGAON GOVT U.P SCHOOL

Amount put to Tender : 838429.00
 Class of Contractor : 'C' & 'D' class only
 Cost of Tender Paper : Rs. ~~8000.00~~ 4000/-
 Date required for completion : 4(four) calender Month

Sl. no.	Item of Work	Quantity	Unit	Rate	Amount
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth . as per direction of Engineer-in-charge	58.31	cum	203.30	11853.00
2	Supplying, filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty and all taxces of materials cost of all labour with T&P etc. complete. as per direction of Engineer-in-charge	55.77	cum	414.91	23140.00
3	C.C (1:3:6) using 40 mm hg metal in foundation with 40 mm size hand Broken metal including cost, conveyance, royalty etc complete as per direction of Engineer-in-charge	12.53		4466.56	55947.00
4	Fly ash.Brick masonry in cement mortar (1:6) in F & P including cost ,conveyance etcas per direction of Engineer-in-charge .	18.04		4191.70	75618.00
5	Fly ash.Brick masonry in cement mortar (1:6) in Superstructure including cost ,conveyance etcas per direction of Engineer-in-charge .	24.90		4224.70	105195.00
6	RCC M20 grade with 20mm and down graded black hard granite crusher broken chips including hosting and laying as per direction of Engineer-in-charge	23.84	Cum	4789.32	114177.00
7	Rigid & smooth centring and shuttering				
	(A) Column foundation & Plinth	36.40	Sqm	102.10	3716.00
	(B) Column & beam	60.18	Sqm	724.09	43576.00
	(C) Lintel	17.81	Sqm	263.57	4693.00
	(D) Chajja & Roof slab	75.89	Sqm	425.21	32269.00

8	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as requires as per direction of Engineer-in-charge	21.45	Qtl	6460.20	138571.00
9	Supplying fitting & fixing of M.S.Grill for Window including all cost of material & Laour charges as per direction of Engineer-in-charge.	423.50	KG	80.00	33880.00
10	6mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials as	99.40	Sqm	153.70	15278.00
11	12 mm thick cement plaster in C.M.(1:6) in external surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	139.60	Sqm	139.80	19516.00
12	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	146.80	Sqm	198.40	29125.00
13	Supplying fitting & fixing vetrified tiled in floors of size 600mmx600mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thinkness of 10mm & filling joints of with Epoxy grout of approved quility including cost of all material labour & T & P ect comp as per direction of Engineer in Charges.	51.10		1132.70	57881.00
14	Fixing the tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement Slurry as per the direction of Engineer-in-Charge.	7.34		994.28	7298.00
15	Supplying fitting & fixing of tiles in floors, treads or steps and landing on 25 mm thick bed of C.M(1:1) (1cement :1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing as per the direction	9.99		762.33	7616.00
16	Fixing the tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement Slurry as per the direction of Engineer-in-Charge.	15.89		738.97	11742.00
17	Painting 2 coat with approved paint over 1 coat of priming on new Door & Window work as per the direction of Engineer-in-Charge.	34.07		167.20	5697.00
18	One coat of cement washing over plastering surfaces	271.30		14.32	3885.00


19	Distemping two coat to wall Distemper of approved shade on new work to give on even shed including all cost etc comp.	223.00		61.07	13619.00
20	Finishing wall surface with weather coat including all cost	139.60		73.57	10270.00
21	20 mm thick grading plaster in C:M (1:4) over roof slab etc. complete as per direction of Engineer-in-charge.	63.03	Sqm	220.00	13867.00
Total					838429.00

TOTAL 21 (Twenty one) NOS ITEM ONLY

Approved for 21 (Twenty one) items only


 Assistant E. Engineer
 Ghatgaon Block


 Executive Engineer
 DRDA Keonjhar


 Block Development Officer
 Ghatagaon Block

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

Assistant E. Engineer
 Ghatgaon Block

Executive Engineer
 DRDA Keonjhar

Block Development
 Ghatagaon Block