

BILL OF QUANTITY (BOQ)

46

NAME OF THE WORK: - CONSTRUCTION OF ADDITIONAL CLASS ROOM ,TOILET,DRINKING WATER FACILITY AND BOUNDRY WALL AT AMBIKA .HIGH SCHOOL,PANDAPADA.

Amount put to Tender : Rs. 22,27,803.00
 Class of Contractor : C' & B' class only
 Cost of Tender Paper : Rs.6000.00
 Date required for completion : 4(four) calender Month

Sl. no.	Item of Work	Quantity	Unit	Rate	Amount
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth . as per direction of Engineer-in-charge	185.69	cum	203.30	37750.00
2	Supplying, filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty and all taxces of materials cost of all labour with T&P etc. complete. as per direction of Engineer-in-charge	101.81	cum	414.91	42244.00
3	Cement concrete(1:3:6) with 4cm size hard granite Hand broken metal including cost, conveyance & royalty and all taxces of materials cost of all labour with T&P etc. complete. as per direction of Engineer-in-charge	35.69	Cum	4458.98	159159.00
4	Fly ash.Brick masonry in cement mortar (1:6) in foundation and plinth including cost ,conveyance etcas per direction of Engineer-in-charge .	65.55	Cum	4293.30	281430.00
5	Fly ash.Brick masonry in cement mortar (1:6) in Superstructure including cost ,conveyance etcas per direction of Engineer-in-charge .	90.49	Cum	4326.30	391473.00
6	RCC M20 grade with 20mm and down graded black hard granite crusher broken chips including hosting and laying	54.33	Cum	4833.77	262612.00
7	Supplying, fitting and placing uncoated HYSD bar	50.04	Qntl	6481.80	324318.00
8	Rigid & smooth centring and shuttering				
a	Column base	69.14	Sqm	102.10	7059.00
b	Plinth band	67.20	Sqm	102.10	6861.00
c	Column	109.60	Sqm	724.09	79360.00
d	Beam	32.38	Sqm	724.09	23447.00
e	Lintel	23.44	Sqm	263.57	6177.00
f	Chajja	10.95	Sqm	425.21	4656.00
g	Roof slab	103.00	Sqm	425.21	43830.00

9	6 mm.thick cement plaster in C.M.(1:4) for ceiling plaster including deep chipping	149.10	Sqm	154.70	23066.00
10	12 mm thick cement plaster in C.M.(1:6) in external surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	153.20	Sqm	141.20	21632.00
11	Supplying fitting &fixing of M.S.Grill for Window including all cost of material & Laour charges as per direction of Engineer-in-charge.	901.50	Kg	80.00	72120.00
12	16 mm thick cement plaster in C.M.(1:6) in internal surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	495.10	Sqm	200.10	99070.00
13	Supplying, fitting and fixing vetrified tile in floors of size 600mm*600 mm of approved make with application of polymer modified cement based water resistant adhesive bed of required thickness of 10 mm and filling joints with Epoxy grout of approved quality including cost of all materials labour, T&p etc completeas per direction of Engineer-in-charge	96.63	Sqm	1345.93	130060.00
14	Fixing the tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost ,conveyance etc as per direction of Engineer-in-charge	6.60	Sqm	1306.89	8625.00
15	painting two coats of enamel paint over one coat of primer to doors and windows including all cost of paint and primer and labour charges etc complete as per direction of Engineer-in-charge	57.46	Sqm	167.20	9607.00
16	One coat of cement washing over Plastering surfaces including all cost of cement and labour charges etc complete as per direction of Engineer-in-charge	351.40	Sqm	14.46	5081.00
17	Priming 1 coat with primer with approved primer including cost of all materials labour, T&p etc completeas per direction of Engineer-in-charge	351.40	Sqm	59.67	20968.00
18	Wall painting two coat with plastic emulsion paint over a coat of priming including cost of all materials and labour etc. complete as per the direction of Engineer-in-Charge.	230.60		80.08	18468.00
19	Distempering 2-coat to walls with distemper of approved shade on old work to give on even shade excluding cost of distemper including cost of all materials labour, T&p etc completeas per direction of Engineer-in-charge	83.60		61.07	5105.00
20	Finishing out side wall surface with Weather Coat (I.S.I) two coats with any approved shade overhead coat of priming including cost of all materials and labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	1304.00	Sqm	73.57	95940.00

21	Supplying fitting & fixing of tiles in floors, treads or steps and landing on 25 mm thick bed of C.M(1:1) (1cement :1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing including cost of all materials labour, T&p etc completeas per direction of Engineer-in-charge	9.99		991.14	9898.00
22	Fixing the tiles in dados skirting risers of on 12 mm thick C.P. (1:3) jointed with neat cement Slurry including cost of all materials labour, T&p etc completeas per direction of Engineer-in-charge	15.89		1048.88	16662.00
23	20 mm. thick cement plaster in cement mortar (1:4) in grading plaster of roof slab including cost ,conveyance etc as per direction of Engineer-in-charge	95.03	Sqm	222.30	21125.00
Total					2227803.00

TOTAL 23 (Twenty three) NOS ITEM ONLY

[Signature]
29/04/2021
Assistant Executive Engineer
Ghatgaon Block

Approved for 23(Twenty three) items only
[Signature]
29/04/2021
Executive Engineer
DRDA Keonjhar

[Signature]
29-4-21
Block Development Officer
Ghatgaon Block

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

	in Figure	in words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The Tenderer should quote the percentage up to two decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

Executive Engineer
DRDA Keonjhar

Block Development Officer
Ghatgaon Block