

**Improvement of Road from Rugudi to Param sahi with box Bridge under Joda Block for the year 2020-21. TENDER SCHEDULE**

SL NO	ITEMS	UNIT	QUANTITY	RATE	AMOUNT
1	Earth in excavation of <b>foundation and trenches</b> in all kind of soil within 50m lead and 1.5 m lift including rough dressing and breaking colds to maximum 5 cm to 7 cm and laying in layers not exceeding 0.3 m in depth and as per specification complete.	Cum	146.77	187.81	<b>27564.87</b>
2	Supplying, <b>filling foundation &amp; plinth with sand</b> including watering, ramming, cost, conveyance, royalty, taxes of all materials and labour (T&P) etc. complete.	Cum	21.47	769.94	<b>16530.61</b>
3	<b>C.C. (1:3:6)</b> using 20mm size down graded h.g.c.b. metal including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	Cum	161.53	4782.57	<b>772528.53</b>
4	<b>R.C.C. M. 20</b> using 12 mm & down graded size b.h.g.c.b. chips including centering & shuttering, watering curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	Cum	40.55	8808.34	<b>276078.19</b>
5	Cutting, bending and binding of <b>M.S. rod and tor steel</b> from SAIL / RINL / TISCO including cutting, bending and tying the grills placing in position for R.C.C work with cost, conveyance, taxes of all materials & labour (T&P) etc. complete.	Qtl	84.95	6226.03	<b>528901.25</b>
6	Rigid smooth centring and shuttering for Rec works including false work and dismantling them after casting including cost of materials complete				
A	<b>slab</b>	sqm	43.65	512.13	<b>22354.47</b>
B	<b>foundation</b>	sqm	227.87	102.39	<b>23331.61</b>
C	<b>Column &amp; Beam</b>	sqm	119	877.63	<b>104437.97</b>
7	Earth work in hard soil within initial lead and lift etc. complete in	Cum	49.59	191.86	<b>9514.34</b>
<b>GRAND TOTAL RS.</b>					<b>1781241.84</b>

say RS 1781242

(Rupees seventeen lakh eighty one thousand two hundred forty two )only

Tender schedule for the project "Improvement of road from Rugudi to param sahi with box bridge in Laidapada gram panchayat under joda Block for RS 1781242.00 (Rupees seventeen lakh eighty one thousand two hundred forty two only) excluding GST 12% With 7 (seven) items only. GST 12% will be added at the time of Agreement

*Sum*  
20-11-20  
Asst. engineer  
Joda Block

*My*  
20/11/20  
Block Development Officer  
Joda Block

Executive Engineer  
DRDA Keonjhar

*20*  
05/06/2021  
Executive Engineer  
D.R.D.A., Kendujhar.