

**PANCHAYAT SAMITI: HARICHANDANPUR**  
**DETAILED TENDER CALL NOTICE (01/2018-19)**

**Terms and Conditions**

1. Sealed tenders in conformity with detailed tender call notice to be eventually drawn in from of the OPWD F-2 Agreement and will be received up to 5.00 P.M on 21.09.2021 by the Block Development Officer, Harichandnpur for the work: "....." at a tender value of Rs. .... from Government Registered Contractors of R&B / N.H / RW Wings of Class "D", "C", "B" and above and will be opened on 21-09-2021 at 11.00 A.M in presence of the tenderers or their authorized agents by the Block Development Officer, Harichandnpur .
2. The tenderers shall pledge and note that the work shall have to be completed within 4(Four) calendar month commencing from the date of issue of the written order. Tenders submitted through telephone or telegram will not be accepted.
3. Tenderers are required to pay earnest money at 1% (one percent) of the estimated amount as mentioned in the tender call notice i.e. Rs...../- in shape of draft or N.S.C. etc drawn in favour of Block Development Officer, Harichandnpur failing which the tenders will be summarily rejected. The earnest money shall be refunded to the unsuccessful tenderers on application without any interest after acceptance of the tenders on application and the same shall be retained in case of the successful tenderers and shall carry no interest.
4. Bidders submitting downloaded bid documents from official website of NIC, Keonjhar (<http://www.kendujhar.nic.in>) are requested to deposit the requisite non-refundable fees of Rs. 6000/- in shape of demand draft and prepared on or before last date of sale of tender paper and submit the same along with the bid keeping in a separate envelop marks cost of tender documents downloaded from internet.
5. The Block Development Officer, Harichandnpur reserves the right to reject any or all the tenders received without assigning any reason. The tenderer, whose tender is selected for acceptance shall within a period of seven days upon written intimation being given to his of acceptance of his tender mark an **Initially Security Deposit** equal to that of E.M.D. over and above the E.M.D. as stipulated in clause above and sign the agreement in the item rate contract from the P.W.D. The initially security deposit with the earnest money and the amount withheld from successive work bills according to the provisions of the item rate contract shall be retained as security deposit. Failure to execute required agreement and deposit of the security as above shall be entitled for forfeiture of the earnest money. No tender shall be finally accepted unless the required amount of security money is deposited. The written agreement to be entered into between the contractor and the Block Development Officer, Harichandnpur shall be the foundation of

Contractor

*Po...*  
*21.9.21*  
Block Development Officer, Harichandnpur .

the right of both parties and the contract shall be deemed to be incomplete until the agreement has first been signed by the contractor and then by the Block Development Officer, Harichandnpur in the manner as laid down in O.P.W.D. code. The Block shall accept the security deposit in shape of Bank Draft/NSC etc drawn in favour of Block Development Officer, Harichandnpur in any Nationalized Bank or Post Office as the case may be and payable at Harichandnpur. The document/receipt shall be furnished to the Block Development Officer, Harichandnpur. Exemption will be allowed to Govt. Agencies or Engineer Contractor or ST/SC contractors.

6. Both E.M.D. & I.S.D. shall be refunded to the successful tender after One year of completion of works provided that all defects if pointed out by Engineering Staff are rectified. However, the security deposit will be refunded only after audit, which is being deducted from time to time in all running as well as final bills.
7. The rate shall be quoted in words and figures. Otherwise, the tender will be liable for rejection. In case of discrepancy between unit's rates and totals, the unit / %rate mentioned in words shall prevail. The rates shall be quoted in % rate contract. The tender shall be written legibly and free from erasers, over writings, conversion of figures. Corrections, where unavoidable should be made by scoring out, initialing dating and re-writing.
8. The Contractor shall be responsible for payment of royalties or other charges for quarrying materials. All local taxes including state sales tax and income tax, ferry and tollage charges, other local taxes as well as GST as applicable shall be paid by the contractor. The same will be deducted from the work bill if the contractor fails to produce the valid receipt in support of the payment of the above said charges/taxes.
9. The tender shall not be considered unless the tenderer encloses true copies of PAN Card, GST Clearance Certificate and Labour License from the Competent Authority along with his tender and original certificate are to be produced before the Block Development Officer, Harichandnpur at the time of sale of tender papers.
10. If the contractor removes any materials or stock supplied to him from the site of the work with a view to dispose off the same dishonestly or for any other reason without written permission of the Block Development Officer, Harichandnpur he shall in addition to any other liabilities civil or criminal arising out of such removal, liable to pay a penalty equivalent to given times rate of the materials or stock so removed according to the stipulated rate and the penalty so imposed shall be recovered from the Contractor from any sum that may then be immediately due or any time there after becomes due to the contractor or from his security.
11. The contractor shall be fully liable to indemnify the Block payment of any compensation under workmen compensation Act VIII of 1923 on account of worker employed by him and the full amount of compensation paid shall be recovered from the contractor.
12. All Reinforced Cement Concrete work shall conform to the detailed Indian standard specification and shall be of proportion as per design with the specification mentioned in the tender schedule. All items of work shall be executed in accordance with the detailed standard specification of Orissa as followed by State PWD (Roads & Buildings).
13. Shuttering and centering shall be with seasoned Sal wood planks inner width of which shall be lined with suitable shuttering made of leak proof and tight including false work as directed or alternatively steel shuttering and centering shall be used.
14. For the purpose of the jurisdiction, in the event of dispute if any, the contractor shall be deemed to have been into within the Block Area and it is agreed that neither party to the agreement will be competent to bring any suit with regards to the matter covered by this contract at any place.

Contractor

*P. S. Choudhary*  
6.9.17  
Block Development Officer, Harichandnpur.

15. It is contractor's responsibility to correctly demarcate the lay-out and orientation of the building etc. and fixation of level pillars at site as directed by the Asst. Executive Engineer or Asst. Engineer or Junior Engineer Or Grama Panchayat Technical Assistant. All expenditure in connection with tools and plants, instrumental materials etc., shall be borne by the contractor.
16. After the work is finished, all surplus materials and debris shall be removed, preliminary work such as mixing plates etc., are to be dismantled and all the materials removed from the site and ground upto 50 mtrs. wide from the building etc. should be cleaned and dressed by the Contractor at his own cost. The net rate quoted should be inclusively of all these expenditures. He should return all the unused Departmental materials to the Department, otherwise the cost of such materials to be recovered from the final bill / Security Deposit.
17. The Contractor shall not interfere with the execution of water supply or electrical fittings and other works entrusted to any other agency by the Block at the time during the progress of work.
18. The Engineer-in-Charge of work shall have the right to reject the scaffolding and centering etc., made for the work and such structure if found defective shall be rectified at his own cost.
19. The contractor shall make water supply for drinking purpose at his own cost and make sanitary arrangements for his labour campus. The Contractors shall also arrange adequate lighting arrangement for night work, wherever at his own cost.
20. Boiling of water arising from any reason whatsoever from the foundation if necessary shall be borne by the Contractor. No payment shall be made for fixing arranges bench-marks. Level pillars profiles and benching and leveling the ground whenever required. The rates quoted shall be for finished items of work inclusive of all incidental items of work.
21. It should be understood clearly that on claim whatsoever shall be entertained as regards extra item of work or extra quantity of any item in excess of the estimate, written order must be obtained from the Block Development Officer, Harichandnpur for such extra item or quantity of work.
22. The Contractor must follow the fair wages clauses as introduced by the State Government.
23. Except as otherwise provided in the contract, all quotation and disputes relating to the meaning of the specification, designs, drawings and instructions contained there in and as to the quality of workmanship of materials used in the work, or as the any other question claim right, matter of any thing whatsoever of any arising out of the execution of failure to execute the same whether arising during the progress of the work or after the completion or abandonment thereof shall be referred to the tender committee. The decision of the Tender Committee shall be final, conclusive and binding on all parties to this contract.
24. The contractor shall arrange at his own cost, machinery equipments, necessary tools and plants as may be required for the efficient execution of the work and the rates quoted should be inclusive of the running and hire charges of such machinery tools and plants.
25. The Contractor shall submit to the Block office monthly return of the labour both skilled and un-skilled employed by him on the work. In case of non-payment, contractor is solely responsible in the labour court.
26. No part of the contract shall be sublet without written permission of the Block Development Officer, Harichandnpur or transfer is made by power of attorney authorizing other to receive payment on the contractor's behalf.
27. No tender documents shall be sold to the intending tenderers on the date of opening of the tender.

Contractor

*Pradon*  
*6.9.7*  
Block Development Officer, Harichandnpur .

28. If any further necessary information is required the Block Development Officer, Harichandnpur will furnish such information but it must be in order and according to instructions.
29. Only Ultratech / Konark brand Cement (OPC – 43 Grade) will be used and weight of each cement bag being taken as 50Kg. Further that, the M.S. or Tor Rod shall be used in the work as per SAIL / Tata Tiscon Brand.
30. No contractor shall be permitted to furnish his tender in his own manuscript papers or letter pads.
31. In the event of delay in the supply of detailed structural designs for unavoidable reasons, reasonable extension of time will be granted on application by the contractor, but no claim for monetary compensation therefore shall be entertained under any circumstances.
32. Before quoting his rates the tenderer can inspect the site of proposed work. He should inspect the quarries and satisfy himself about the quality, availability of materials, medical aids, labour, food stuff etc., and the rates shall be inclusive of all these items, in every case the materials must comply with the relevant specification. The sample of materials in sealed packets should be submitted along for approval in respect quality control test of Block Development Officer, Harichandnpur while executing the work.
33. The tenders containing extraneous conditions not covered by the tender call notice are liable for rejection.
34. The Contractor shall have to furnish certificate along with the tender to the effect that he is not related to any Block Office staff.
35. Tenders shall be deemed valid and hold good till 90 days from the date of obtaining of tenders and subject to extend depending upon the situation with written consent from the Agency Concerned so arise out of unavoidable circumstances if any.
36. After completion of the work, the contractor shall arrange at his own cost all requisites and equipments for testing for the work of building, roads and culverts etc., if found necessary and bear the entire cost of such test.
37. Before executing the work, contractor must erect one transparency board stating a brief note on the work to be executed and payment will be made out of estimated amount. No running bill will be paid unless transparency board is setup at the work site. Also, after the work is completed necessary correction is to be made if required over the transparency board by the executants as directed by Engineer-in-Charges.
38. The tenderer may at his option quote reasonable rate for each item of work carefully so that rates for one item should not be unworkably low and for other items too high. He should be able to substantiate his rates for any or all items through detailed analysis.
39. The Block Development Officer, Harichandnpur reserves the right to reject any or all tenders received without assigning any reason whatsoever. The Block Development Officer, Harichandnpur also reserves the right to accept any tender without assigning any reasons to other tenders.
40. The Engineer-in-Charge shall have the power to make any alternations in or addition to the original specification, drawing, designs and instructions that may appear to him to be necessary or advisable during the progress of the work in case of site condition if needed. The Contractor shall be bound to carry out the work in accordance with any instruction, which may be issued to the contractor after being signed by the Engineer-in-Charges and such alteration shall not invalidate the contract and any additional work which the contractor may be directed to do the manner, above, specification as part of the work shall be carried out by the contract on the same conditions in all respects on which he agreed to do the main work. The time for the completion of the work shall be extended in the proportion that the additional work bears to the original work shall be extended in the proportion that the additional work bears to the

Contractor

Block Development Officer, Harichandnpur  
6.9.24

original contract work and the certificate of the Engineer-in-Charge shall be conclusive as to such proportion, and if the additional work included any class of work shall be carried out at the rate entered in the sanctioned schedule of rates of the locality during the period when the work is being carried on and if such mentioned class of work is not entered in the schedule of rate of the district then the contractor shall within seven days of the date of his receipt of the order to carry out the work, inform the Engineer-in-Charges of the rate which it is his intention to charge for such class of work and if the Engineer-in-Charges of the rate which it is his intention to charge for such class of work and if the Engineer-in-Charges does not agree to this rate, he shall notice in writing be at liberty to cancel his order to carry out such class of work and arrange to carry it out in such manner as may be consider advisable provided always that the contractor shall commence work of any expenditure in regard thereof before the rates shall have been determined as lastly here in before mentioned when and in such case he shall only be entitled to the paid in respect of the determination of the rate as aforesaid according to such rate of determination of the rate as shall be fixed by the Engineer-in-Charge. In the event of dispute, decision of the Block Development Officer, Harichandnpur will be final.

41. Tenderers are required to go through each clause of the item rate contract from the Block Office carefully in addition to the clause herein before tendering.
42. As per Office Memorandum No. 14299 / Dtd. 03.10.2017 of Works Department, Additional Performance Security shall be obtained from the bidder when the bid amount is less than estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price / rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost i.e. estimated cost put to tender minus the quoted amount as Additional Performance Security (APS) in shape of Demand Draft / Term Deposit Receipt pledge in favour of the Block Development Officer within seven days from the date of lottery, otherwise the bid shall be canceled and the security deposit shall be forfeited. Further, proceeding for blacklisting shall be initiated against bidder. Following all codal procedure from time to time as laid down.
43. Item of work not covered by the tender notice will be paid at the Current Schedule of Rates of the Public Works Departments, and those not covered by S.R. will be paid on actual analysis approved by the Engineer-in-Charges.
44. Standard Public Works Department specification of the Govt. of Orissa will be followed in executing the work.
45. The time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall be reckoned from the date on which the written order commence work is issued to the contractor. The work shall throughout the stipulated period of the contract be carried on with all due diligence (time being deemed to be the essence of the contract on the part of the contractor) and the contractor shall pay the compensation and amount that equal to 1/3<sup>rd</sup> percent on the amount of the estimated cost if the whole works shown by the tender for every day that the whole work remain un commenced or during the execution of the work the contractor shall be bound, in all case in which the time allowed for any work exceed on month, to complete one fourth to whole of the work before three fourths of such times has lapsed in the event of the contractor failing to comply with the condition, he shall be liable to pay as compensation an amount equal to one third percent of the said estimate cost of the whole work for every day that the due quantity of work remains in complete provided always that the entire amount for compensation to be paid under provisions of this clause shall not exceed 10 percent on the estimated cost of work as shown in the tender.

Contractor

*Prasanna*  
6.9.17  
Block Development Officer, Harichandnpur .

46. Measurement will be taken and payment will be made for M.S.Rods and reinforcement grills as per the actual length and weight of M. S. Rods utilized in works. The weight of binding wires and cut pieces will not be considered for payment.
47. 4% ("D" & "C" Class)/ 5% ("B" and above) will be deducted from each payment of bill on gross value towards security deposit money. This security money is excluding EMD & ISD payments towards EMD & ISD will be paid to the contractor without any interest on application after One year of completion of work provided the final bill is paid and the defects if any pointed out within six months of completion for work have been rectified by the Contractor. S.D. shall be refunded after audit only.
48. Income Tax @1% for person and 2% for firms and GST (TDS @2%) will be deducted from the bill amount as per Govt. prescribed from time to time accordingly a bill voucher will be submitted to Block Development Officer, Harichandnpur by the Contractor. .
49. No monetary compensation will be entertained on account of natural calamities like cyclone, earth quake, flood and heavy rain fall etc., but suitable extension of time may be granted by on consideration of the application of the contractor at once and that too only on valid reasons. No escalation claim will be entertained during the time period and extension period.
50. The earth work for roads will be done & assessed as per the actual pit excavated and measured or by truck measurement or by section measurement on actual level taken or as assessed by the Engineer-in-charges of the works.
51. Rubble Stone, boulders, rough stone, soling stones and over size metals measured by volume of closely packed stacks. 1/6 of the volume for voids will normally be deducted from closely packed stacks. For loosely packed stacks percentage of voids will be determined on actual observation and deducted as assessed at site by Engineer-in-Charges.
52. 12 ½ % will be deducted from metal and moorum towards void. The box heaps of 1.50x1.50x0.50m to be measured as one cum. similar measurement to be adopted for gravel stacks and voids deducted. The rates should be excluding voids.
53. Sand will be measured in box heaps of 1.50x1.50x0.50m being taken as one cubic meter or as directed by the Engineer-in-Charges of the work.
54. Maintaining traffic, cutting trenches from road side lines and watching, providing signals and providing diversion road, barricading etc and maintenance for them till completion of work should be done by the contractor at his own cost.
55. It is contractor responsibility to correctly demarcate the road alignment, centre line and edge line of the road and formation width metalling width and soling width and fencing line etc., for execution of work as directed by the Assistant Executive Engineer / Assistant Engineer / Junior Engineer / Gram Panchayat Technical Assistant. All expenditure in connections with T&P instruments materials etc., required for this purpose shall be borne by the Contractor.
56. The quantities of item of work may vary at the time of actual execution of the work. The Contractors should do the work at his tendered rate whatsoever the quantity may be without any extra claim.
57. Compacted thickness as of soling stone and metal including consolidation of bill materials for which no claim for extra payment shall be entertained.

Contractor

*Prabhu*  
G. G. Y  
Block Development Officer, Harichandnpur .

58. Only Crusher broken chips shall be allowed for R.C.C. Work as the case may be as stated in Tender Schedule or as directed by Engineer-in-Charges.
59. Five percent will be deducted for voids of chips of size 6mm and above.
60. The Contractor shall sign on the plan and documents for service connection (Such as P.H.D. and Electric) as and where required by the Department or house owner other wise the security money of the contractor will not be released.
61. If the rate quoted by the bidder is more less than (14.99% Less) of the tendered amount, then such a bid shall be rejected and the tender shall be finalized basing on merits of rest bids. But if more than one bid is quoted at 14.99% (Decimals upto two numbers will be taken for all practical purposes) less than the estimated cost, the tendered accepting authorities will finalize the tender through a transparent lottery system where all bidders / authorized representatives, the Concerned Block Development Officer and the tender committee will remain present.
62. No excess over and above the estimated rates shall be allowed. In case, the lowest tenderer fails to negotiate his rates to estimated rates, the documents shall be forwarded to Govt. for approval.
63. No empty Cement Bags will be taken back by the Block and the same will be recovered from the bill @Rs.3.60 / per bags.

Verified by

Account Officer  
Harichandnpur Block

Approved by

Block Development Officer  
Harichandnpur Block

*Prasanna*  
*0.9.17*

**CERTIFICATE NO.-1**

**(CLAUSE NO. 40)**

I/We hereby certify that I/We\* am/are\* **related/not related**( \* ) to any officer of the rank of Additional Project Director(Tech) of DRDA, Keonjhar & above and any officer of the rank of GPTA/Account Officer and above of the Panchayat Samiti, Harichandnpur, Govt. of Odisha I/We\* am/are\* aware that, if the facts subsequently proved to be false, my/our\* contract will be rescinded with forfeiture of E.M.D and security deposit and I/We\* shall be liable to make good the loss or damage resulting from such cancellation. I/We also note that, non-submission of this certificate will render my / our tender liable for rejection.

(\*) - Strike out which is not applicable

Contractor

Signature of the Contractor.

Date: *Prasanna*  
*0.9.17*

Block Development Officer, Harichandnpur

BILL OF QUANTIT/ (BOQ)


Construction of Three nos of Class room at Saraswati sishu mandira at Harichandanpur

Amount put to Tender	:	Rs 16,95,357.00
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date required for completion	:	04(Four) calender Month


ITEM NO	NAME OF ITEMS	QUANTITY	UNIT	RATE	AMOUNT
1	Earth Work in excavation of hard soil in foundation trenches.	123.42	Cum	187.81	23180.00
2	Filling in foundation and plinth with sand well watered and rammed	75.46	Cum	323.63	24421.00
3	Cement concrete (1:4:8) with 4cm hard granite metal with cost , carriage , royalty of materials & cost of labour , T & P etc etc complete with all respect	31.27	Cum	4221.34	132001.00
4	R.C.C (1:1.5:3) using 12mm size CBHG chips including hoisting etc. complete with cost of all material & labour.	55.20	Cum	6774.11	373931.00
5	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification	49.13	Qntl	5249.17	257892.00
6	Rigid and smooth centring, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.				
a	Plinth band	249.32	Sqm	104.11	25957.00
b	Beam	124.73	Sqm	705.45	87991.00
c	Lintel	25.34	Sqm	272.13	6896.00
d	Roof slab	147.50	Sqm	430.01	63426.00
7	Fly ash brick masonry in CM (1:6) in foundation and plinth	24.75	Cum	4000.24	99006.00
8	Fly Ash.Brick masonry in cement mortar (1:6) in Superstructure.	36.81	Cum	4033.24	148464.00
9	12 mm thick cement plaster in C.M.(1:6) in external surface of wall	211.67	Sqm	143.44	30362.00

10	Weight of MS Door , Window & Grill	549.12	kg	121.20	66553.00
11	16mm thick cement plaster in C.M.(1:6) in external surface of wall	249.86	Sqm	202.79	50669.00
12	Labour for fitting and fixing of M.S grill , Door & Window shutter & Gates as per approved Design cost of all materials	22.88	Sqm	489.17	11192.00
13	Finishing wall surface of walls with Acylic Wall putty (water based) of approved	398.20	Sqm	63.36	25230.00
14	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement : 1 sans) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including	134.17	Sqm	611.33	82022.00
15	Fixing tiles in dados skirting and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete excluding cost of pre cast tiles.	13.70	Sqm	706.62	9681.00
16	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to	619.38	Sqm	77.28	47866.00
17	Painting 2-coats with enamel paint over a coat of priming to door and windows.	67.93	Sqm	190.88	12966.00
18	20mm thick Grading cement plaster (1:4) over RC.C. Roof slab including curing etc. complete.	152.24	Sqm	225.66	34354.00
19	Cost of Vitrified Tiles	155.26	Sqm	523.62	81297.00
				<b>Total</b>	<b>1695357.00</b>

TOTAL 19 (Nineteen) NOS ITEM ONLY

  
27.7.21  
Block Development Officer  
Harichandanpur Block

Approved for 19(Nineteen) items only

  
21-06-21  
Executive Engineer  
DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

BILL OF QUANTITY (BOQ)


Construction of Three nos of Class room at Sri Aurobindo integral Education Centre at Laxmipur

Amount put to Tender	:	Rs 16,95,357.00
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date required for completion	:	04(Four) calender Month

ITEM NO	NAME OF ITEMS	QUANTITY	UNIT	RATE	AMOUNT
1	Earth Work in excavation of hard soil in foundation trenches.	123.42	Cum	187.81	23180.00
2	Filling in foundation and plinth with sand well watered and rammed	75.46	Cum	323.63	24421.00
3	Cement concrete (1:4:8) with 4cm hard granite metal with cost , carriage , royalty of materials & cost of labour , T & P etc etc complete with all respect	31.27	Cum	4221.34	132001.00
4	R.C.C (1:1.5:3) using 12mm size CBHG chips including hoisting etc. complete with cost of all material & labour.	55.20	Cum	6774.11	373931.00
5	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification	49.13	Qntl	5249.17	257892.00
6	Rigid and smooth centring, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.				
a	Plinth band	249.32	Sqm	104.11	25957.00
b	Beam	124.73	Sqm	705.45	87991.00
c	Lintel	25.34	Sqm	272.13	6896.00
d	Roof slab	147.50	Sqm	430.01	63426.00
7	Fly ash brick masonry in CM (1:6) in foundation and plinth	24.75	Cum	4000.24	99006.00
8	Fly Ash.Brick masonry in cement mortar (1:6) in Superstructure.	36.81	Cum	4033.24	148464.00
9	12 mm thick cement plaster in C.M.(1:6) in external surface of wall	211.67	Sqm	143.44	30362.00

10	Weight of MS Door , Window & Grill	549.12	kg	121.20	66553.00
11	16mm thick cement plaster in C.M.(1:6) in external surface of wall	249.86	Sqm	202.79	50669.00
12	Labour for fitting and fixing of M.S grill , Door & Window shutter & Gates as per approved Design cost of all materials	22.88	Sqm	489.17	11192.00
13	Finishing wall surface of walls with Acylic Wall putty (water based) of approved	398.20	Sqm	63.36	25230.00
14	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement : 1 sans) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including	134.17	Sqm	611.33	82022.00
15	Fixing tiles in dados skirting and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete excluding cost of pre cast tiles.	13.70	Sqm	706.62	9681.00
16	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to	619.38	Sqm	77.28	47866.00
17	Painting 2-coats with enamel paint over a coat of priming to door and windows.	67.93	Sqm	190.88	12966.00
18	20mm thick Grading cement plaster (1:4) over RC.C. Roof slab including curing etc. complete.	152.24	Sqm	225.66	34354.00
19	Cost of Vitrified Tiles	155.26	Sqm	523.62	81297.00
				<b>Total</b>	<b>1695357.00</b>

TOTAL 19 (Nineteen) NOS ITEM ONLY

  
Block Development Officer  
Harichandanpur Block

Approved for 19(Nineteen) items only

  
Executive Engineer  
DRDA Keonjhar

  
21-06-21

21.06.2021

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

BILL OF QUANTITY (BOQ)


## NAME OF THE WORK:-CONSTRUCTION OF ROAD WITH CULVERT AT DAITARI

Amount put to Tender	:	Rs 25,73,043.00
Class of Contractor	:	C' & B' class only
Cost of Tender Paper	:	Rs.6000.00
Date required for completion	:	3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Construction of embankment with approved materials obtained from borrow pits with all lifts and leads, transporting to site by mechanical means within a lead of 5.0 Kms , spreading, grading to required slope and compacting to meet requirement of table 300-2 and clause 305 of MoSRT & H specifications for road & bridge works(4th Revision)	4732.50	CUM	127.55	603633.00
2	Collecting, stacking good quality of moorum at the road side to regular box heaps of 1.50m×1.50m×0.44m to be measured as One cum.	349.92	CUM	276.29	96679.00
3	Collecting, stacking good quality of Sand at the road side to regular box heaps of 1.50m×1.50m×0.44m to be measured as One cum.	233.28	CUM	272.48	63564.00
4	Labour for admixing sand and moored etc. complete including cost of all labour and hire charges of T & P, materials required for work as per specification excluding cost and conveyance of sand & moored	583.20	CUM	90.09	52540.00
5	Labour for laying Sub-base in layers not exceeding 225 mm watering and compacting to the required density in OMC with Vibratory Roller but excluding cost and conveyance of sub-base materials	583.20	CUM	83.46	48671.00
6	E/W excavation in h/s within initial lead and lift.	300.71	CUM	189.95	57121.00
7	Filling F&P with sand well watered and rammed Etc comp.	185.73	CUM	323.59	60102.00
8	Cement concrete (1:3:6) with 4cm hard granite	189.63	CUM	4475.67	848733.00
9	C.C (1:2:4) using 12mm size hg cb chips including all cost	88.49	CUM	5961.69	527524.00
10	Hire charges of vibrator	38.02	HOOR	92.17	3504.00


11	Cost of Bitumemous jont board 25 mm thick	7.56	SQM	1109.24	8386.00
12	12mm thick cement plaster (1:6) for brickwork including curing etc. complete.	48.40	SQM	140.09	6781.00
13	Cost ,carriage of 600 mm dia RCC Hume pipe	6.00	NOS	6000.00	36000.00
14	Cost ,carriage of 1000 mm dia RCC Hume pipe	9.00	NOS	13500.00	121500.00
15	Rigid smooth centering and shuttering				
A	B)RCC foundation & plinth band footings, bases of columns, mass concrete,etc.	330.95	SQM	115.74	38305.00
	<b>TOTAL RS</b>				<b>2573043.00</b>

**TOTAL 15 (Fifteen) NOS ITEM ONLY**

  
 21.7.21  
 Block Development Officer  
 Harichandanpur Block

**Approved for 15(Fifteen) items only**

  
 21-06-21

  
 21.06.2021  
 Executive Engineer  
 DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
 Excess in Percentage  
 Less in Percentage

in Figure

	%
	%
	%

In words


**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

Executive Engineer  
 DRDA Keonjhar

Block Development Officer  
 Harichandanpur Block


**BILL OF QUANTITY (BOQ)**

Construction of CC road from Panchayat office to 80 tanament

Amount put to Tender : Rs 15,90,046.00  
 Class of Contractor : D' & C' class only  
 Cost of Tender Paper : Rs.6000.00  
 Date required for completion : 3(Three) calender Month


SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc, complete with all	162.68	CUM	187.81	30553.00
2	Filling foundation & plinth by sand well watered and rammed.	142.28	CUM	323.63	46046.00
3	Cement concrete (1:3:6) with 4cm hard granite metal with cost, carriage & royalty.	120.20	CUM	4564.78	548687.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	149.03	CUM	6135.43	914363.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	217.60	SQM	104.11	22654.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	29.57	SQM	602.52	17817.00
7	Hire charges of Plate Vibrator	107.69	hr SQM	92.17	9926.00
<b>TOTAL RS</b>					<b>1590046.00</b>


TOTAL 07 (Seven) NOS ITEM ONLY

  
 Block Development Officer  
 Harichandanpur Block

Approved for 07(Seven) items only

  
 Executive Engineer  
 DRDA Keonjhar

  
 21-06-21

  
 21-06-2021

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

9

**BILL OF QUANTITY (BOQ)**


**Construction of Three nos of Class room at Brahmanipal, Kushabhadra High school**

Amount put to Tender	:	Rs 16,95,357.00
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date required for completion	:	04(Four) calender Month

ITEM NO	NAME OF ITEMS	QUANTITY	UNIT	RATE	AMOUNT
1	Earth Work in excavation of hard soil in foundation trenches.	123.42	Cum	187.81	23180.00
2	Filling in foundation and plinth with sand well watered and rammed	75.46	Cum	323.63	24421.00
3	Cement concrete (1:4:8) with 4cm hard granite metal with cost , carriage , royalty of materials & cost of labour , T & P etc etc complete with all respect	31.27	Cum	4221.34	132001.00
4	R.C.C (1:1.5:3) using 12mm size CBHG chips including hoisting etc. complete with cost of all material & labour.	55.20	Cum	6774.11	373931.00
5	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification	49.13	Qntl	5249.17	257892.00
6	Rigid and smooth centring, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.				
a	Plinth band	249.32	Sqm	104.11	25957.00
b	Beam	124.73	Sqm	705.45	87991.00
c	Lintel	25.34	Sqm	272.13	6896.00
d	Roof slab	147.50	Sqm	430.01	63426.00
7	Fly ash brick masonry in CM (1:6) in foundation and plinth	24.75	Cum	4000.24	99006.00
8	Fly Ash.Brick masonry in cement mortar (1:6) in Superstructure.	36.81	Cum	4033.24	148464.00
9	12 mm thick cement plaster in C.M.(1:6) in external surface of wall	211.67	Sqm	143.44	30362.00

10	Weight of MS Door , Window & Grill	549.12	kg	121.20	66553.00
11	16mm thick cement plaster in C.M.(1:6) in external surface of wall	249.86	Sqm	202.79	50669.00
12	Labour for fitting and fixing of M.S grill , Door & Window shutter & Gates as per approved Design cost of all materials.	22.88	Sqm	489.17	11192.00
13	Finishing wall surface of walls with Acylic Wall putty (water based) of approved	398.20	Sqm	63.36	25230.00
14	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement : 1 sans) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including	134.17	Sqm	611.33	82022.00
15	Fixing tiles in dados skirting and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete excluding cost of pre cast tiles.	13.70	Sqm	706.62	9681.00
16	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to	619.38	Sqm	77.28	47866.00
17	Painting 2-coats with enamel paint over a coat of priming to door and windows.	67.93	Sqm	190.88	12966.00
18	20mm thick Grading cement plaster (1:4) over RC.C. Roof slab including curing etc. complete.	152.24	Sqm	225.66	34354.00
19	Cost of Vitrified Tiles	155.26	Sqm	523.62	81297.00
<b>Total</b>					<b>1695357.00</b>

TOTAL 19 (Nineteen) NOS ITEM ONLY

  
 Block Development Officer  
 Harichandanpur Block

Approved for 19(Nineteen) items only

  
 Executive Engineer  
 DRDA Keonjhar

21-06-21

21-06-2021

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

BILL OF QUANTITY (BOQ)

## Construction of CC road from Jantia to Tentulipal

Amount put to Tender : Rs 35,50,748.00  
 Class of Contractor : C' & B' class only  
 Cost of Tender Paper : Rs.6000.00  
 Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc. complete with all	363.44	CUM	187.81	68258.00
2	Filling foundation & plinth by sand well watered and rammed.	317.84	CUM	323.63	102863.00
3	Cement concrete (1:3:6) with 4cm hard granite metal with cost, carriage & royalty.	268.04	CUM	4564.78	1223544.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	332.99	CUM	6135.43	2043037.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	486.40	SQM	104.11	50639.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	66.80	SQM	602.52	40248.00
7	Hire charges of Plate Vibrator	240.41	hr SQM	92.17	22159.00
<b>TOTAL RS</b>					<b>3550748.00</b>

TOTAL 07 (Seven) NOS ITEM ONLY

  
 2-7-21  
 Block Development Officer  
 Harichandanpur Block

Approved for 07(Seven) items only

  
 21-06-21  
 Executive Engineer  
 DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**


**BILL OF QUANTITY (BOQ)**

**Construction of CC road from Plot Chhak to SKUG School**

Amount put to Tender : Rs 35,50,748.00  
 Class of Contractor : C' & B' class only  
 Cost of Tender Paper : Rs.6000.00  
 Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc, complete with all	363.44	CUM	187.81	68258.00
2	Filling foundation & plinth by sand well watered and rammed.	317.84	CUM	323.63	102863.00
3	Cement concrete (1:3:6) with 4cm hard granite metal with cost, carriage & royalty.	268.04	CUM	4564.78	1223544.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	332.99	CUM	6135.43	2043037.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	486.40	SQM	104.11	50639.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	66.80	SQM	602.52	40248.00
7	Hire charges of Plate Vibrator	240.41	hr SQM	92.17	22159.00
<b>TOTAL RS</b>					<b>3550748.00</b>

TOTAL 07 (Seven) NOS ITEM ONLY

  
 7.7.21  
**Block Development Officer**  
 Harichandanpur Block

Approved for 07(Seven) items only

  
 21-06-21  
**Executive Engineer**  
 DRDA Keonjhar

3  
 21.06.2021

**TO BE FILLED BY THE TENDERER**

i) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
Excess in Percentage  
Less in Percentage

in Figure	
	%
	%
	%

In words

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

**BILL OF QUANTITY (BOQ)**

Construction of CC road from PWD Road to Kantajhari sahi

Amount put to Tender : Rs 26,57,943.00  
 Class of Contractor : C' & B' class only  
 Cost of Tender Paper : Rs.6000.00  
 Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc, complete with all	272.02	CUM	187.81	51088.00
2	Filling foundation & plinth by sand well watered and rammed.	237.90	CUM	323.63	76992.00
3	Cement concrete (1.3:6) with 4cm hard granite metal with cost, carriage & royalty.	200.73	CUM	4564.78	916288.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	249.22	CUM	6135.43	1529072.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	364.00	SQM	104.11	37896.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	49.82	SQM	602.52	30018.00
7	Hire charges of Plate Vibrator	179.98	hr SQM	92.17	16589.00
<b>TOTAL RS</b>					<b>2657943.00</b>

TOTAL 07 (Seven) NOS ITEM ONLY

  
 3-7-21  
 Block Development Officer  
 Harichandanpur Block

Approved for 07(Seven) items only

  
 21-06-21  
 Executive Engineer  
 DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	In Figure	In words
Equal to Estimate Cost	_____ %	_____
Excess in Percentage	_____ %	_____
Less in Percentage	_____ %	_____

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

5

**BILL OF QUANTITY (BOQ)**

Construction of CC road from Talapada dam site to Dalki sahi

Amount put to Tender : Rs 35,50,748.00  
Class of Contractor : C' & B' class only  
Cost of Tender Paper : Rs.6000.00  
Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc, complete with all	363.44	CUM	187.81	68258.00
2	Filling foundation & plinth by sand well watered and rammed.	317.84	CUM	323.63	102863.00
3	Cement concrete (1:3:6) with 4cm hard granite metal with cost, carriage & royalty.	268.04	CUM	4564.78	1223544.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	332.99	CUM	6135.43	2043037.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	486.40	SQM	104.11	50639.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	66.80	SQM	602.52	40248.00
7	Hire charges of Plate Vibrator	240.41	hr SQM	92.17	22159.00
<b>TOTAL RS</b>					<b>3550748.00</b>

TOTAL 07 (Seven) NOS ITEM ONLY

  
7.7.21  
Block Development Officer  
Harichandanpur Block

Approved for 07(Seven) items only

  
21.06.2021  
Executive Engineer  
DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**


BILL OF QUANTITY (BOQ)

Construction of CC road From Talapada school to Dumasahi

Amount put to Tender : Rs 17,76,060.00  
 Class of Contractor : D' & C' class only  
 Cost of Tender Paper : Rs.6000.00  
 Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc. complete with all	182.13	CUM	187.81	34206.00
2	Filling foundation & plinth by sand well watered and rammed.	154.83	CUM	323.63	50108.00
3	Cement concrete (1:3:6) with 4cm hard granite metal with cost, carriage & royalty.	136.92	CUM	4564.78	625010.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	163.89	CUM	6135.43	1005536.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	291.20	SQM	104.11	30317.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	32.85	SQM	602.52	19793.00
7	Hire charges of Plate Vibrator 4cm x 10' 3' x 9' - cum	120.32	hr SQM	-92.17	11090.00
<b>TOTAL RS</b>					<b>1776060.00</b>

TOTAL 07 (Seven) NOS ITEM ONLY

  
 21.06.2021  
 Block Development Officer  
 Harichandanpur Block

Approved for 07(Seven) items only

  
 21.06.2021  
 Executive Engineer  
 DRDA Keonjhar

  
 21-06-21

o/c

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
Excess in Percentage  
Less in Percentage

in Figure	
	%
	%
	%

In words

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**


**BILL OF QUANTITY (BOQ)**

Construction of CC road from Talapada school to Nuasahi

Amount put to Tender : Rs 13,26,517.00  
 Class of Contractor : D' & C' class only  
 Cost of Tender Paper : Rs.6000.00  
 Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Earth work excavation of foundation in hard soil within initial lead and lift etc. complete with all	135.79	CUM	187.81	25503.00
2	Filling foundation & plinth by sand well watered and rammed.	118.77	CUM	323.63	38438.00
3	Cement concrete (1:3:6) with 4cm hard granite metal with cost, carriage & royalty.	100.41	CUM	4564.78	458350.00
4	C.C (1:2:4) using 12mm size hg cb chips including all cost	124.39	CUM	6135.43	763186.00
5	Rigid and smooth centering, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.	181.60	SQM	104.11	18906.00
6	Supplying & fixing 12mm thick Bituminous expansion Joint	24.64	SQM	602.52	14846.00
7	Hire charges of Plate Vibrator	89.92	SQM	92.17	8288.00
<b>TOTAL RS</b>					<b>1327517.00</b>

TOTAL 07 (Seven) NOS ITEM ONLY

  
 7-7-21  
 Block Development Officer  
 Harichandanpur Block

Approved for 07(Seven) items only

  
 21-06-21  
 Executive Engineer  
 DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
Excess in Percentage  
Less in Percentage

in Figure	
	%
	%
	%

In words

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**


**BILL OF QUANTITY (BOQ)****Construction of School Building at Bareigoda High School**

Amount put to Tender	:	Rs 16,95,357.00
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date required for completion	:	04(Four) calender Month

ITEM NO	NAME OF ITEMS	QUANTITY	UNIT	RATE	AMOUNT
1	Earth Work in excavation of hard soil in foundation trenches.	123.42	Cum	187.81	23180.00
2	Filling in foundation and plinth with sand well watered and rammed	75.46	Cum	323.63	24421.00
3	Cement concrete (1:4:8) with 4cm hard granite metal with cost , carriage , royalty of materials & cost of labour , T & P etc etc complete with all respect	31.27	Cum	4221.34	132001.00
4	R.C.C (1:1.5:3) using 12mm size CBHG chips including hoisting etc. complete with cost of all material & labour.	55.20	Cum	6774.11	373931.00
5	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification	49.13	Qntl	5249.17	257892.00
6	Rigid and smooth centring, shuttering for RCC works including false work and dismantling them after casting including cost of materials complete.				
a	Plinth band	249.32	Sqm	104.11	25957.00
b	Beam	124.73	Sqm	705.45	87991.00
c	Lintel	25.34	Sqm	272.13	6896.00
d	Roof slab	147.50	Sqm	430.01	63426.00
7	Fly ash brick masonry in CM (1:6) in foundation and plinth	24.75	Cum	4000.24	99006.00
8	Fly Ash.Brick masonry in cement mortar (1:6) in Superstructure.	36.81	Cum	4033.24	148464.00
9	12 mm thick cement plaster in C.M.(1:6) in external surface of wall	211.67	Sqm	143.44	30362.00

10	Weight of MS Door , Window & Grill	549.12	kg	121.20	66553.00
11	16mm thick cement plaster in C.M.(1:6) in external surface of wall	249.86	Sqm	202.79	50669.00
12	Labour for fitting and fixing of M.S grill , Door & Window shutter & Gates as per approved Design cost of all materials	22.88	Sqm	489.17	11192.00
13	Finishing wall surface of walls with Acylic Wall putty (water based) of approved	398.20	Sqm	63.36	25230.00
14	Fixing tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement : 1 sans) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including	134.17	Sqm	611.33	82022.00
15	Fixing tiles in dados skirting and risers of steps on 12 mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing complete excluding cost of pre cast tiles.	13.70	Sqm	706.62	9681.00
16	Wall painting 2 coat with plastic emulsion paint of approved shade on new work to	619.38	Sqm	77.28	47866.00
17	Painting 2-coats with enamel paint over a coat of priming to door and windows.	67.93	Sqm	190.88	12966.00
18	20mm thick Grading cement plaster (1:4) over RC.C. Roof slab including curing etc. complete.	152.24	Sqm	225.66	34354.00
19	Cost of Vitrified Tiles	155.26	Sqm	523.62	81297.00
				<b>Total</b>	<b>1695357.00</b>

TOTAL 19 (Nineteen) NOS ITEM ONLY

  
 21.7.21  
 Block Development Officer  
 Harichandanpur Block

Approved for 19(Nineteen) items only

  
 21-06-21  
 Executive Engineer  
 DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer  
DRDA Keonjhar**

**Block Development Officer  
Harichandanpur Block**

1

**BILL OF QUANTITY (BOQ)**

**NAME OF THE WORK:-CONSTRUCTION OF GUARD WALL AND APPROCH ROAD ON TINIPOLIA CHHAK TO PANCHAM**

Amount put to Tender : Rs 9,56,145.00  
Class of Contractor : D' & C' class only  
Cost of Tender Paper : Rs.6000.00  
Date required for completion : 3(Three) calender Month

SI No	Description Items with Measurement	QUANTITY	UNIT	RATE	AMOUNT
1	Construction of embankment with approved materials obtained from borrow pits with all lifts and leads, transporting to site by mechanical means within a lead of 5.0 Kms , spreading, grading to required slope and compacting to meet requirement of table 300-2 and clause 305 of MoSRT & H specifications for road & bridge works(4th Revision)	1893.00	CUM	127.55	241453.00
2	Collecting, stacking good quality of moorum at the road side to regular box heaps of 1.50m×1.50m×0.44m to be measured as One cum.	139.97	CUM	276.29	38672.00
3	Collecting, stacking good quality of Sand at the road side to regular box heaps of 1.50m×1.50m×0.44m to be measured as One cum.	93.31	CUM	272.48	25426.00
4	Labour for admixing sand and moored etc. complete including cost of all labour and hire charges of T & P, materials required for work as per specification excluding cost and conveyance of sand & moored	233.28	CUM	90.09	21016.00
5	Labour for laying Sub-base in layers not exceeding 225 mm watering and compacting to the required density in OMC with Vibratory Roller but excluding cost and conveyance of sub-base materials	233.28	CUM	83.46	19468.00
6	E/W excavation in h/s within initial lead and lift.	64.00	CUM	189.95	12157.00
7	Filling F&P with sand well watered and rammed Etc comp.	9.60	CUM	323.59	3106.00
8	Cement concrete (1:3:6) with 4cm hard granite	9.60	CUM	4475.67	42966.00
9	R.C.C M-20 grade with 20mm and down graded black hard granite crucher broken chips including hosting	51.36	CUM	4867.49	249994.00
10	Supplying, fitting and palcing HYSD bar reinforcement (Fe-415) complete as per drawing and	46.22	QTL	6210.45	287072.00

1	Rigid smooth centering and shuttering				
(A)	base of foundation	128.00	SQM	115.74	14815.00
	TOTAL RS				956145.00

TOTAL 11 (Elevteen) NOS ITEM ONLY

  
7.7.21  
Block Development Officer  
Harichandanpur Block

Approved for 11 (Elevteen) NOS ITEM ONLY

  
21.06.2021  
Executive Engineer  
DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost  
Excess in Percentage  
Less in Percentage

in Figure

	%
	%
	%

In words


**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

Executive Engineer  
DRDA Keonjhar

Block Development Officer  
Harichandanpur Block