

BILL OF QUANTITY

Construction of Sub Centre Building at Gayalmunda under Anandapur block for the year 2021-22 under NHM

TENDER AMOUNT	Rs. 2083281.00
EMD @ 1%	Rs. 20900.00
COST OF TENDER PAPER	Rs 6000.00
TIME OF COMPLETION	Six months
CLASS OF CONTRACTOR	C & B

SI No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	91.01	Each cum	207.89	18920.07
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	91.01	Each cum	138.59	12613.38
3	Cement Concrete (1:3:6) in Foundation using 4 cm size bhg metal including watering, curing with cost, conveyance, royalty and taxes of all materials and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	68.12	Each cum	549.27	37415.97
4	Cement Concrete (1:3:6) in Foundation using 4 cm size bhg metal including watering, curing with cost, conveyance, royalty and taxes of all materials and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	21.46	Each cum	4867.71	104461.07
5	Cement Concrete (1:1.5:3) using 12mm size cbhg chips including watering, curing with cost, conveyance, royalty and taxes of all materials and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	0.74	Each cum	7093.64	5249.30
6	R.C.C. M20 using 20 mm & down size b.h.g.c.b chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				
A	Foundation footing	13.40	Each Cum	5424.59	72689.47
B	Plinth Beam	5.44	Each Cum	5784.61	31468.25
C	Column and Beams (GF)	8.10	Each Cum	11148.17	90300.18
	Column and Beams (FF)	0.55	Each Cum	12396.59	6818.13
D	Lintel(GF)	3.39	Each Cum	8996.78	30499.08
	Lintel (FF)	0.10	Each Cum	9814.92	981.49
E	Sunshade(GF)	9.47	Each Sam	815.35	7719.59
	Sunshade(FF)	0.84	Each Sam	913.25	764.39
F	R.C.C Shelves	2.14	Each Sam	779.28	1666.89


R.C.C Stair		1.52	Each Cum	10677.17	16221.98
H	Roof slab, landing & Chajja	10.27	Each Sqm	9568.30	98266.42
7	Cutting, Bending, binding and tying the grills and placing in position including cost, conveyance, taxes of all materials and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	47.74	Each Qntl	8963.50	427917.49
8	20mm thick C.P. (1:4) as grading plaster including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	89.81	Each Sqm	234.44	21054.62
9	Fly Ash Brick masonry with CM (1:6) in foundation including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	27.23	Each Cum	4294.42	116937.07
10	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				
A	GF	44.96	Each Cum	4327.75	194575.66
B	FF	10.20	Each cum	4976.92	50764.54
11	16mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.				
A	GF	319.64	Each Sqm	201.15	64294.63
B	FF	63.25	Each Sqm	205.40	12992.05
12	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.				
A	GF	304.03	Each Sqm	141.48	43014.62
B	FF	50.30	Each Sqm	146.25	7357.15
13	Supplying, fitting, fixing of Vetrified tile flooring on 20mm thick bed of C.M. (1:4) jointed with neat cement slurry & pigment to match the shade including watering & curing with cost, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	72.93	Each Sqm	956.12	69729.72
14	Supplying, fitting, fixing of Vetrified tile in dados on 12mm thick C.P. (1:3) jointed with neat cement slurry & pigment to match the shade including watering & curing with cost, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	13.50	Each Sqm	1371.67	18517.545
15	Supplying, fitting, fixing of Ceramic Glazed Wall tile in walls on 12mm thick C.P. (1:3) jointed with neat cement slurry & pigment to match the shade including watering & curing with cost, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	24.41	Each Sqm	1061.63	25914.3883

16	Fixing tiles (Vitrified Industrial Tiles) in floors treads or steps and landing on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing with cost, conveyance of all materials etc. complete.				
A	GF	28.72	Each Sqm	1261.01	36215.36
B	FF	0.33	Each Sqm	1287.43	419.06
17	Supplying, fitting, fixing of vitrified industrial tile in dados on 12mm thick C.P. (1:3) jointed with neat cement slurry & pigment to match the shade including watering & curing with cost, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	8.04	Each Sqm	1261.01	10144.19
18	Supplying, fitting, fixing of Grinite on 20mm thick bed of C.M. (1:4) jointed with neat cement slurry & pigment to match the shade including watering & curing with cost, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	4.73	Each Sqm	2524.08	11938.90
19	6mm thick C.P. (1:4) as ceiling plaster including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.				
A	GF	141.06	Each Sqm	156.85	22124.98
B	FF	1.77	Each Sqm	160.19	283.54
20	Providing, supplying and fitting and fixing of M.S. Door / Window shutters, gates & M.S. grills as per approved design etc. complete.				
	MS Grills..	86.10	Each KG	92.93	8001.24
	MS Door & Windows	1637.75	Each KG	134.00	219458.50
21	Supplying, fitting, fixing up window (sliding type) made up aluminium section 9778 as window frame Section No. 4095, 4096 and 9777, 3994 as shutter frame pannel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes of labour, T&P etc. complete.	1.12	Each Sqm	3651.23	4089.38
22	Providing MS Colour sheets (as per IS :14871) up to any pitch and fixing with polymer coated J or L hook and bitumen washer and bolt etc. complete with supply of all labour, taxes, T & P etc.(As SR-page no 127/36	13.44	Each Sqm	656.75	8826.66
23	Wall painting two coat with plastic emulsion paint over a coat of priming including cost of all materials and labour etc.				
A	GF	413.05	Each Sam	155.31	64150.08
B	FF	25.14	Each Sam	156.58	3936.38
24	Painting two coats over a coat of primer with any approved Enamel paints including cost, conveyance of all materials and labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	87.29	Each Sqm	179.87	15701.16
25	Finishing out side wall surface with Weather Coat (I.S.I) two coats with any approved shade over a coat of priming including cost of all materials and labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				

A	GF	326.87	Each Sqm	135.08	44152.78
B	FF	92.43	Each Sqm	159.21	14715.63
26	Supplying, fitting afixing of stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost conveyance, taxes of all materials labour, T&P etc. required for the complete as per the direction of Engineer-	7.91	Each Rmt	3501.98	27684.87
27	Providing and fixing 100 mm dia PVC rain water pipe 1 mtr long with all cost of labour and materials etc.	9.25	Each Rmt	250.05	2312.96
				Total	2083280.80
				say	2083281.00

TOTAL 27 (Twenty Seven) NOS ITEM ONLY

Approved for 27(Twenty Seven) items only


 14/12/21
 Assistant Engineer
 NHM, Keonjhar


 15.12.2021
 Executive Engineer
 DRDA Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost
 Excess in Percentage
 Less in Percentage

in words	In Figure	
		%
		%
		%

Notes:-

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

Executive Engineer
 DRDA Keonjhar

Block Development Officer
 Anandapur Block

Signature of the Contractor