

## BILL OF QUANTITY (BOQ)

N/W- Construction of Block Office Building of Banspal Block.

Amount put to Tender:- Rs 2487829.00

Cost of Tender Paper:- Rs 6000.00

Class of Contractor:- C' & 'B' Class

Sl.No.	Item of Work	Unit	Quantity	Rate	Amount
1	Earth in excavation of foundation in all kinds of soil within 50m lead and 1.5 m lift including rough dressing and breaking colds to maximum 5 cm to 7 cm and laying in layers not exceeding 0.3 m in depth and as per specification complete.including levelling and dressing the bed complete.	Cum	133.20	192.07	25585.00
2	Supplying, filling foundation & plinth with sand including watering, ramming, cost, conveyance, royalty, taxes of all materials and labour (T&P) etc. complete.	Cum	110.02	745.41	82009.00
3	C.C. (1:4:8) using 4cm size h.b.g. metal including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	Cum	32.11	4159.56	133553.00
4	Fly Ash Brick Masonry in C.M.(1:6) in Foundation including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	Cum	30.15	4494.41	135515.00
5	1st Class Fly Ash Brick Masonry in C. M. (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	Cum	21.50	4532.74	97442.00
6	1st Class Fly Ash Brick Masonry in C. M. (1:4) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.	Cum	11.86	4754.83	56373.00
7	R.C.C. M. 20 using 12 mm & down graded size b.h.g.c.b. chips including centering & shuttering, watering, curing with cost, conveyance, royalty and taxes of all materials and labour etc. complete.				
	A) Column Base & Plinth Beam	Cum	33.25	5691.45	189250.00
	B) Column & Beam	Cum	12.46	10908.84	135895.00
	C) Lintel	Cum	3.80	8903.61	33869.00
	D) Roof Slab & Chajja	Cum	29.64	9328.98	276518.00
8	Supplying, fitting and placing uncoated HYSD bar reinforcement as per drawing and technical specification including cost, conveyance and all taxes of steel and binding wire etc. complete.	Qntl	87.07	7456.25	649209.00
9	16mm.thick Cement Plaster in C.M. (1:6) over Brick work complete.	Sqm	573.33	211.76	121405.00
10	12mm.thick Cement Plaster in C.M. (1:6) over Brick work complete	Sqm	194.51	150.31	29236.00
11	6mm thick cement plater in CM(1:4) to RCC surfaces finished smooth including closed deep chiping and slurry treatment.	Sqm	192.28	154.08	29626.00

12	Providing MS Grill in window & door including cost, conveyance taxes and all labour charges etc. complete.	Sqm	756.00	134.02	101319.00
13	landing on 25mm thick of bed of cement mortar(1:1) jointed with neat cement slurry mixed with pigments to match the shades of the tiles including rubbing and polishing complete.	Sqm	154.94	1249.70	193629.00
14	Fixing Vetrified tiles in dados skirting and risers of of steps on 12mm thick cement plaster(1:3) jointed with neat cement slurry mixed wit pigments to match the shades of the tiles including rubbing and polishing complete including cost of tiles.	Sqm	33.43	1345.00	44964.00
15	landing on 20mm thick bed of cement plaster in C.M.1:4(1 cement:4 sand) jointed with neat cement slurry mixed with pigments to match the shades of tiles including rubing and polishing with cost, conveyance of all materials etc. complete.	Sqm	18.76	904.21	16960.00
16	Fixing tiles (Ceramic Wall Tile) in dadoo, skirting and rises of steps on 12mm thick cement plaster in C.M.1:3(1 cement :3 sand) jointed with neat cement slurry mixed with pigments to match the shades of tiles including rubing and polishing with cost, conveyance of all materials etc. complete.	Sqm	71.96	1103.41	79404.00
17	20mm thick cp in cm (1:4) in grading plaster.	Sqm	222.18	236.28	52497.00
18	Cost of Brick masonry Display Board of Size 5'0" x 5'0" x 0'10" with painting and writing	No	1.00	3571.00	3571.00

Total Rs 2487829.00

Total 18 (Eighteen) nos item only.

Approved for 18(Eighteen) items only

GST-12% will be added at the time of Agreement over the quoted amonut.

  
Asst. Exe. Engineer  
Banspal Block.

  
B.D.O.  
Banspal.

  
Executive Engineer  
DRDA Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

Equal to Estimate Cost

Excess in Percentage

Less in Percentage

in Figure	In words
	%
	%
	%

**Notes:-**

- 1) The Tenderer should quote the percentage up to two decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

  
Block Development Officer  
Banspal.