

ABSTRACT

NAME OF THE WORK :- CONSTRUCTION OF CEMENT CONCRETE ROAD WITH 3NOS CULVERT FROM SOSO MAUDA P.W.D.ROAD TO JENASAH I AT BERUNAPADI, SOSO G.P

SCHEME: I.A.P		ESTIMATED COST			Rs	2471472.00
1	Earth work in excavation of foundation in hard soil within initial lead and lift including rough dressing and levelling the bed of the foundation to the required width & depth and stacking the excavated materials away from the working areas as per the direction of E.I.C.	141.32	Cum	199.29	/ Cum	28162.95
2	Providing and filling clean dry sand of approved quality from approved quarry in foundation and plinth in 0'9" thick layer well watered and rammed including cost, conveyance, royalty and taxes of all materials.	169.46	Cum	508.36	/ Cum	86146.34
3	C.C(1:3:6) using 4cm size Hand brocken Hard Granite metal of approved quality from approved quarry including hoisting, laying concrete in layers not exc. 15cm thick, compacting curing, finishing the exposed surface smooth, dewatering, shoring, shuttering if necessary at the time of laying concrete with cost,	187.31	Cum	4359.56	/ Cum	816591.43
4	C.C(1:2:4) using (12 to 20)mm size Hand brocken Hard Granite chipsl of approved quality from approved quarry including hoisting, laying concrete in layers not exc. 15cm thick, compacting curing, finishing theC.C(1:2:4) using (12 to 20)mm size Hand brocken Hard Granite chipsl of approved quality from approved quarry including hoisting, laying	219.72	Cum	5200.07	/ Cum	1142564.96

5	R.C.C(M-20) using (12 to 20)mm size Hand broken Hard Granite chipsl of approved quality from approved quarry including hoisting, laying concrete in layers not exc. 15cm thick, compacting curing, finishing the C.C(1:2:4) using (12 to 20)mm size Hand broken Hard Granite chipsl of	15.28	Cum	10345.43	/ Cum	158098.87
6	Rigid smooth centring and shuttering for RCCwork including false work and dismantling them after casting including cost of materials complete					
(A)	RCC foundation ,footings,bases etc.	782.62	Sqm	101.51	/Sqm	79443.84
7	Hire charges of vibrator as per local market rate.	164.17	Hours	92.17	/Hour	15131.65
8	Reinforcement cutting bending and binding in position including cost of binding wire etc. Complete	14.52	Qtl	8592.21	/Qtl	124740.91
9	6mm thick cement plaster in cement mortar (1:4) over Concrete work ..etc.Complete	80.58	Sqm	128.47	/Sqm	10351.48
10	Add for Display Board & Photography	1.00	No	5000.00		5000.00
11	Add for Unforeseen work.i.e.Site clearance,levelling & dressing,Salitex board to expansion Joints,watering etc	1617.10	Sqm	3.24	/Sqm	5239.41
				Total	Rs	2471471.84
				Or Say	Rs	2471472.00

(Rupees Twenty Four Lakhs Seventy One Thousand Four Hundred Seventy Two)only

**B.D.O
Hatadihi Block**

**Asst. Exe. Engineer
Hatadihi Block**

**Junior Engineer
Hatadihi Block**

TO BE FILLED BY THE TENDERER

My / Our quoted rate is (both in figure and words)

Equal to Estimate Cost

Excess in Percentage

Less in Percentage

Notes:-

In Words	In Figure
	%
	%
	%

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go thorough the special conditions in the DTCN for percentage rate contract before tendering.
- 3) The Tenderer should quoted their percentage only inside the space provided for the purpose
- 4) The percentage quoted at any other place will not be taken into consideration.

Add. Executive Officer (Technical)
Zilla Parishad, Keonjhar