

BILL OF QUANTITY (BOQ)

N/W- Construction of Boundary Wall of Chhamunda G.P. High School.

Amount put to Tender:- Rs 873505.00

Cost of Tender Paper:- Rs 4000.00

Class of Contractor:- D & 'C' Class only

Sl.No.	Item of Work	Unit	Quantity	Rate	Amount
1	2	3	4	5	6
1	Earth work excavation in hard soil or gravel within 50 mtr initial lead & 1.5 mtr initial lift including rough dressing the trench etc complete as per the direction of the Engineer-in-Charge.	Cum	53.21	195.38	10396.00
2	Filling foundation & plinth with coarse sand well watered and rammed as per the direction of Engineer in charge etc complete as per the direction of the Engineer-in-Charge.	Cum	10.00	328.64	3286.00
3	C.C (1:3:6) in foundation and plinth using 40mm H.G.C.B metal including cost, conveyance, royalty etc complete as per the direction of the Engineer-in-Charge.	Cum	10.00	4591.63	45916.00
4	Brick work with Fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75kg/cm ² with dimension tolerance+- 2percent in cement mortar(1:6) in foundation and plinth including cost, conveyance, royalty and taxes etc all complete as per the direction of the Engineer-in-Charge.	Cum	13.83	4616.99	63853.00
5	R.C.C M-20 using 12mm H.G.C.B chips including centering & shuttering cost, conveyance, royalty etc complete as per the direction of the Engineer-in-Charge.				
	A- Column Base	Cum	10.77	4932.00	53118.00
	B- Plinth beam	Cum	7.50	5296.94	39727.00
	C- Column	Cum	3.83	10644.48	40715.00
6	Brick work with Fly ash bricks 25cm x 12cm x 8cm size having crushing strength not less than 75kg/cm ² with dimension tolerance+- 2percent in cement mortar(1:6) in Superstructure including cost, conveyance, royalty and taxes etc all complete as per the direction of the Engineer-in-Charge.	Cum	64.84	4655.32	301851.00
7	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification including, cutting, bending and tying etc all complete as per the direction of the Engineer-in-Charge.	Qntl	10.22	8706.21	88947.00
8	12mm thick cement plaster in c.m (1:6) over brick or stone work including cost, conveyance, royalty and taxes etc all complete as per the direction of the Engineer-in-Charge.	Sqm	340.00	139.53	47439.00
9	16mm thick cement plaster in c.m (1:6) over brick or stone work including cost, conveyance, royalty and taxes etc all complete as per the direction of the Engineer-in-Charge.	Sqm	340.00	199.94	67980.00
10	Priming one coat with any approved primer of wall primer over putty surface complete as per the direction of the Engineer-in-Charge.	Kg	680.00	59.77	40645.00
11	Wall painting 2 coats with Weather coat paint of approved shade on new work to give an even shade including cost of paint complete as per the direction of the Engineer-in-Charge.	Sqm	680.00	97.99	66632.00

12	Cost of Brick Masonry Display Board of 4'0" x 0'10" x 4'0" size to be erected at worksite with colouring and painting writing with logo complete as per the direction of the Engineer-in-Charge.	No	1.00	3000.00	3000.00
				Total Rs	873505.00
				or Say	873505.00

Total 12 (Twelve) nos item only.

GST-18% will be added at the time of Agreement over the quoted amount.

Approved for 12(Twelve) items only

[Signature]
Asst. Exe. Engineer
Telkoi Block.
Asst. Executive Engineer
Telkoi Block

[Signature]
B.D.O.
Telkoi.

[Signature]
Addl. Executive Officer(Technical)
Zilla Parishad, Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

- Equal to Estimate Cost
- Excess in Percentage
- Less in Percentage

in Figure	In words
%	
%	
%	

Notes:-

- 1) The Tenderer should quote the percentage up to **two decimal point** only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

[Signature]
Block Development Officer
Telkoi.