

## TENDER SCHEDULE

CONSTRUCTION OF ONE NO , TOILET AND BOUNDARY WALL AT PALANGATHI HIGH SCHOOL PALANGHATI		AMOUNT PUT TO TENDER :- RS.1491526.00			
		CLASS OF CONTRACTOR :- D & C			
		COST OF TENDER PAPER :- RS. 4000.00			
		E.M.D ; bid declaration			
		TIME OF COMPLETION : 4 MONTHS			
SI No.	ITEM OF WORK	Quantity	Unit	Rate	Amount
1	2		4	5	6
1	E/W in excavation of foundation in hardsoil within initial lead & lift including levelling and dressing the bed complete.	77.72	One cum	Rs. 195.38	15184.93
2	Filling F & P with sand well watered and rammed complete.	21.42	One cum	Rs. 461.96	9895.18
3	Cement concrete (1:4:8) with 4cm size H.G.C.B. metal including all cost carriage rayalty etc.complete	8.30	One cum	Rs. 4,063.94	33730.67
4	C.C.(1:3:6) with using 40mm.size h.b.g. metal complete.	9.47	One cum	Rs. 4,403.57	41701.81
5	Brick work with Fly ash.Bricks in cement mortar (1:6) in Fdn & Pl of size 10"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and sim in Foundation & Plinth	34.56	One cum	Rs. 4,649.47	160685.68
6	RCC M-20 work with 20mm & down graded cbhg chips including all cost carriage rayalty etc.complete.	28.58	One cum	Rs. 4,737.92	135409.75
7	Supplying fitting and placing uncoated HYSD Bar reinforcement complete as per drawing and technical specification and placing in proper position as required for RCC work including cost, conveyance, taxes of steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc. complete in all respect in all floors a per direction of Engineer-in-charge.	25.73	One Qntl	Rs. 8,355.45	214985.73
8	Brick work with Fly ash.Bricks in cement mortar (1:6) in superstructure of size 10"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and sim in Foundation & Plinth	73.50	One cum	Rs. 4,682.80	344185.72
9	Rigid smooth centring, shuttering for R.C.C. works including falseworks				0.00
9	Plinth Bend	20.29	One Sqmt	Rs. 114.75	2328.28
9	B) Lintel Bend :-	12.18	One Sqmt	Rs. 270.04	3289.09
9	C) Column & Beam :-	66.55	One Sqmt	Rs. 764.02	50845.53
9	D) Roof Slab & Chajja :-	60.68	One Sqmt	Rs. 452.66	27487.41
10	20 mm thick cement plaster 1:6	150.98	One Sqmt	Rs. 233.68	35280.99
11	16mm thick cement plaster (1:6) finshed smooth to inside rough surface of brick walls after racking out the joint including watering and curing with cost and conveyance, royalties and taxes of all materials and labour charges required fo	342.45	One Sqmt	Rs. 219.41	75135.25
12	12mm thick cement plaster (1:6) finishing smooth to outside smooth surface of brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for	260.94	One Sqmt	Rs. 142.49	37181.34
13	Cement washing 1coats etc. complete	443.09	One Sqmt	Rs. 14.38	6372.31
14	Priming one coat over plaster surface with water bound cement primer with cost of all material	693.68	One Sqmt	Rs. 67.99	47165.13
15	Wall painting two coats with distemper paint with cost of materials and labours	166.05	One Sqmt	Rs. 68.60	11390.54
16	Wall painting two coats with weather coat with cost of materials and labours	527.63	One Sqmt	Rs. 77.90	41102.10
17	Painting two coats over a coat of primer inluding cost of primer and	23.41	One Sqmt	Rs. 203.53	4764.60

  
 15.11.22  
**Asst. Executive Engineer**  
**Patna Block**

  
 15.11.22  
**Block Development Officer**  
**PATNA, KEOJHAR**

18	Fixing ceramic tiles in floor over thick bed of cement mortar 1:1 including rubbing and polishing excluding cost of tiles	55.07	One Sqmt	Rs. 908.34	50022.28
19	Fixing ceramic tiles in dados and riser of steps on 12 mm thick cement plaster (1:3) including rubbing and polishing excluding	83.65	One Sqmt	Rs. 1,025.59	85790.60
20	Cost of M.S.Door, Windows	245.00	One Sqmt	Rs. 102.00	24990.00
21	cost door	4	nos	Rs. 5,000.0	20000.00
22	Provision of Steel Hand rail 6m				12621.00

TOTAL = 1491525.93

**say = 1491526.00**

(RUPEES FORTEEN LAKHS NINTY ONE THOUSAND FIVE HUNDRED TWENTY SIX ONLY )

Tender schedule for the project:--CONSTRUCTION OF ONE NO , TOILET AND BOUNDARY WALL AT PALANGATHI HIGH SCHOOL PALANGHATI approved for Rs.1491526/- (RUPEES FORTEEN LAKHS NINTY ONE THOUSAND FIVE HUNDRED TWENTY SIX ONLY ) with 22 (TWENTY TWO ) item only.

Add for G.S.T cost 18% (CGST9%+SGST 9%) will be added at the time of agreement .

  
15.11.22

Asst. Executive Engineer  
Patna Block

  
15.11.22

Block Development Officer  
Patna Block

  
16/11/22

Executive Engineer  
DRDA,Keonjhar

My / Our quoted rate is ..... % Excess / Less /

(write both in words and figures )

**NOTES:-**

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less without treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

**Signature of the Contractor  
with address.**