

## TENDER SCHEDULE

CONSTRUCTION OF THREE NOS ADDITIONAL CLASS ROOM AT B.K.P HIGH SCHOOL CHAKUNDAPAL		AMOUNT PUT TO TENDER :- RS :- 3225407.00			
		CLASS OF CONTRACTOR :- B & C			
		COST OF TENDER PAPER :- RS. 6000.00			
		E.M.D : bid declaration			
		TIME OF COMPLETION : 6 MONTHS			
Sl No.	ITEM OF WORK	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	E/W in excavation of foundation in hardsoil within initial lead & lift including levelling and dressing the bed complete.	141.78	One cum	Rs. 195.38	27700.98
2	Filling F & P with sand well watered and rammed complete.	108.86	One cum	Rs. 461.96	50288.97
3	C.C.(1:3:6) with using 40mm.size h.b.g. metal complete.	57.82	One cum	Rs. 4,403.57	254614.42
4	Brick work with Fly ash.Bricks in cement mortar (1:6) in Fdn & Pl of size 10"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and sim in Foundation & Plinth	64.49	One cum	Rs. 4,649.47	299844.32
5	RCC M-20 work with 20mm & down graded cbhg chips including all cost carriage royalty etc.complete.	89.33	One cum	Rs. 4,737.92	423238.39
6	Supplying fitting and placing uncoated HYSD Bar reinforcement complete as per drawing and technical specification and placing in proper position as required for RCC work including cost, conveyance, taxes of steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc. complete in all respect in all floors a per direction of Engineer-in-charge.	89.33	One Qntl	Rs. 8,355.45	746392.35
7	Brick work with Fly ash.Bricks in cement mortar (1:6) in superstructure of size 10"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and sim in superstructure	53.99	One cum	Rs. 4,682.80	252824.37
8	Rigid smooth centring, shuttering for R.C.C. works including falseworks and dismantling them after casting.				
	Plinth Bend	50.07	One Sqmt	Rs. 114.75	5745.53
	B) Lintel Bend :-	35.03	One Sqmt	Rs. 270.04	9459.50
	C) Column & Beam:-	151.94	One Sqmt	Rs. 764.02	116085.20
	D) Roof Slab & Chajja :-	257.87	One Sqmt	Rs. 452.66	116727.43
9	20 mm thick cement plaster 1:4 for Grading Plaster	223.38	One Sqmt	Rs. 233.68	52199.44
10	16mm.thick Cement Plaster in C.M. (1:6) over Brick work complete.	406.53	One Sqmt	Rs. 219.41	89196.75
11	12mm.thick Cement Plaster in C.M. (1:6) over Brick work complete	178.42	One Sqmt	Rs. 142.49	25423.07
12	6 mm thick cement plaster (1:4) over concrete work finished smooth including closed deep chipping and slury treatment.	257.85	One Sqmt	Rs. 158.77	40938.84
13	Fixing vetrified tiles (600 X 600 ) in floor over thick bed of cement mortar 1:1 including rubbing and polishing excluding cost of tiles	243.70	One Sqmt	Rs. 1,129.43	275242.09
14	Fixing vetrified tiles (600 X 600 ) in dados and riser of steps on 12 mm thick cement plaster (1:3) including rubbing and	30.25	One Sqmt	Rs. 1,234.33	37338.62
15	finishing wall with accrlic wall putty	664.38	One Sqmt	Rs. 92.20	61255.84
16	Painting two coats over a coat of primer including cost of primer and	59.64	One Sqmt	Rs. 203.53	12138.53
17	Priming one coat over plaster surface with water bound cement primer with cost of all material	842.80	One Sqmt	Rs. 67.99	57301.97
18	Wall painting two coats with distemper paint with cost of materials and labours	664.38	One Sqmt	Rs. 68.60	45576.47

*[Signature]*  
15.11.22

**Asst. Executive Engineer  
Patna Block**

*[Signature]*  
15.11.22  
Block Development Officer  
PATNA, KEOUNJAR


19	Wall painting two coats with weather coat with cost of materials and labours	178.42	One Sqmt	Rs. 77.90	13898.92
20	Cost of M.S.Door, Windows	1020.00	One Sqmt	Rs. 102.00	104040.00
21	providing fixing AL window sliding types	10.03	One Sqmt	Rs. 6,230.71	62494.02
22	Add Provision for cost & supply of ventilator	12.00	nos	Rs. 100.00	1200.00
23	Add Provision for Cost hand rail ( S.Steel) 11.00m	1.00	no	Rs. 33,241.00	33241.00
24	display board (5'0"x4'0")	1.00	no	Rs. 5,000.00	5000.00
25	Provision for Black Board (8'0"x4'0")	3.00	nos	Rs. 2,000.00	6000.00
<b>TOTAL</b>				<b>=</b>	<b>3225407.02</b>
<b>say</b>				<b>=</b>	<b>3225407.00</b>

(RUPEES THIRTY TWO LAKHS TWENTYFIVE THOUSAND FOUR HUNDRED SEVEN) ONLY

Tender schedule for the project:--CONSTRUCTION OF THREE NOS ADDITIONAL CLASS ROOM AT B.K.P HIGH SCHOOL CHAKUNDAPAL approved for Rs.3225407/- (RUPEES THIRTY TWO LAKHS TWENTYFIVE THOUSAND FOUR HUNDRED SEVEN) ONLY with 25 (Twentyfive ) Item only.

Add for G.S.T cost 18% (CGST9%+SGST 9%) will be added at the time of agreement .

  
15.11.22  
Asst. Executive Engineer  
Patna Block

  
15.11.22  
Block Development Officer  
Patna Block

  
16/11/22  
Executive Engineer  
DRDA,Keonjhar

My / Our quoted rate is ..... % Excess / Less /  
Equal to the corresponding estimate rate

(write both in words and figures )

NOTES:-

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less without treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.