

APPROVED TENDER SCHEDULE

Name of the work: -Construction of GP Level Federation (GPLF) Building at kendeiposi		Amount put to tender:Rs 11,10,721/-			
		Class of contractor: D & C			
		Cost of Tender Paper : Rs. 6,000/-			
		Earnest money Deposit - Bid declaration.			
		Time of Completion: 4months			
St. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	52.72	195.38	10300.43
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	40.30	373.08	15035.12
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	11.68	4056.65	47381.67
4	Reinforcement cement concrete M-20 grade with 20 mm nominal size down graded nominal size aggregate mechanically mixed and vibrated in foundation and bed protection of speciation for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the engineering-in-charge.	Cum	30.33	4723.76	143271.64
5	Rigid smooth centering and shuttering for Rcc works including false works and dismantling them after casting including cost of all materials complete as per the direction of the Engineering-in-charge				
	(a)Column & Beam	Sqm	56.35	764.02	43052.53
	(b) Lintel	Sqm	17.90	270.02	4833.36
	(c) Roof slab & chajja	Sqm	78.35	452.66	35465.91
6	Fly ash brick masonry in CM(1:6) in foundation and plinth with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	20.25	4646.70	94095.68
7	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	20.73	4680.03	97017.02
8	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specifaicon as directed by the engineering-in-charge.	Qtl	27.30	8339.36	227664.53


 Asst. Executive Engineer
 Patna Block
 PATNA, BIHAR

9	12 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	105.81	142.34	15061.00
10	16 mm thick cement plaster in C.M. (1:6) finishing smooth to inner side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	79.23	218.94	17346.62
11	20 mm thick cement plaster in C.M. (1:4) for Grading plaster including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	84.74	238.94	20247.78
12	20 mm thick cement plaster in C.M. (1:6) finished smooth over brick masonry after ranking out joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	21.80	227.28	4954.70
13	12 mm thick ceiling cement plaster in C.M. (1:4) to Rcc surface including all cost conveyance royalty etc complete	Sqm	76.80	153.36	11778.05
14	Fixing tiles in floors ,treads and landings on 25 mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	68.23	1107.36	75555.17
15	Fixing tiles in dados ,skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	9.70	1236.24	11991.53
16	Fixing Ceramic tiles in dados ,skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	12.03	1056.11	12705.00
17	Painting two coats in all Doors and windows (two coats with paint of approved shade and base coat with primer to new wood and iron work including all labour and T&P etc.	Sqm	73.69	203.53	14998.13
18	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of disteper	Sqm	156.03	68.60	10703.66
19	Providing and finishing inside wall surface with acrylic putty (water based)	Sqm	156.03	85.12	13281.27
20	Providing and applying paint over external plastered surfaces with 2 coats of plastic emulsion paint of approved quality and shade using the required quantity of paint	Sqm	156.03	79.42	12391.90
21	Providing and applying paint over external plastered surfaces with 1 coat of primer of approved quality .	Sqm	127.61	67.99	8676.20
22	Providing and applying paint over external plastered surfaces with 2 coats of weather coat of approved quality and shade using the required quantity of paint	Sqm	127.61	77.90	9940.82
23	Supplyin, fitting of and fixing MS Grill, window& door etc of approved quality and make including cost of all materials and labour for fixing in position ,conveyance,taxes,and all respect as directed by the Engineering in- charge	kg	1442.04	104.00	149972.16
24	Display Board				3000.00
		Grand	Total Rs		1110721.88

Say Rs 11,10,721.00

(Rupees eleven lakhs ten thousand seven hundred twenty one)only


Asst. Executive Engineer
Patna Block


20/07/2024
PATNA, K.BONJHAR

Tender schedule for the project:-Const. of Gp Level Federation (GPLF) Building at Kendeiposi, Under Kendeiposi GP
Patna Block is approved for RS 11,10,721/- (Rupees eleven lakhs ten thousand seven hundred twenty
one) only with 24 (twenty four) items only.

G.S.T. cost in 18% (CGST9% +SGST9%) will be added at the time of agreement.


Asst. Executive Engineer
Patna


Block Development Officer
Patna


Addl. Executive Officer(Tech)
Zillaparishad,Keonjhar

My /Our quoted rate is ----- % Excess/Less/Equal
to the corresponding estimate rate
(Write both in words and Figures)

NOTES:-

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor
with address.