

TENDER SCHEDULE

CONSTRUCTION OF ONE NO OF SCIENCE LAB ROOM AT DINDAPAT HIGH SCHOOL BHULUDA		AMOUNT PUT TO TENDER :- RS.1492720.00			
		CLASS OF CONTRACTOR :- D & C			
		COST OF TENDER PAPER :- RS. 6000.00 <i>6000/-</i>			
		E.M.D ; bid declaration			
		TIME OF COMPLETION :- 4 MONTHS			
SI No.	ITEM OF WORK	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	E/W in excavation of foundation in hardsoil within initial lead & lift including levelling and dressing the bed complete.	55.53	One cum	Rs. 195.38	10849.45
2	Filling F & P with sand well watered and rammed complete.	49.79	One cum	Rs. 461.96	23000.99
3	Cement concrete (1:4:8) with 4cm size H.G.C.B. metal including all cost carriage royalty etc.complete	18.88	One cum	Rs. 4,063.94	76727.12
4	Brick work with Fly ash.Bricks in cement mortar (1:6) in Fdn & Pl of size 10"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and sim in Foundation & Plinth	14.55	One cum	Rs. 4,649.47	67649.79
5	RCC M-20 work with 20mm & down graded cbhg chips including all cost carriage royalty etc.complete.	42.35	One cum	Rs. 4,737.92	200650.91
6	Copying, tying and placing uncoated iron bar reinforcement complete as per drawing and technical specification and placing in proper position as required for RCC work including cost, conveyance, taxes of steel and cost of binding wire 18 to 20 gauge and labour with T&P required for the work etc. complete in all aspect in all floor	42.35	One Qntl	Rs. 8,355.45	353853.31
7	Fly-ash Brick work in C.M.(1:6) in superstructure	28.96	One cum	Rs. 4,682.80	135613.86
8	Rigid smooth centring, shuttering for R.C.C. works including falseworks				
	Plinth Bend	26.03	One Sqmt	Rs. 114.75	2986.94
	B) Lintel Bend :-	18.27	One Sqmt	Rs. 270.04	4933.63
	C) Column & Beam:-	88.87	One Sqmt	Rs. 764.02	67898.46
	D) Roof Slab & Chajja :-	126.53	One Sqmt	Rs. 452.66	57275.07
9	20 mm thick cement plaster 1:6	113.15	One Sqmt	Rs. 233.68	26440.88
10	16mm thick cement plaster (1:6) finished smooth to inside rough surface of brick walls after racking out the joint including watering and curing with cost and conveyance, royalties and taxes of all materials and labour charges required fo	121.14	One Sqmt	Rs. 219.41	26578.72
11	12mm thick cement plaster (1:6) finishing smooth to outside smooth surface of brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for	258.29	One Sqmt	Rs. 142.49	36803.74
12	6mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	105.16	One Sqmt	Rs. 158.77	16696.57
13	Fixing tiles in floor over thick bed of cement mortar 1:1 including rubbing and polishing excluding cost of tiles	108.76	One Sqmt	Rs. 1,129.43	122837.01
14	Fixing tiles in dados and riser of steps on 12 mm thick cement plaster (1:3) including rubbing and polishing excluding	48.09	One Sqmt	Rs. 1,246.68	59952.84
15	Fixing granite in top of the Lab table over thick bed of cement mortar 1:1 including rubbing and polishing including cost of granite (20mm thick)	15.61	One Sqmt	Rs. 2,355.94	36776.27
16	Cement washing 1coats etc. complete	484.6	One Sqmt	Rs. 14.38	6969.43
17	Priming one coat over plaster surface with water bound cement primer with cost of all material	484.6	One Sqmt	Rs. 67.99	32949.91
18	Wall painting two coats with distemper paint with cost of materials and labours	226.30	One Sqmt	Rs. 68.60	15523.51

[Signature]
15.11.22
Asst. Executive Engineer
Patna Block

[Signature]
15.11.22
Block Development Officer
PATNA, KUNJHAR


19	Wall painting two coats with weather coat with cost of materials and labours	258.29	One Sqmt	Rs. 77.90	20120.66
20	Painting two coats over a coat of primer including cost of primer and	36.23	One Sqmt	Rs. 203.53	7374.65
21	Cost of M.S.Door, Windows	628.00	One Sqmt	Rs. 102.00	64056.00
22	Provision of Steel Hand rail	1.00	one	Rs.15,000.00	15000.00
23	Supplying and fixing of ventilators (L.S) 12 NOS @ Rs. 100.00	12.00	nos	Rs. 100.00	1200.00
24	Provision for Black Board	1.00	nos	Rs. 2,000.00	2000.00

TOTAL = 1492719.71
say = **1492720.00**


(RUPEES FOURTEEN LAKHS NINETY TWO THOUSAND SEVEN HUNDRED TWENTY ONLY)

Tender schedule for the project:--CONSTRUCTION OF ONE NO OF SCIENCE LAB ROOM AT DINDAPAT HIGH SCHOOL BHULUDA approved for Rs.1492720/- (RUPEES FOURTEEN LAKHS NINETY TWO THOUSAND SEVEN HUNDRED TWENTY ONLY) with 24 (Twenty four) item only.

Add for G.S.T cost 18% (CGST9%+SGST 9%) will be added at the time of agreement .



Asst. Executive Engineer
Patna Block



Block Development Officer
Patna Block



Executive Engineer
DRDA,Keonjhar

My / Our quoted rate is % Excess / Less /

(write both in words and figures)

NOTES:-

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less without treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

**Signature of the Contractor
with address.**