

APPROVED TENDER SCHEDULE (BOR)


Name of the work: -Construction of one no. of science laboratory and construction of one no. of e library at L.N High school Chinamaliposi		Amount put to tender:Rs 2545508/-			
		Class of contractor: C & B			
		Cost of Tender Paper : Rs. 6,000/-			
		Earnest money Deposit - Bid declaration.			
		Time of Completion: 6 months <i>Six months</i>			
Sl. No.	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	104.48	195.38	20413.30
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	112.52	373.08	41978.96
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	37.25	3825.07	142483.86
4	RRHG Stone masonry (1:6) in Foundation and plinth with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	45.35	3293.97	149381.54
5	Reinforcement cement concrete M-20 grade with 20 mm nominal size down graded nominal size aggregate mechanically mixed and vibrated in foundation and bed protection of speciation for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the engineering-in-charge.	Cum	69.45	4738.00	329054.10
6	Rigid smooth centering and shuttering for Rcc works including false works and dismantling them after casting including cost of all materials complete as per the direction of the Engineering-in-charge				
	(a) Column & Beam	Sqm	175.43	764.02	134032.03
	(b) Lintel	Sqm	37.91	270.04	10237.22
	(c) Roof slab & chajja	Sqm	201.04	452.66	91002.77


[Signature]
15.11.22
A.E.E.(P)

**Asst. Executive Engineer
Patna Block**

[Signature]
15.11.22
**Block Development Officer
PATNA, KATNIHAR**

7	Fly ash brick masonry in CM(1:6) in foundation and plinth with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	7.00	4649.48	32546.36
8	Fly ash brick masonry in CM(1:6) in superstructure with using good quality flyash brick of size (25x12x8)cm having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.	Cum	42.32	4682.81	198176.52
9	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specificalton as directed by the engineering-in-charge.	Qti	69.45	8347.64	579743.60
10	12 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	240.30	142.49	34240.35
11	16 mm thick cement plaster in C.M. (1:6) finishing smooth to inner side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	240.30	219.41	52724.22
12	20 mm thick cement plaster in C.M. (1:4) for Grading plaster including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed byl ineering-in-charge.	Sqm	191.15	233.68	44667.93
13	20 mm thick cement plaster in C.M. (1:6) finished smooth over brick masonry after ranking out joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed byl ineering-in-charge.	Sqm	58.77	223.31	13123.93
14	12 mm thick ceiling cement plaster in C.M. (1:4) to Rcc surface in cluding all cost conveyance royalty etc complete	Sqm	220.64	136.49	30115.15
15	Fixing vetried tiles (600mmx600mm) in floors ,treads and landings on 25 mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	181.64	1129.44	205151.48
16	Fixing tiles in dados ,skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	19.87	1246.68	24771.53



 15.11.22
 Asst. Executive Engineer
 Patna Block



 15.11.22
 Block Development Officer
 PATNA, KEONJHAR

17	Fixing granite tiles in top of the lab table over 25 mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	Sqmt	15.75	2405.79	37891.19
18	Painting two coats in all Doors and windows (two coats with paint s of approved shade and base coat with primer to new wood and iron work including all labour and T&P etc.	Sqm	72.46	203.53	14747.78
19	Cement washing one coat including cost conveyance and taxes asper the direction of the Engineer in charge.	Sqm	731.43	14.38	10517.96
20	Distemping two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper	Sqm	442.98	68.60	30388.43
21	wall priming one coat asper the direction of the Engineer in charge	Sqm	731.43	67.99	49729.93
22	Providing and applying paint over external plastered surfaces with 2 coats of weather coat of approved quality and shade using the required quantity of paint	Sqm	288.45	77.90	22470.26
23	Supplyin, fitting of and fixing MS Grill, window& door etc of approved quality and make including cost of all materials and labourfor fixing in position ,conveyance,taxes,and all respect as directed by the Engineering in- charge	kg	1351.60	105.00	141918.00
24	Provision for Ventilator	nos	20.00	100.00	2000.00
25	Provision for Stainless steel Handrails	nos	2.00	22500.00	45000.00
26	Provision for construction of Black Board (8 ft x 4 ft)	nos	2.00	2000.00	4000.00
27	Provision for Rechargepit of roof top water harvesting & sludge pit size(4'-0"x4'-0"x4'-0") with cover slab connected with 4" PVC pipe with fitting asper the direction of the Engineer incharge.	nos	3.00	15000.00	45000.00
28	Provision for Display Board and working platform(4ft x5ft)				8000.00
			Grand	Total Rs	2545508.40
					Say Rs 2545508.00
(Rupees tewnty five lakhs forty five thousand five hundred eight)only					

Tender schedule for the project:-Const. of one no. of science laboratory and construction of one no. of e library at L.N High school Chinamaliposi , Under Chinamaliposi GP ,Patna Block is approved for RS 2545508/- (Rupees twenty five lakhs forty five thousand five hundred eight) only with 28 (twenty eight) items only.

G.S.T.cost in 18% (CGST9% +SGST9%) will be added at the time of agreement.


Asst. Executive Engineer
Patna


Block Development Officer
Patna


Addl. Executive Officer (Tech)
Zillaparishad,Keonjhar

My /Our quoted rate is ----- % Excess/Less/Equal
to the corresponding estimate rate
(Write both in words and Figures)

NOTES:-

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor
with address.