

BILL OF QUANTITY (BOQ)

NAME OF THE WORK: - Construction of Boundary wall at Hatisila UGHS.

Amount put to Tender	:	Rs.13,75,002.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date of sale of Tender Paper	:	14.12.2022 to 28.12.2022 up to 1.00P.M.
Date of Receipt of Tender Paper	:	28.12.2022 up to 5.00 P.M.
Date of Opening of Tender	:	29.12.2022
Date required for completion	:	4(Four) calendar Month

SI No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	106.75	Each cum	195.40	20858.00
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	62.30	Each cum	715.57	44580.00
3	P.C.C. (1:3:6) using 40 mm & down size b.h.g.c.b chips including watering, curing with cost, direction of Engineer-in-Charge.	17.62	Each cum	4987.03	87871.00
4	R.C.C. M20 using 20 mm & down size b.h.g.c.b chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	12.87	Each cum	5692.39	73261.00
5	Straightening, Cutting, Bending, binding of M.S rod/TOR steel and tying up the grills and placing in position including cost of binding wire with all cost conveyance, taxes etc completed in all respect as per the direction of Engineer-in-Charge.	11.583	Each Qntl	8570.50	99272.00
6	Fly Ash Brick masonry with CM (1:6) in foundation including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	46.78	Each Cum	4209.70	196929.00
7	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	104.37	Each Cum	4243.10	442852.00
8	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	509.81	Each Sqmt	151.20	77083.00

9	16mm thick C.P. (1:6) Including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	667.50	Each Sqmt	230.00	153525.00
10	Priming one coat with any approved primer over plastered surface	1177.31	Each Sqmt	60.27	70956.00
11	Weather Coat painting two coat to wall with distemper of approved shade on new work to glve an even shade including cost of all materials and labour (T&P) etc. complete.GF	1177.31	Each Sqmt	90.40	106428.00
12	Display Board writing	1	no	1411.00	1411.00
				TOTAL	1375026.00

OR SAY 1375002.00


(Rupees Thirteen Lakh Seventy Five Thousand Two) Only.

18% GST will be added at the time of aggrement over the quoted amount.

TOTAL 12 (Twelve) NOS ITEM ONLY

Approved for 12(Twelve) items only


Asst. Exe. Engineer
Banspal Block


B.D.O.
Banspal


Addl. Exicutive Officer Tech.
Zilla Parishada Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our qouted rate is (both in figure and words)

Equal to Estimate Cost
Excess in Percentage
Less in Percentage

In Figure

In words

	%	
	%	
	%	


Notes:-

- 1) The Tenderer should qoute the percentage up to one decimal point only. tendering .
- 3) The Tenderers should qouted their percentage only inside the space provided for the purpose .
- 4) The percentage qouted at any other place will not be taken into consideration.

OFFICE USE ONLY

payment of RS.....only per set vide money receipt No..... Book

EMD: Rs..... In shape of
Regisration certificate furnished / not furnished
STCC (GSTIN) furnished / not furnished
ITCC (Pan Card) furnished / not furnished
No of Correction
No of over writing
No of Interpolation.....


Block Development Officer
Banspal Block

