

**BILL OF QUANTITY (BOQ)**

NAME OF THE WORK: - Construction of Addl. Class room at Taramakant H/S

Amount put to Tender	:	Rs.10,82,765.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date of sale of Tender Paper	:	14.12.2022 to 28.12.2022 up to 1.00P.M.
Date of Receipt of Tender Paper	:	28.12.2022 up to 5.00 P.M.
Date of Opening of Tender	:	29.12.2022
Date required for completion	:	6(Six) calendar Month

Sl No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	50.16	Each cum	195.40	9801.00
2	Supplying and filling foundation and plinth with sand well watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	67.60	Each cum	872.63	58989.00
3	P.C.C. (1:3:6) using 40 mm & down size b.h.g.c.b chips including watering, curing with cost, direction of Engineer-in-Charge.	17.64	Each Cum	5038.02	88870.00
4	R.C.C. M20 using 20 mm & down size b.h.g.c.b chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				
	A.Column Base(Footing)	7.03	Each Cum	5180.90	36421.00
	B.Plinth beam	2.98	Each Cum	5753.40	17145.00
	C.Column and Beams(G.F)	8.22	Each Cum	11244.20	92427.00
	E.Sill band(G.F)	1.80	Each Cum	9016.60	16229.00
	F.Roof Slab(G.F)	10.30	Each Cum	9613.10	99014.00
5	Straightening, Cutting, Bending, binding of M.S rod/TOR steels and tying up the grills and placing in position including cost of binding wire with all cost conveyance, taxes etc completed in all respect as per the direction of Engineer-in-Charge.(GF)	27.33	Each Qntl	8588.00	234710.00
6	Fly Ash Brick masonry with CM (1:6) in foundation including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	12.32	Each Cum	4372.50	53869.00

	Fly Ash Brick masonry with CM (1:6) In superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				
A	Ground Floor	20.34	Each Cum	4405.80	89613.00
8	20mm thick Grading Plaster (1:4) over roof slabs including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	83.00	Each Sqmt	245.10	20343.00
9	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.(GF)	146.20	Each Sqmt	153.90	22500.00
10	16mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	91.46	Each Sqmt	233.30	21337.00
11	Priming one coat with approved primer over plastered surface with cost of primer and labour(GF)	324.92	Each Sqmt	60.27	19582.00
12	Distemping two coats to walls with distemper of approved shade on new work to give an shade excluding cost of distemper per one sqm. Data for 10 sqm.	91.46	Each Sqmt	65.30	5972.00
13	Weather Coat painting two coat to wall with distemper of approved shade on new work to give an even shade including cost of all materials and labour (T&P) etc. complete.GF	324.92	Each Sqmt	90.40	29372.00
14	Providing, fitting, fixing of M.S. Door / Window / Grill gates made out of M.S. Angle, flat, sheet etc. including cost, conveyance, taxes of all materials and labour (T&P) etc. complete.	330.78	Per Kg	147.20	48690.00
15	Painting two coats with any approved on new wood work/iron work with all cost of material and labour, T&P etc.	23.69	Each Sqmt	194.40	4605.00
16	Providing, supplying, fitting, fixing of Vetrified tiles on floors on 25mm bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shade including cost, conveyance, royalty and taxes of all materials and labour etc. complete.	70.73	Each Sqmt	1258.10	88985.00
17	Providing, supplying, fitting, fixing of Vetrified tiles on Dadoos & Skitting on 12mm bed of cement mortar (1:3) jointed with neat cement slurry mixed with pigment to match the shade including cost, conveyance, royalty and taxes of all materials and labour etc. complete.	5.72	Each Sqmt	1109.10	6344.00
18	Fixing tiles in dados skirting and riser of steps on 12 mm thick cement plaster 1:3 jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles per 1sqm(Chequered tiles to ramp)	13.55	Each Sqmt	953.6	12921.00

19	25mm thick A.S. Flooring with C.C.(1:2:4) over metal concrete including cost, conveyance, royalty and all taxes of materials and labour etc	17.42	Each Sqmt	288.54	5026.00
				TOTAL	1082765.00

(Rupees Ten Lakh Eighty Two Thousand Seven hundred Sixty Five) Only.

**18% GST will be added at the time of aggrement over the quoted amount.**

TOTAL 19 (Nineteen) NOS ITEM ONLY

*Bardi*  
09/12/2022  
Asst. Exe. Engineer  
Banspal Block

Approved for 19(Nineteen) items only  
*[Signature]*  
12/12/2022  
B.D.O.  
Banspal  
Addl. Exicutive Officer Tech.  
Zilla Parishada Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only. tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**OFFICE USE ONLY**

payment of RS.....only per set vide money receipt No.....

EMD: Rs..... In shape of  
Regisration certificate furnished / not furnished  
STCC (GSTIN) furnished / not furnished  
ITCC (Pan Card) furnished / not furnished  
No of Correction .....

No of over writing .....

No of Interpolation.....

*[Signature]*  
12/12/2022  
Block Development Officer  
Banspal Block