

**BILL OF QUANTITY (BOQ)**

**NAME OF THE WORK: - Construction of Boundary wall at Talakainsari U.G. High school**

Amount put to Tender	:	Rs.17,28,542.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.6000.00
Date of sale of Tender Paper	:	14.12.2022 to 28.12.2022 up to 1.00P.M.
Date of Receipt of Tender Paper	:	28.12.2022 up to 5.00 P.M.
Date of Opening of Tender	:	29.12.2022
Date required for completion	:	4(Four) calender Month

Sl No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	139.18	Each cum	195.40	27195.00
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	81.22	Each cum	715.57	58118.00
3	P.C.C. (1:2:4) using 12 mm & down size b.h.g.c.b chips including watering, curing with cost, direction of Engineer-in-Charge.	22.977	Each cum	4987.03	114586.00
4	R.C.C. M20 using 20 mm & down size b.h.g.c.b chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	16.77	Each cum	5692.39	95461.00
5	Straightening, Cutting, Bending, binding of M.S rod/TOR steel and tying up the grills and placing in position including cost of binding wire with all cost conveyance, taxes etc completed in all respect as per the direction of Engineer-in-Charge.	15.09	Each Qntl	8570.50	129328.00
6	Fly Ash Brick masonry with CM (1:6) in foundation including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	60.99	Each Cum	4209.70	256749.00
7	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	136.10	Each Cum	4243.10	577485.00
8	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	573.47	Each Sqmt	151.20	86708.00

9	16mm thick C.P. (1:6) Including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	779.15	Each Sqmt	230.00	179204.00
10	Priming one coat with any approved primer over plastered surface	1352.02	Each Sqmt	60.27	81486.00
11	Plastic emulsion two coats with priming over wall surface with any approved shade Including cost of all materials and labour (T&P) etc. complete.	1352.02	Each Sqmt	90.40	122222.00
				TOTAL	17,28,542.00

(Rupees Seventeen Lakh Twenty Eight Thousand Five Hundred Forty Two)Only

**18% GST will be added at the time of agreement over the quoted amount.**

TOTAL 11 (Eleven) NOS ITEM ONLY

  
Asst. Exp. Engineer  
Banspal Block

Approved for 11(Eleven) items only

  
B.D.O.  
Banspal

  
Addl. Exicutive Officer Tech.  
Zilla Parishada Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

**Notes:-**

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**OFFICE USE ONLY**

Sold for the work : Construction of Labour Room at Suakati PHC under Banspal Block. FOR THE YEAR 2020-21 on payment of RS.....only per set vide money receipt  
No..... Book No..... Dt.....

EMD: Rs..... In shape of  
Regisration certificate furnished / not furnished  
STCC (GSTIN) furnished / not furnished  
ITCC (Pan Card) furnished / not furnished  
No of Correction .....

No of over writing .....

No of Interpolation.....

  
Block Development Officer  
Banspal Block

