

BILL OF QUANTITY (BOQ)**NAME OF THE WORK: - Construction of Boundary wall at GPB High school Karangadihi**

Amount put to Tender	:	Rs. 8,56,538.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.4000.00
Date of sale of Tender Paper	:	14.12.2022 to 28.12.2022 up to 1.00P.M.
Date of Receipt of Tender Paper	:	28.12.2022 up to 5.00 P.M.
Date of Opening of Tender	:	29.12.2022
Date required for completion	:	4(Four) calender Month

SI No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	60.99	Each cum	195.40	11917.00
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	35.59	Each cum	734.42	26138.00
3	P.C.C. (1:3:6) using 40 mm & down size b.h.g.c.b chips including watering, curing with cost, direction of Engineer-in-Charge.	15.25	Each cum	4868.39	74242.00
4	R.C.C. M20 using 20 mm & down size b.h.g.c.b chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	7.35	Each cum	5577.85	40997.00
5	Straightening, Cutting, Bending, binding of M.S rod/TOR steel and tying up the grills and placing in position including cost of binding wire with all cost conveyance, taxes etc completed in all respect as per the direction of Engineer-in-Charge.	8.83	Each Qntl	8460.10	74702.00
6	Fly Ash Brick masonry with CM (1:6) in foundation including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	35.62	Each Cum	4262.40	151826.00
7	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	65.41	Each Cum	4295.80	280988.00
8	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	291.35	Each Sqmt	152.50	44430.00
9	16mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	381.44	Each Sqmt	231.50	88303.00
10	Priming one coat with any approved primer over plastered surface	672.80	Each Sqmt	60.27	40549.00

11	Finishing walls with water proofing cement paint of approved shade on new work two coats to give an even shade including cost of paint	672.80	Each Sqmt	33.40	22471.00
				TOTAL	856563.00

OR SAY 856538.00

(Rupees Eight Lakh Fifty Six thousand Five hundred Thirty Eight)

18% GST will be added at the time of aggrement over the quoted amount.

TOTAL 11 (Eleven) NOS ITEM ONLY

Approved for 11(Eleven) items only

[Signature]
09/12/2022
Asst. Exe. Engineer
Banspal Block

[Signature]
12/12/2022
B.D.O.
Banspal

[Signature]
12/12/2022
Addl. Exlcutive Officer Tech.
Zilla Parishada Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The Tenderer should quote the percentage up to one decimal point only. tendering .
- 3) The Tenderers should quoted their percentage only inside the space provided for the perpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

OFFICE USE ONLY

payment of RS.....only per set vide money receipt No.....

EMD: Rs..... In shape of
Regisration certificate furnished / not furnished
STCC (GSTIN) furnished / not furnished
ITCC (Pan Card) furnished / not furnished
No of Correction

No of over writing

No of Interpolation.....

[Signature]
12/12/2022
Block Development Officer
Banspal Block