

9	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials				
a	Column Base	cum	28.20	4993.64	140835.15
b	Column & Beam	cum	24.37	10791.21	262992.92
c	(C-2)Column for 1st floor	cum	20.92	12067.15	252404.42
	Colm (2nd floor)	cum	2.42	13594.59	32890.30
d	Plinth Beam	cum	16.76	4839.00	81193.37
	Plinth Beam(boundary toilet)	cum	0.00	5354.52	0.00
e	Lintel Band	cum	10.41	8585.37	89394.39
e1	(E) Lintel band 1st floor	cum	10.41	9420.15	98086.41
f	ChhajaGround floor	cum	38.50	779.45	30010.59
f1	Chajja 1st floor	cum	38.50	880.24	33891.07
g	SlabGround floor	cum	39.16	9175.47	359334.59
g1	Slab First floor	cum	39.16	10128.75	396667.28
g2	Slab (2nd floor)	cum	3.77	11268.39	42492.81
h	RCC Stair(Ground floor)	cum	2.91	10317.27	29993.88
	RCC Stair (1ST floor)	cum	2.91	11498.35	33427.45
10	Straightening bent up or coiled M.S. rod or HYSD steel (Fe 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete	qtl	168.35	8516.11	1433721.21
11	Straightening bent up or coiled M.S. rod or HYSD steel (Fe 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and	qtl	106.31	8540.24	907878.17
12	Straightening of M.S rod for 2nd floor	qtl	5.70	8565.58	48781.96
13	Supplying fitting and fixing of M.S Door and windows	kg	3136.00	112.09	351522.60

14	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	sqm	440.65	203.50	89672.17
15	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges 1ST FLOOR.	sqm	470.14	208.50	98024.31
16	2nd floor Parapet	sqm	233.41	213.60	49855.67
17	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	sqm	351.88	142.80	50245.94
18	12MM thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges req(1ST FLOOR)	sqm	333.62	148.37	49499.59
19	12MM thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges req(2ND FLOOR)	sqm	38.35	154.25	5916.21
20	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	sqm	334.45	157.90	52810.40
21	6mm thick cement plaster(1:4) to RCC Surface(1ST FLOOR)	sqm	334.45	181.80	54114.77
22	2.5C.M grading concrete(1:2:2)(2nd floor)	sqm	344.31	326.50	112417.26
23	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. in 3 rows in stair case	rm	33.54	3466.00	116237.80
24	Supplying ,fitting and fixing vetrified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved qual	rm	342.16	980.43	335465.41
25	supplying,fitting and fixing of vetrified tiles in floors,treads or stepsetc(1ST FLOOR)	rm	321.72	990.39	318632.54
26	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ Iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	sqm	120.40	196.40	23646.25
27	Supplying,fitting and fixing of Chequered tile	sqm	39.48	810.70	32008.46

28	Painting two coats with syntetic enamel paint to door and windows(1ST FLOOR)	sqm	120.40	201.45	24254.26
29	Supplying and applying of primer over putty surface	sqm	1126.97	56.10	63222.82
30	Finishing wall surface with primer(1st floor)	sqm	1126.97	57.55	64856.92
31	Finishing wall surface with putty(GROUND FLOOR)	sqm	714.60	85.30	60955.54
32	Finishing wall surface with putty(1ST FLOOR)	sqm	714.60	86.66	61926.46
33	Finishing wall surface with cementwash(GROUND FLOOR)	sqm	915.12	21.60	19766.69
34	Finishing wallsurface with cementwash(1ST FLOOR)	sqm	915.12	21.90	20041.23
35	Aplying plastic emulsion paint(GROUND FLOOR)	sqm	714.60	78.10	55810.41
36	Aplying plastic emulsion paint(FIRST FLOOR)	sqm	714.60	79.70	56953.77
37	Wall painting twocoats to weather coat(GROUND FLOOR)	sqm	426.18	72.50	30898.36
38	Wall painting twocoats to weather coat(1ST FLOOR)	sqm	396.17	75.10	29752.27
				TOTAL RS	8127147.16
				TOTAL RS	8127147

Approved 38 items only

(Rupees eightyone lakhs twentyseven thousand onehundred fortyseven)
only

Gst 18%,Cess1% and Qc1%Will be added at the time of agreement.




Asst Engineer

Hatadihi



Block dev
officer
Hatadihi



Addl Tech Officer

Zilla parisad Keonjhar

TO BE FILLED BY THE TENDERER

1) My/Our quoted rate is (both in figure and words)

	In figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The tenderer should quote the percentage up to 2(two) digits after the decimal point .
- 2) The Tenderers should quoted their percentage only inside the space provided for the purpose. And in case anything else regarding tender rate is mentioned, the tender is liable for rejection
- 3) The percentage quoted at any other place will not be taken in to consideration.
- 4)Rate of all items are inclusive of cost,carriage,royalty and other taxes of material.

Tenderer:

No. of Correction.....

No. of Over writing.....

No of Interpolation.....



Asst Exe. Engineer
Hatadihi Block



Block Dev. Officer
Hatadihi Block

Addl. Executive Officer (Tech.)
ZP,Keonjhar