

Bill of Quantity(BQQ)

Name of the Work: Const. of a Science lab, E-library, Toilet & Boundary wall at Salania High school.

Amount put to tender:

Rs 3631402.00

EMD:

1% of the Amount put to tender

Class of Contractor:

C & B class only

Cost of Tender Paper

Rs 6000.00

Completion Period:

6 (six) Calender Month

SL No.	Item Description	Quantity	Units	Estimated Rates in Rs. P	Total Amount in Rs. P
1	2	3	4	5	6
1	Foundation excavation in hard soil including levelling and dressing the bed and sides depositing muck within initial lead and lift etc. complete.	139.96	cum	195.40	27347.31
2	Filling foundation and plinth with sand well watered and rammed including cost, conveyance and royalty of sand etc. complete.	114.77	cum	366.40	42053.31
3	Cement concrete 1:3:6 using 4cm. size HBG metal including cost, conveyance and royalty of materials curing etc. complete.	30.55	cum	4974.40	151984.06
4	Cement concrete 1:4:8 using 4cm. size HBG metal including cost, conveyance and royalty of materials curing etc. complete.	2.79	cum	4525.60	12633.48
5	Cement concrete 1:2:4 using 12mm. size HBG crusher broken chips including cost, conveyance and royalty of materials curing etc. complete.	9.32	cum	6494.00	60513.01
6	Masonry work with Flyash Bricks having crushing strength between 75kg/sq.cm twith dimensional tolerance ±8 percent in c.m. 1:6 in F & P including cost conveyance and royalty of materials curing etc. complete.	59.77	cum	4273.90	255448.60
7	Masonry work with Flyash Bricks having crushing strength between 75kg/sq.cm twith dimensional tolerance ±8 percent in c.m. 1:6 in super structure including cost conveyance and royalty of materials curing etc. complete.				
	Ground Floor	82.42	cum	4312.30	355400.56
	1st Floor	29.08	cum	4585.51	133349.61
8	R.C.C. work M-20 grade using 20mm. and down grade HBG crusher broken chips including hoisting, laying, cost, conveyance and royalty of materials curing etc. complete.				
	A) Column Base	17.61	cum	5517.52	97178.06
	B) Plinth Beam	17.13	cum	5361.31	91835.59
	C) Column & Beam				
	Ground Floor	16.52	cum	11373.07	187923.88
	C-1) 1st Floor	6.91	cum	12662.06	87531.54
	D) Lintel Band				
	Ground Floor	3.06	cum	9145.17	27997.95
	1st Floor	2.81	cum	9988.58	28032.95
	E) Chaja				
	Ground Floor	14.90	sqm	816.87	12168.21
	1st Floor	11.71	sqm	918.64	10759.10
	F) Staircase				
	Ground floor	1.90	cum	10894.39	20647.81
	G) Slab				
	Ground Floor	18.26	cum	9741.17	177842.32
	1st Floor	11.55	cum	10703.78	123619.80
9	Supplying, fitting and placing uncoated HYSD bar reinforcement as per drawing and technical specification including cost, conveyance and all taxes of steel and binding wire etc. complete.				

	Ground Floor	62.62	Qntl	8445.80	528885.54
	1st Floor	20.93	Qntl	8470.20	177267.39
10	16mm. thick cement plaster in c.m. 1:6 including cost conveyance and royalty of materials curing etc. complete.				
	Ground Floor	490.94	sqm	208.10	102165.08
	1st Floor	174.97	sqm	216.50	37882.04
11	12mm. thick cement plaster in c.m. 1:6 over brick masonry including cost conveyance and royalty of materials curing etc. complete.				
	Ground Floor	526.95	sqm,	146.30	77092.34
	1st Floor	142.43	sqm,	151.98	21646.63
12	6mm. thick cement plaster (1:4) to R.C.C. surfaces finished smooth including losed deep chipping and slury treatment, cost, conveyance and royalty of materials curing etc. complete.				
	Ground Floor	207.83	sqm	163.80	34041.96
	1st Floor	110.99	sqm	167.80	18623.33
13	Supplying ,fitting and fixing vertrifed tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of EIC (For New work Only)				
	Ground Floor	142.40	sqm	1140.80	162449.58
	1st Floor	75.75	sqm	1150.86	87180.75
14	Supplying ,fitting and fixing ceramic floor titles of size 30cm x 30cm/ 40cm x 40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of EIC				
	Ground Floor	32.03	sqm	842.30	26975.75
15	Fixing chequered tiles in floors,treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades includind cost for rubbing, polishing & cost of marbel tiles etc. complete				
	Ground Floor	28.98	sqm	952.10	27587.76
16	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. DSR item no- 9.48.2				
	Ground Floor	600.57	kg	113.22	67997.68
	1st Floor	595.02	kg	113.22	67368.81
17	Painting two coats with enamel paint of approved quality over one coat of primer .				
	Ground Floor	46.20	sqm	198.30	9162.00
	1st Floor	36.41	sqm	203.42	7406.24
18	Priming 1 Coat on wall to receive paint/dlstemper				
	Ground Floor	676.44	sqm	60.40	40856.71
	1st Floor	428.39	sqm	61.90	26517.40
19	Finishing walls with water proofing cement paint of approved shade on new work two coats to give an even shade excluding cost of paint etc. complete.				
	Ground Floor	561.22	sqm	35.10	19698.81
20	Wall painting two coats on new work with plastic emulsion paint of approved shade on new work to give an even shade				
	Ground Floor	301.96	sqm	78.80	23794.29
	1st Floor	247.79	sqm	80.50	19946.94


21	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of				
	1st floor	247.79	sqm	119.50	29610.68
22	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade excluding cost of paint.				
	Ground Floor	321.49	sqm	92.30	29673.91
	1st Floor	180.60	sqm	95.00	17157.27
23	Cement washing one coat with cost of all labour &	428.39	sqm	16.80	7196.97
24	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and				
	Ground Floor	16.1	sqm	3350.90	53949.49
					Provision for Display board
					5000.00
					Total Rs
					3631402.00


18% GST will be added at the time of agreement over the quoted amount.

Total 24(Twenty four) Nos Item only

Approved for 24(Twenty four) items only


Asst.Exe. Engineer
Hatadihi Block


Block Dev. Officer
Hatadihi Block


Addl. Executive Officer (Tech.)
ZP,Keonjhar

TO BE FILLED BY THE TENDERER

1) My/Our quoted rate is (both in figure and words)

	In figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The tenderer should quote the percentage up to 2(two) digits after the decimal point .
- 2) The Tenderers should quoted their percentage only inside the space provided for the purpose. And in case anything else regarding tender rate is mentioned, the tender is liable for rejection
- 3) The percentage quoted at any other place will not be taken in to consideration.
- 4)Rate of all items are inclusive of cost,carriage,royalty and other taxes of material.

Tenderer:

No. of Correction.....

No. of Over writing.....

No of Interpolation.....



Asst Exe. Engineer
Hatadihi Block



Block Dev. Officer
Hatadihi Block

Addl. Executive Officer (Tech.)
ZP,Keonjhar