

BILL OF QUANTITY (BOQ)

Name-Construction of Additional Class Room Building at Laxmidhar Primary School under  
Banspal Block

Amount put to Tender	:	₹ 9,45,896.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	D' & C' class only
Cost of Tender Paper	:	Rs.4000.00
Date required for completion	:	6(Six) calender Month

SI No	Item of Work	Quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	34.68	Each cum	169.21	5868.00
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	46.79	Each cum	716.58	33528.00
3	P.C.C. (1:3:6) using 40 mm & down size B.S.Ch. chips including watering, curing with cost, direction of Engineer-in-Charge.	13.14	Each cum	4474.42	58793.00
4	R.C.C. M20 using 20 mm & down size B.S.Ch. chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				
	a. Footing	4.14	Each cum	4932.58	20420.00
	b. Plinth Beam	2.8	Each cum	5457.35	15280.00
	c. Column & Wall Beam	5.69	Each cum	10883.32	61926.00
	d. Lintel & Sill band	1.58	Each cum	8752.88	13829.00
	e. Roof slab	8.03	Each cum	9212.2	73973.00
	f. Chajja	0.76	Each cum	799.6	607.00
5	Straightening, Cutting, Bending, binding of M.S rod/TOR stein tying up the grills and placing in position including cost of binding wire with all cost conveyance, taxes etc completed in all respect as per the direction of Engineer-in-Charge.	21.85	Each Qntl	8945.60	195461.00
6	Fly Ash Brick masonry with CM (1:6) in foundation including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	12.4	Each Cum	4460.91	55315.00

7	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge. (G.F)	18.25	Each Cum	4499.24	82111.00
8	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge. (F.F)	6.84	Each Sqmt	4777.80	32680.00
9	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.				
	a. Ground Floor	132.04	Each Sqmt	152.83	20179.00
	b. 1st Floor(Parapet)	27.98	Each Sqmt	158.59	4437.00
10	16mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.				
	a. Ground Floor	85.22	Each Sqmt	216.62	18460.00
	b. 1st Floor(Parapet)	33.34	Each Sqmt	221.76	7393.00
11	Finishing surface of walls with acrylic wall putty of approved make and finished smooth and even surface to receive painting including cost of staging charges with cost of all material taxes, labour T&P etc complete .	50.80	Each Sqmt	70.78	3595.00
12	Providing 20 mm thick grading plaster (1:4) over roof slab including cost, conveyance, royalty, curing all etc complete	63.05	Each Sqmt	239.22	15082.00
13	25mm thick A.S flooring with C.C (1:2:4) including punning using 12 mm size H.G.C.B chips including cost , conveyence, royalties, taxes etc of all materials , cost of all labour sundries T& P etc complete as per direction of Engineer in charge.	1.02	Each Sqmt	308.46	314.00
14	Finishing walls with water proofing cement paint og approved shade on new work two coats to give an even side including cost os paint	136.03	Each Sqmt	35.67	4852.00
15 a	Weather Coat painting two coat to wall with approved shade on new work to give an even shade including cost of all materials and labour (T&P) etc. complete.GF	132.04	Each Sqmt	98.95	13065.00
b.	Weather Coat painting two coat to wall with approved shade on new work to give an even shade including cost of all materials and labour (T&P) etc. complete.FF	61.31	Each Sqmt	101.70	6235.00
16	Priming one coat with any approved primer over plastered surface	329.38	Each Sqmt	60.64	19973.00

17	Supplying , fitting and fixing MS Grills , Door and windows made out of structural steel flat etc as per direction of Engineer in charge.	330.78	Each Sqmt	151.56	50133.00
18	Painting two coats with any approved on new wood work / iron work with all cost, of materials and labour, T & P etc completed as per direction of Engineer in charge.	23.68	Each Sqmt	145.32	3441.00
19	Fixing Vetrified tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement : 1 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles. Per 1sqm	52.14	Each Sqmt	1253.22	65342.00
20	Fixing Chequered tiles in floors treads or steps and landing on 25mm thick bed of cement mortar 1:1 (1 cement : 1 sand) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of precast tiles. Per 1sqm	13.37	Each Sqmt	846.24	11314.00
21	Fixing tiles in dados skirting and risers of steps on 12mm thick CP(1:3) jointed with neat cement slurry mixed with pigments to match the shade of the tiles including cost of precast tiles.	3.81	Each Sqmt	1110.59	4231.00
22	Wall painting with art painting including one coat priming to the wall surface .	10.05	Each Sqmt	490.25	4927.00
23	Supplying , fitting and fixing of stainless steel of Grade in hand railing using 50mm dia. Of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.090mtr . C/C and stainless square pipe bracing of size 32mm x32mm x 2mm in 3 row in stair case as per approved design and specificatin , buffing , polishing etc . with cost , conveyance , taxes of all materials , labour, T&P etc .. required for the complete in all respect .	12 mtr		3511	42132.00
24	Construction of Black boards ( L.S)	2	Each nos	500	1000.00
					945896.00

*Parodi*  
22/05/2023  
Asst. Exe. Engineer  
Banspal Block

*22/05/2023*  
B.D.O.  
Banspal

*22/05/2023*  
Addl. Exicutive Officer Tech.  
Zilla Parishada Keonjhar

**TO BE FILLED BY THE TENDERER**

1) My/ Our qouted rate is (both in figure and words)

Equal to Estimate Cost  
Excess in Percentage  
Less in Percentage

in Figure	In words
%	
%	
%	

Notes:-

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

OFFICE USE ONLY

Sold for the work : Construction of Additional Class Room Building at Laxmidhar Primary School under Banspal Block. FOR THE YEAR 2022-23 on payment of

RS.....only per set vide money receipt No.....

Book No..... Dt.....

EMD: Rs..... In shape of  
Registration certificate furnished / not furnished  
STCC (GSTIN) furnished / not furnished  
ITCC (Pan Card) furnished / not furnished  
No of Correction .....

No of over writing .....

No of Interpolation.....

Block Development Officer  
Banspal Block