

APPROVED TENDER SCHEDULE

Name of the work: Const. of Boundery wall at Raikala P.U.P.S G.P- RAJANAGAR		Amount put to tender:Rs 1052343.00			
		Class of contractor: D & C			
		Cost of Tender Paper : Rs. 6,000/-			
		Earnest money Deposit 1% :Rs.10523.00			
		Time of Completion: 03months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	105.65	184.59	19501.93
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	22.42	370.50	8306.61
3	Cement concrete of proportion (1:3:6)) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	10.94	4267.02	46681.20
5	Fly ash brick(25cmx12cmx8cm) masonry in CM(1:6)for superstructure in foundation and plinth having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, convenience, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.				
a.	In foundation & plinth.	Cum	33.72	4160.67	140297.79
b.	In superstructure .	Cum	62.01	4198.62	260356.43
6	Reinforcement cement concrete M-20 grade with 20 mm nominal size down graded nominal size aggregate mechanically mixed and vibrated in foundation and bed protection of specification for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the engineering-in-charge.	cum	10.65	4847.74	51628.43
a	Plinth bend	cum	5.93	5223.27	30973.99
b.	boundery column	cum	9.21	10422.15	95988.00
c	roof slab	cum	0.67	10577.44	7086.88
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specifcaiton as directed by the engineering-in-charge.	Qtl	26.46	6481.53	171501.28
8	12 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	312.14	134.98	42132.66


 30.04.2021
 Acy


2021.05.2021
 Block Development Officer
 PATNA, KEONJHAR


9	16 mm thick cement plaster in C.M. (1:6) finishing smooth to inner side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials, labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	312.14	192.34	60037.01
10	6mm thick cement plaster in C.M. (1:4) to R.c.c surface including cement punning and skirting with all cost conveyance royalty etc complete	Sqm	32.42	150.40	4875.97
11	cement washing one coat	SQM	656.70	14.10	9259.47
12	Priming one coat with appoved primer	sqm	656.70	71.17	46737.34
13	Providing and applying paint over external plastered surfaces with 2 coats of weather coat of approved quality and shade using the required quantity of paint	Sqm	656.70	80.23	52687.04
14	Provison of Disply board (4 ft x3ft)	nos	1.00	5000.00	5000.00
15	Provision of dismentling by mechanical means				5000.00
			Grand	Total Rs	1052343.48
				Say	1052343.00

(Rupees Ten lakhs fifty two thousand three hundred forty three) only.

Tender schedule for the project:-Const. of Boundery wall at Raikala P.U.P.S Under Rajanagar GP Under OMBADC Patna Block is approved for RS 10,52,343.-(Rupees Ten lakhs fifty two thousand three hundred forty three) only with 15 (fifteen) items only.

G.S.T.cost in 12% (CGST6% +SGST6%)and 1% cess will be add at the time of agreement.


30.04.21
Asst. Executive Engineer
Patna


03.05.2021
Block Development Officer
Patna


04/5/2021
Executive Engineer
DRDA, Keonjhar

My /Our quoted rate is _____ % Excess/Less/Equal
to the corresponding estimate rate
(Write both in words and Figures)

NOTES:-

1. The Contractor should not write anything except quoting of percentage, excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned, the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only. If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor
with address.