

Detail Estimate

⑪

SD Nodal UPS, Sankho (Class Room-24.30 lakhs , Toilet-2.77 lakhs and Boundary wall-11.00 lakhs)

AMBO GP.

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	221.65	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	40509.84
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	141.73	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	64460.98
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	58.28	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	260958.97
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	4.25	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	24679.97
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	66.35	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	269323.65
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	124.05	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	508299.06
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.89	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	25667.94
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	25.40	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	123911.78
b	Column & Beam	One Cubic Meter	20.99	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	219552.88
c	(C-2)Column for 1st floor	One Cubic Meter	0.43	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4990.63

d	Plinth Beam	One Cubic Meter	21.67	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	102411.43
e	Lintel Band	One Cubic Meter	4.26	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	35711.09
f	Chhaja	One Square Meter	20.64	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	15657.11
g	Slab	One Cubic Meter	29.43	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	262993.55
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	69.84	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	545556.99
10	15mm (¾") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	666.59	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	132167.77
	(B)For parapet Both side	One Square Meter	66.61	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	13141.45
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	739.23	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	99869.61
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	279.50	150.60	Rupees One Hundred Fifty And Sixty Paise Only	42091.95
13	20mm, thick cement plaster grading in c.m. 1:4 including cost, conveyance and royalty of materials curing etc. complete.	One Square Meter	214.17	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	45682.34
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.67
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	196.91	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	203855.80
16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38


17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 8 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	925.50	86.30	Rupees Eighty Six And Thirty Paise Only	79870.65
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	73.37	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	13859.17
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	8.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	861.62	33.60	Rupees Thirty Three And Sixty Paise Only	28950.32
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	859.85	70.00	Rupees Seventy Only	60189.73
					Total	3266307.41
					Limited to	3266307.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.


Asst Executive Engineer
Hatadihi


Block Development Officer
Hatadihi


Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

12

Karagola Nodal UPS, Ambo (Class Room-24.30 lakhs ,Boundary-13.25 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	217.11	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	39680.16
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	136.66	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	62154.90
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	57.05	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	255435.00
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	3.84	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	21119.67
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	63.10	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	256167.12
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	130.94	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	536502.57
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.89	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	25667.94
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	26.95	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	131471.36
b	Column & Beam	One Cubic Meter	20.93	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	219018.40
c	(C-2)Column for 1st floor	One Cubic Meter	0.43	11690.05	Rupees Eleven Thousand Six Hundred Ninety Four And Six Paise Only	4990.63

d	Plinth Beam	One Cubic Meter	23.30	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	110112.70
e	Lintel Band	One Cubic Meter	4.26	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	35711.09
f	Chhaja	One Square Meter	20.64	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	15657.11
g	Slab	One Cubic Meter	26.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	238950.58
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	88.81	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	539308.73
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	714.13	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	137470.51
	(B)For parapet Both side	One Square Meter	66.61	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	13141.45
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	772.34	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	104343.48
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	266.48	150.60	Rupees One Hundred Fifty And Sixty Paise Only	40132.01
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	214.17	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	45682.34
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm @ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying, fitting and fixing vertified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	196.91	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	203855.80
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrip staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Klogram	798.00	86.30	Rupees Eighty Six And Thirty Paise Only	58867.40

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	62.71	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	11845.45
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	359.71	33.60	Rupees Thirty Three And Sixty Paise Only	32246.22
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	859.85	70.00	Rupees Seventy Only	60189.73
					Total	3241320.21
					Limited to	3241320.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Prerna
3.5.21
Asst Executive Engineer
Hatadihi

Jas
3.5.21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

13

Sibanarayanpur UGMES, Bancho (Class Room-8.10 lakhs and Toilet-2.77 lakhs)

SL	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	60.98	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	11145.97
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	43.39	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	19732.96
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	17.34	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	77637.14
4	CC (1:2:4) by using 12 mm size cbhg chips including all cost etc complete	One Cubic Meter	2.55	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	14793.69
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	18.17	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	73740.28
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	23.48	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	96202.09
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	5.24	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	25572.27
b	Column & Beam	One Cubic Meter	6.34	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	66347.16

c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26
d	Plinth Beam	One Cubic Meter	3.74	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	17668.39
e	Lintal Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	10.08	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	90066.54
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	27.87	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	169254.38
10	18mm (¾") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	130.87	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	25193.39
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	161.71	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	21847.06
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	95.26	150.60	Rupees One Hundred Fifty And Sixty Paise Only	14345.84
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90

16	Supplying ,fitting and fixing Ceramic Floor tyles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38
17	Supplying, fitting and fixing steel angle Iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	393.50	86.30	Rupees Eighty Six And Thirty Paise Only	33959.05
18	Painting two coats with any approved synthetic enamale paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	31.56	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	5962.21
19	Supplying,fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20356.78
					Total	921098.99
					Limited to	921099.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Haram
3.5.21
Asst Executive Engineer
Hatadihi

Jed
3.5.21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Singidova Project UPS-Bancho (Class Room-16.20 lakhs and Boundary-13.50 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	in words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	187.22	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	34217.55
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	94.94	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	43182.84
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	45.21	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	202415.72
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete.	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	53.30	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	216369.52
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	115.90	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	474876.56
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	24.38	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	118929.57
b	Column & Beam	One Cubic Meter	16.77	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	175470.75
c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32

d	Plinth Beam	One Cubic Meter	21.06	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	99532.05
e	Lintel Band	One Cubic Meter	2.84	8379.96	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8836.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	67.23	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	408212.68
10	16mm (¾") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	622.44	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	119818.85
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	701.83	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	94817.53
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm @ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13765 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126645.67
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mitered and electrically welded with fish-tails hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrops staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	973.82	33.60	Rupees Thirty Three And Sixty Paise Only	32720.43
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	2565566.42
					Limited to	2565566.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

A/K
3-5-21
Asst Executive Engineer
Hatadihi

Jad
3-5-21
Block Development Officer
Hatadihi

02
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Barahi MES, Bancho (Class Room-16.20 lakhs and Boundary-10.75 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	161.85	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	29580.26
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	90.67	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	41240.01
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	41.18	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	184399.22
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P. of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	46.43	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	188492.59
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	98.64	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	404164.32
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	20.91	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	102018.52
b	Column & Beam	One Cubic Meter	15.27	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	159765.55

c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11680.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32
d	Plinth Beam	One Cubic Meter	17.78	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	84051.28
e	Lintel Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grids, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	62.63	8072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	380284.55
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	531.45	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	102303.28
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	595.24	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	80416.25
12	8 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 Including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.67
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126845.67

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	776.24	33.60	Rupees Thirty Three And Sixty Paise Only	26081.50
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	2327799.71
					Limited to	2327800.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Arjun
25.5.21
Asst Executive Engineer
Hatadihi

Prad
3-5-21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

(16)

Bill of Quantity

BangoreGovt Nodal UPS (Class Room- 16.20 lakhs and 24.30 lakhs , Toilet-2.77 lakhs, Boundary wall-13.25 lakhs)

Sl. No.	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	304.35	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	55625.24
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	219.10	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	99654.88
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	86.99	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	389509.54
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	7.22	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	41937.31
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	91.69	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	372194.22
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	169.69	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	695275.79
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	11.79	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	51335.88
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers, not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	35.42	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	172781.27
b	Column & Beam	One Cubic Meter	31.54	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	329959.34
c	(C-2)Column for 1st floor	One Cubic Meter	0.81	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	9438.96

d	Plinth Beam	One Cubic Meter	29.39	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	138914.63
e	Lintel Band	One Cubic Meter	7.10	8379.96	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	59528.47
f	Chhaja	One Square Meter	34.91	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	26477.63
g	Slab	One Cubic Meter	46.17	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	412629.87
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	138.16	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	838918.77
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	938.56	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	180673.22
	(B)For parapet Both side	One Square Meter	120.92	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	23857.31
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1007.06	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	136053.36
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	449.72	150.60	Rupees One Hundred Fifty And Sixty Paise Only	67728.04
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	348.29	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	74289.67
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	18.29	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	63195.73
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 800mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	319.23	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	330501.48
16	Supplying ,fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and lower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1457.50	86.30	Rupees Eighty Six And Thirty Paise Only	125782.25
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	115.17	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	21756.14
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	1030.98	33.80	Rupees Thirty Three And Sixty Paise Only	34640.83
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1434.84	70.00	Rupees Seventy Only	100438.62
					Total	4863444.51
					Limited to	4863444.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

M. K. Singh
3-5-21
Asst Executive Engineer
Hatadihi

J. K. Singh
3-5-21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Gopabandhu Nodal UPS, Boula, Bangore (Class Room-2 x 16.20 lakhs , Toilet-2.77 lakhs and Boundary-10.75 lakhs)

17

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	249.09	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	45525.34
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	173.12	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	78739.99
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	71.13	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	316473.76
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	6.56	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	38074.98
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	75.02	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	304519.69
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	137.39	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	562937.54
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	10.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	43524.04
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	29.38	4978.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	143328.43
b	Column & Beam	One Cubic Meter	25.88	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	270706.53
c	(C-2)Column for 1st floor	One Cubic Meter	0.76	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	8896.64

d	Plinth Beam	One Cubic Meter	23.88	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	112853.21
e	Lintel Band	One Cubic Meter	5.68	8378.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	47634.75
f	Chhaja	One Square Meter	28.53	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	21641.44
g	Slab	One Cubic Meter	35.18	8938.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	323315.60
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	111.97	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	879894.59
10	18mm (¾") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	755.88	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	145505.99
	(B)For parapet Both side	One Square Meter	108.63	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	21431.72
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	829.95	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	112126.13
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and skury treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	353.47	150.60	Rupees One Hundred Fifty And Sixty Paise Only	53232.11
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	268.24	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	57214.68
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.80m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	18.29	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	83195.73
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	244.66	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	253291.35
16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtale hold fasts made out of MS flat size 200mmx50mmx3mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1191.50	86.30	Rupees Eighty Six And Thirty Paise Only	102826.45
18	Painting two coats with any approved synthetic enamals paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	94.27	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	17807.65
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	847.50	33.60	Rupees Thirty Three And Sixty Paise Only	28476.11
21	Wall painting with two coats weather cost paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1149.97	70.00	Rupees Seventy Only	80497.78
					Total	3946018.09
					Limited to	3946018.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Handwritten signature
3-5-21
Asst Executive Engineer
Hatadihi

Handwritten signature
3.5.21
Block Development Officer
Hatadihi

Handwritten signature
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Bidyadharpur UGMES, Balibareil (Class Room-8.10 lakhs and Boundary-10.75 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	135.59	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	24781.14
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	51.61	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	23472.99
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	28.58	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	127961.82
4	CC (1:2:4) by using 12 mm size cbhg chips including all cost etc complete.	One Cubic Meter	1.93	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	11233.39
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	36.02	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	146205.77
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	83.37	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	341593.18
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	17.69	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86280.89
b	Column & Beam	One Cubic Meter	11.01	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	115171.80

c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1623.26
d	Plinth Beam	One Cubic Meter	15.43	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	72917.75
e	Lintal Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	6.20	756.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6216.38
g	Slab	One Cubic Meter	7.39	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	66023.57
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	41.16	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	249628.89
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	437.89	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	84293.95
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	522.23	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	70553.42
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	82.24	150.60	Rupees One Hundred Fifty And Sixty Paise Only	12385.89
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx5mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, sldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	266.00	86.30	Rupees Eighty Six And Thirty Paise Only	22955.80
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	20.90	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	3948.48
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	775.24	33.60	Rupees Thirty Three And Sixty Paise Only	26061.50
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					Total	1630680.33
					Limited to	1630680.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

H. Ram
3.5.21
Asst Executive Engineer
Hatadihi

Jad
3.5.21
Block Development Officer
Hatadihi

[Signature]
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

(19)

Chasakhanda Nodal UPS, Danar (Class Room-8.10 lakhs and Toilet-2.77 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	60.98	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	11145.97
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	43.39	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	19732.96
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	17.34	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	77637.14
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.55	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	14793.69
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	18.17	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	73740.28
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	23.48	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	96202.09
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	5.24	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	25572.27

b	Column & Beam	One Cubic Meter	6.34	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	66347.15
c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26
d	Plinth Beam	One Cubic Meter	3.74	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	17668.39
e	Lintel Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	10.08	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	90086.54
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	27.87	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	169254.38
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	130.87	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	25193.39
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	181.71	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	21847.06
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	95.26	150.60	Rupees One Hundred Fifty And Sixty Paise Only	14345.84
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29

15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved qual	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90
16	Supplying ,fitting and fixing Ceramic Floor tyles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38
17	Supplying ,fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	393.50	86.30	Rupees Eighty Six And Thirty Paise Only	33959.05
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	31.56	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	5962.21
19	Supplying,fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					Total	921098.99
					Limited to	921099.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Hiran
2.5.21
Asst Executive Engineer
Hatadihi

Jai
3.5.21
Block Development Officer
Hatadihi

21/5/21
Executive Engineer
DRDA,Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Danar Nodal UPS, Danar (Class Room-2 x 16.20 lakhs , Toilet-2.77 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	148.20	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	27085.66
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	156.16	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	71028.59
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	55.21	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	247182.39
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	6.56	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	38074.98
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	48.04	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	195003.15
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	69.59	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	285139.46
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	10.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	43524.04
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	15.52	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	75684.21
b	Column & Beam	One Cubic Meter	19.87	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	207685.83
c	(C-2)Column for 1st floor	One Cubic Meter	0.76	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	8896.64

d	Plinth Beam	One Cubic Meter	11.01	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	52035.89
e	Lintel Band	One Cubic Meter	5.68	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	47634.75
f	Chhaja	One Square Meter	28.53	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	21641.44
g	Slab	One Cubic Meter	36.18	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	323315.60
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	93.71	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	569034.43
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	398.41	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	76694.82
	(B)For parapet Both side	One Square Meter	108.63	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	21431.72
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	411.17	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	55549.68
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	353.47	150.60	Rupees One Hundred Fifty And Sixty Paise Only	53232.11
13	20mm, thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	268.24	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	57214.66
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	18.29	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	63195.73
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	244.66	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	253291.35
16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly matted and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1191.50	86.30	Rupees Eighty Six And Thirty Paise Only	102826.45
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	94.27	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	17807.65
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm, Dia of 2mm, thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1149.97	70.00	Rupees Seventy Only	80497.78
					Total	3007649.53
					Limited to	3007650.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement

Aran
3.5.21
Asst Executive Engineer
Hatadihi

Jad
3.5.21
Block Development Officer
Hatadihi

08/05/2021
Executive Engineer
DRDA,Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation: