




## APPROVED TENDER SCHEDULE


Name of the work: Const. of Two nos Additional Class Room ,Drinking water facility,science laboratory at Dumuria B.S High school.		Amount put to tender:Rs 36,61,645.00			
		Class of contractor: C &B			
		Cost of Tender Paper : Rs. 6,000/-			
		Earnest money Deposit 1% :Rs.36616			
		Time of Completion: 4 months			
Sl. No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering,shorring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	182.12	184.59	33617.53
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	179.94	370.50	66667.77
3	Cement concrete of proportion (1:4:8) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	55.77	3744.11	208809.01
4	R.R H.G stone Masonary in cm (1:6) in foundation and plinth with all cost conveyance Royalty etc	cum	76.35	3192.96	243782.50
5	Fly ash brick(25cmx12cmx8cm) masonry in CM(1:6)for superstructure in foundation and plinth having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering in-charge.				
a.	In foundation & plinth.	Cum	11.26	4560.03	51345.94
b.	In superstructure .	Cum	70.59	4593.36	324245.28
6	Reinforcement cement concrete M-20 grade with 20 mm nominal size down graded nominal size aggregate mechanically mixed and vibrated in foundation and bed protection of speciation for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the engineering-in-charge.	cum	120.47	4771.27	574794.90
7	Suppling, coiled M.S rod or HYSD steel (Fe-415),cutting, bending,cracking,hooking,olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specificaiton as directed by the engineering-in-charge.	Qtl	120.27	6328.63	761144.33

  
 30.04.21  
 AEEU

  
 0705.2021  
 Block Development Officer  
 PATNA, KEONJHAR

8	Rigid smooth centring and shuttering at all heights for R,C,C work including false work and distempering them after casting				
	1) R.C.C. Column & beam	sqmt	250.27	736.64	184358.89
	2) lintel	sqmt	57.80	263.33	15220.47
	3) Roof slab	sqmt	319.88	439.89	140712.01
9	Fixing Verified tiles in floors ,treads and landings on 25 mm thick bed of cement mortar (1:1) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	303.91	1088.60	330836.43
10	Fixing of verified tiles in dados ,skirting and in rises of steps on 12mm thick bed of cement plaster (1:3) joined with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing including cost of tile	sqmt	94.94	1207.56	114645.75
11	12 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	355.86	137.14	48802.64
12	16 mm thick cement plaster in C.M. (1:6) finishing smooth to inner side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	355.86	210.76	75001.05
13	20 mm thick cement plaster in C.M. (1:4) Roof slab Grading plaster after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	sqm	320.16	225.16	72087.23
14	20 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	72.43	214.68	15549.27
15	12 mm thick cement plaster in C.M. (1:4) including cement punning and skirting with all cost conveyance royalty etc complete	Sqm	346.67	148.29	51407.69
16	Supplying fitting & fixing of M.S shutter including cost of all materials etc .complete as per direction of in charge	kg	1741.86	64.00	111479.04
17	Painting two coats in all Doors and windows (two coats with paint s of approved shade and base coat with primer)to new wood and iron work including sand	Sqm	126.90	196.00	24872.40
18	Distempering two coats to walls with distemper of approved shade on new work to give an even shade including cost of distemper	Sqm	665.18	66.21	44041.57
19	Providing and applying paint over external plastered surfaces with 2 coats of weather coat of approved quality and shade using the required quantity of paint	Sqm	290.23	75.43	21892.05

  
 30.04.21  
 AEE


  
 03.05.2021  
 Block Development Officer  
 PATNA, KEONJHAR


20	cement washing one coat	sqm	1367.12	14.06	19221.71
21	Priming one coat with appoved primer	sqm	660.76	65.34	43174.06
22	Provison of Disply board (4 ft x3ft) and construction Flat from	nos	1.00	11000.00	11000.00
23	Primiming of Door and window	sqm	7.26	138.28	1003.91
24	Fixing Granite in top of the Lab table over thick bed of cement mortar1.1 including rubbing and polishing including cost of Granite 20 mm thick	sqm	11.10	2336.18	25931.60
25	Provison of recharge pit of roof top water harvesting & sluge pit (size- 5'.0"x5.0"x'4'.0") with cover slab connected with 4" dia PVC pipe with fittings as the direction of the Engineer incharge	nos	1.00	15000.00	15000.00
26	Supplying, fitting and fixing of in less steel lineerngn hand railing using 50 mm dia of 2mm thick circular pipe with balustade in Ramp as per approved design and specification buffing,polishing etc complete asper Direction of Engi neer-In -charge	RM	10.00	2500.00	25000.00
27	Supplying fitting & fixing of fabricatdnce and Aluminum Door for toilet including cost,conveys taxes required for the work etc complete as per direction of in charge	nos	1.00	5000.00	5000.00
28	Cost of ventilator	nos	10.00	100.00	1000.00
				Total Rs	3661645.03
			Grand	Total Rs	3661645.00


(Rupees Thirty six lakhs sixty one thousand six hundred forty five ) only

Tender schedule for the project:-Const. of Two nos Additional class room , Drinking water facility,Science Labortory at Dumuria B.S high schoolGP Dumuria Under OMBADC Patna Block is approved for Rs36,61,645.00-(Rupees thirty six lakhs sixty one thousand six hundred forty five ) only with 28 (twenty eight) items only.

G.S.T.cost in 12% (CGST6% +SGST6%) will be add at the time of agreement.

  
30.04.21  
Asst. Executive Engineer  
Patna Block

  
03.05.2021  
Block Development Officer  
Patna Block

  
04/05/2021  
Executive Engineer  
DRDA,Keonjhar

My /Our quoted rate is \_\_\_\_\_ % Excess/Less/Equal  
to the corresponding estimate rate  
(Write both in words and Figures)

**NOTES:-**

1. The Contractor should not write anything except quoting of percentage,excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned,the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words,so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender without mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only.If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.

Signature of the Contractor  
with address.