

Bill of Quantity

31

Hadgarh Nodal UPS, Hadgarh (Class Room-16.20 lakhs , Toilet-2.77 lakhs and Boundary-13.75 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	217.13	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	39684.52
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	104.28	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	47431.75
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	50.46	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	225956.19
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	3.58	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	20817.64
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	63.41	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	257402.99
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	126.27	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	517385.29
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers, not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	26.30	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	128281.04
b	Column & Beam	One Cubic Meter	18.32	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	191710.41
c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32

d	Plinth Beam	One Cubic Meter	22.70	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	107311.55
e	Lintel Band	One Cubic Meter	2.94	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	19.43	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	173679.29
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S. rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 16 to 20 gauge and labour charges required for the work etc complete.	One Quintal	72.85	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	442388.07
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	685.88	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	132031.68
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	775.31	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	104744.94
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	183.24	150.60	Rupees One Hundred Fifty And Sixty Paise Only	27596.03
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing verified tiles in floors,trade or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126645.67
16	Supplying ,fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mottared and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	659.50	86.30	Rupees Eighty Six And Thirty Paise Only	56914.85
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	52.47	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	9910.69
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	1073.32	33.60	Rupees Thirty Three And Sixty Paise Only	36063.46
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	2828320.32
					Limited to	2828320.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Hrush
3-5-21
Asst Executive Engineer
Hatadihi

Jee
3-5-21
Block Development Officer
Hatadihi

08/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

32

Dangabahal UGUPS, Hadagarh (Class Room-16.20 lakhs and Boundary-10.75 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	161.85	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	29580.26
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	90.67	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	41240.01
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	41.18	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	184399.22
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete.	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17267.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	46.43	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	188492.59
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	98.64	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	404164.32
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	20.91	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	102018.52
b	Column & Beam	One Cubic Meter	15.27	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	159765.58

c	(C-2) Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32
d	Plinth Beam	One Cubic Meter	17.78	4728.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	84051.28
e	Lintel Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	62.63	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	380284.55
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	531.45	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	102303.28
	(B) For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	595.24	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	80416.25
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm, thick circular pipe with Balustrade of size 32mm.x32mm, x2mm @ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying, fitting and fixing vitrified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	128645.67

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and lower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chroma primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	776.24	33.60	Rupees Thirty Three And Sixty Paise Only	26081.50
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	2327799.71
					Limited to	2327800.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Amit
3.5.21
Asst Executive Engineer
Hatadihi

Jad
3.5.21
Block Development Officer
Hatadihi

03
06/05/2021
Executive Engineer
DRDA,Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

33

Malra UGUPS, Hadgarh (Class Room-8.10 lakhs and Boundary-11.00 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	137.40	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	25112.38
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	51.91	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	23611.76
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	28.87	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	129248.71
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	1.93	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	11233.39
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	36.51	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	148196.98
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	84.60	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	346644.06
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers, not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	17.94	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	87488.62
b	Column & Beam	One Cubic Meter	11.12	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	116293.59
c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26

d	Plinth Beam	One Cubic Meter	15.68	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	74023.52
e	Lintel Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chheja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	7.39	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	66023.57
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	41.48	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	251923.75
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	444.39	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	85545.06
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4876.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	529.85	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	71582.09
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	82.24	150.60	Rupees One Hundred Fifty And Sixty Paise Only	12385.69
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.28
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and lower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	266.00	86.30	Rupees Eighty Six And Thirty Paise Only	22955.80
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	20.90	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	3948.48
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	790.35	33.60	Rupees Thirty Three And Sixty Paise Only	26555.71
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					Total	1647663.66
					Limited to	1647663.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

A. Patel
3-5-21
Asst Executive Engineer
Hatadihl

Patel
3-5-21
Block Development Officer
Hatadihl

Patel
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Malliposi NUPS, Hadgarh (Class Room-16.20 lakhs and Boundary-8.25 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	138.29	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	25274.21
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	86.70	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	39435.95
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	37.45	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	167669.61
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete.	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	40.06	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	162608.65
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	82.61	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	338502.96
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	17.69	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86315.40
b	Column & Beam	One Cubic Meter	13.88	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	145182.20
c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32

d	Plinth Beam	One Cubic Meter	14.74	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	69676.28
e	Lintel Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	58.36	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	354351.28
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	446.95	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	86038.82
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	496.25	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	67043.63
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing vetrified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126645.67
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtails hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrip staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	592.75	33.60	Rupees Thirty Three And Sixty Paise Only	19916.78
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	2107016.34
					Limited to	2107016.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Hiran
3-5-21
Asst Executive Engineer
Hatadihi

Jai
3-5-21
Block Development Officer
Hatadihi

[Signature]
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

35

Junapasi new ups, hadagada (Class Room-24.30 lakhs ,Boundary-13.50 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	218.92	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	40011.39
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	136.98	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	62293.67
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	57.34	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	258721.90
4	CC (1:2:4) by using 12 mm size cbhg chips: including all cost etc complete	One Cubic Meter	3.64	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	21119.67
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	63.60	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	258158.33
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	132.17	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	541553.44
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.89	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	25667.94
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	27.20	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	132679.30
b	Column & Beam	One Cubic Meter	21.04	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	220140.19
c	(C-2)Column for 1st floor	One Cubic Meter	0.43	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4990.63

d	Plinth Beam	One Cubic Meter	23.53	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	111218.47
e	Lintel Band	One Cubic Meter	4.26	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	35711.09
f	Chhaja	One Square Meter	20.64	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	15657.11
g	Slab	One Cubic Meter	26.74	8938.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	238950.58
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC work including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	89.14	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	541303.60
10	16mm (%) thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete	One Square Meter	720.63	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	138721.62
	(B)For parapet Both side	One Square Meter	66.61	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	13141.45
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	779.96	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	105372.14
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	266.48	150.60	Rupees One Hundred Fifty And Sixty Paise Only	40132.01
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	214.17	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	45662.34
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	196.91	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	203855.80
16	Supplying, fitting and fixing steel angle Iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mottared and electrically welded with fishtale hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, akdrop staple and lower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	798.00	88.30	Rupees Eighty Six And Thirty Paise Only	68867.40

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	62.71	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	11845.45
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	973.82	33.60	Rupees Thirty Three And Sixty Paise Only	32720.43
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	859.85	70.00	Rupees Seventy Only	80189.73
					Total	3258303.55
					Limited to	3258304.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.


Asst Executive Engineer
Hatadihi


3-5-21
Block Development Officer
Hatadihi


Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Raighati UGMES, Hadgarh (Class Room-24.30 lakhs, Toilet-2.77 lakhs and Boundary wall-14.00 lakhs)

36

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	250.64	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	45809.60
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	146.61	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	66681.36
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	62.88	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	281549.26
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	4.25	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	24679.97
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	74.19	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	301183.01
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	143.78	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	589113.04
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.89	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	25667.94
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	29.36	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	143238.70
b	Column & Beam	One Cubic Meter	22.70	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	237501.65
c	(C-2)Column for 1st floor	One Cubic Meter	0.43	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4990.63

d	Plinth Beam	One Cubic Meter	25.41	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	120103.74
e	Lintel Band	One Cubic Meter	4.26	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	35711.09
f	Chhaja	One Square Meter	20.64	756.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	15657.11
g	Slab	One Cubic Meter	29.43	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	262993.55
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	95.10	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	577473.85
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	790.57	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	152185.56
	(B)For parapet Both side	One Square Meter	66.61	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	13141.45
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	861.05	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	116328.22
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	279.50	150.60	Rupees One Hundred Fifty And Sixty Paise Only	42091.95
13	20mm. thick cement plaster grading in c.m. 1:4 Including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	214.17	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	45682.34
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	196.91	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	203855.80
18	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8316.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	925.50	86.30	Rupees Eighty Six And Thirty Paise Only	79870.65
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	73.37	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	13859.17
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	1087.43	33.60	Rupees Thirty Three And Sixty Paise Only	36537.67
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	859.85	70.00	Rupees Seventy Only	60189.73
					Total	3538040.79
					Limited to	3538041.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

H. K. Singh
3-5-21
Asst Executive Engineer
Hatadihi

J. K. Singh
3-5-21
Block Development Officer
Hatadihi

S. K. Singh
08/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

37

Hatadihi Nodal UPS (Class Room-2 x 16.20 lakhs , Toilet-2.77 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	148.20	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	27085.66
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	156.16	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	71028.59
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	55.21	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	247182.39
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	6.56	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	38074.98
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	48.04	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	195003.15
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	69.59	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	285139.46
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	10.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only.	43524.04
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	15.52	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	75684.21
b	Column & Beam	One Cubic Meter	19.87	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	207885.83
c	(C-2)Column for 1st floor	One Cubic Meter	0.76	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	8896.64

d	Plinth Beam	One Cubic Meter	11.01	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	52035.89
e	Lintel Band	One Cubic Meter	5.68	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	47634.75
f	ChhaJa	One Square Meter	28.53	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	21641.44
g	Slab	One Cubic Meter	36.18	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	323315.60
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	93.71	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	569034.43
10	18mm (¾") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	398.41	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	76694.82
	(B)For parapet Both side	One Square Meter	108.63	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	21431.72
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	411.17	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	55549.68
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	353.47	150.80	Rupees One Hundred Fifty And Sixty Paise Only	53232.11
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc complete.	One Square Meter	268.24	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	57214.66
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	18.29	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	63195.73
15	Supplying, fitting and fixing vitrified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	244.66	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	253291.35
16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter; aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1191.50	86.30	Rupees Eighty Six And Thirty Paise Only	102826.45
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	94.27	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	17807.85
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm, thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1149.97	70.00	Rupees Seventy Only	80497.78
					Total	3007649.53
					Limited to	3007650.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Arjun
3-5-21
Asst Executive Engineer
Hatadihi

Jul
3-5-21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

38

Jalakalanga UGMES, Hatadihi (Class Room-16.20 lakhs , Toilet-2.77 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	87.24	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	15945.09
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	82.45	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	37499.98
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	29.94	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	134074.54
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	3.58	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	20817.64
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	28.58	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	116027.10
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	38.75	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	158773.22
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	8.47	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	41309.91
b	Column & Beam	One Cubic Meter	10.60	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	110940.95

c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32
d	Plinth Beam	One Cubic Meter	6.09	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	26801.93
e	Lintel Band	One Cubic Meter	2.64	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	19.43	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	173679.29
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	49.34	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	299610.04
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	224.43	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	43202.71
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	234.71	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	31709.86
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	183.24	150.60	Rupees One Hundred Fifty And Sixty Paise Only	27596.03
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	26607.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126645.67
16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.36

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx8mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	659.50	86.30	Rupees Eighty Six And Thirty Paise Only	55914.85
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	52.47	186.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	9910.69
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm, thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	1618218.38
					Limited to	1618218.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

H. S. S. S.
3-5-21
Asst Executive Engineer
Hatadihi

J. S. S. S.
3-5-21
Block Development Officer
Hatadihi

B. S. S. S.
06/5/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than /
equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

39

Matha MES, Hatadihi (Class Room-16.20 lakhs and Boundary wall-11.00 lakhs)

Sl No.	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	163.66	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	29911.49
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	90.98	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	41378.78
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	41.47	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	185686.11
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	46.92	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	190483.80
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	99.87	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	409215.20
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	21.16	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	103226.45
b	Column & Beam	One Cubic Meter	15.38	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	160887.38
c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32

d	Plinth Beam	One Cubic Meter	18.02	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	85157.05
e	Lintel Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	62.95	8072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	382279.42
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	537.94	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	103554.39
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.66
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	602.85	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	81444.91
12	8 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	26607.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126645.67
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx5mm size with corners of the frame duly mottened and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, sidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
19	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	780.35	33.60	Rupees Thirty Three And Sixty Paise Only	26555.71
					Total	2344783.05
					Limited to	2344783.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

A. Singh
23-5-21
Asst Executive Engineer
Hatadihi

3.5.21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Anadi Narayan UP(ME) School, Habaleswar (Class Room-24.30 lakhs , Boundary-8.25 lakhs)

SL	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	118.94	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	21738.93
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	124.47	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	56610.81
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	42.07	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	188380.71
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	4.25	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	24679.97
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance $\pm 8\%$ including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	38.88	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	157815.91
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance $\pm 8\%$ including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	55.02	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	225450.10
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete	One Cubic Meter	5.89	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	25667.94
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	11.29	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	55059.63
b	Column & Beam	One Cubic Meter	14.87	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	155610.39

c	(C-2)Column for 1st floor	One Cubic Meter	0.43	11690.08	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4990.63
d	Plinth Beam	One Cubic Meter	8.57	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	40488.34
e	Lintal Band	One Cubic Meter	4.26	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	35711.09
f	Chhaja	One Square Meter	20.64	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	15657.11
g	Slab	One Cubic Meter	29.43	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	262993.55
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	71.26	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	432700.98
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	322.83	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	62105.49
	(B)For parapet Both side	One Square Meter	66.61	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	13141.45
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	312.84	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	42264.50
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	279.50	150.60	Rupees One Hundred Fifty And Sixty Paise Only	42091.95
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	214.17	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	45682.34
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing vetrified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	196.91	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	203855.80
16	Supplying ,fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	6315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish-tail joint fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	925.50	86.30	Rupees Eighty Six And Thirty Paise Only	79670.65
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	73.37	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	13859.17
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm, Dia of 2mm, thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	859.85	70.00	Rupees Seventy Only	60189.73
					Total	2310955.51
					Limited to	2310955.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

H. K. S.
3-5-21
Asst Executive Engineer
Hatadihi

J. S.
3-5-21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation: