

Bill of Quantity

51

Elakana Project UPS, Mareigaon (Class Room-8.10 lakhs and Boundary-10.75 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	135.59	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	24781.14
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	51.61	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	23472.99
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	28.58	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only.	127961.82
4	CC (1:2:4) by using 12 mm size cbhg chippe including all cost etc complete	One Cubic Meter	1.93	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	11233.39
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	36.02	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	146205.77
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	83.37	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	341593.18
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	17.69	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86280.89
b	Column & Beam	One Cubic Meter	11.01	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	115171.80
c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26

d	Plinth Beam	One Cubic Meter	15.43	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	72917.75
e	Lintel Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	7.39	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	86023.57
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grille, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	41.16	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	249928.89
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	437.89	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	84293.95
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	522.23	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	70553.42
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	82.24	150.60	Rupees One Hundred Fifty And Sixty Paise Only	12385.89
13	20mm. thick cement plaster grading in c.m. 1:4 Including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.80

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	266.00	86.30	Rupees Eighty Six And Thirty Paise Only	22955.80
17	Painting two coats with any approved synthetic enamale paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	20.90	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	3948.48
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	776.24	33.60	Rupees Thirty Three And Sixty Paise Only	26081.50
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					<b>Total</b>	<b>1630680.33</b>
					<b>Limited to</b>	<b>1630680.00</b>

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*Mram*  
3.5.21  
Asst Executive Engineer  
Hatadihi

*Prad*  
3.5.21  
Block Development Officer  
Hatadihi

*OB/AS/2021*  
Executive Engineer  
DRDA,Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

Bill of Quantity

52

Jagannathpur Project UPS, Mareigaon (Class Room-2 x 16.20 lakhs ,Boundary Wall-8.25 lakhs )

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	199.24	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	36414.78
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	160.42	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	72964.56
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	62.71	4477.60	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	280777.46
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	5.94	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	34514.68
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	59.51	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	241582.91
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in <b>Superstructure</b> of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	113.46	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	464869.20
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	10.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	43524.04
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	24.74	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	120689.70
b	Column & Beam	One Cubic Meter	23.14	10481.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	242127.09
c	(C-2)Column for 1st floor	One Cubic Meter	0.76	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	8896.64

d	Plinth Beam	One Cubic Meter	19.66	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	92910.25
e	Lintel Band	One Cubic Meter	5.68	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	47634.75
f	Chhaja	One Square Meter	28.53	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	21641.44
g	Slab	One Cubic Meter	33.49	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	299272.63
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S. rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	102.72	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	623775.67
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	620.64	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	119530.93
	(B)For parapet Both side	One Square Meter	108.63	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	21431.72
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	672.71	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	90893.43
12	8 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and skry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	340.45	150.60	Rupees One Hundred Fifty And Sixty Paise Only	51272.16
13	20mm. thick cement plaster grading in c.m. 1:4 including cost, conveyance and royalty of materials curing etc. complete.	One Square Meter	268.24	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	57214.86
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing, using 60mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	18.29	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	63196.73
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	244.66	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	253291.35

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1064.00	86.30	Rupees Eighty Six And Thirty Paise Only	91823.20
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	83.61	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	15793.93
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	664.03	33.60	Rupees Thirty Three And Sixty Paise Only	22311.39
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1149.97	70.00	Rupees Seventy Only	80497.78
					<b>Total</b>	<b>3498842.10</b>
					<b>Limited to</b>	<b>3498842.00</b>

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*[Signature]*  
Asst Executive Engineer  
Hatadihi

*[Signature]*  
3-5-21  
Block Development Officer  
Hatadihi

*[Signature]*  
06/05/2021  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

**Bill of Quantity**

53

**Sankhana UGMES, Mareigaon (Class Room-16.20 lakhs and Boundary wall-11.00 lakhs )**

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delfts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	163.66	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	29911.49
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	90.98	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	41378.78
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	41.47	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	185886.11
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete.	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	46.92	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	190483.80
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	99.87	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	409215.20
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	21.16	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	103226.45
b	Column & Beam	One Cubic Meter	15.38	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	160887.38
c	(C-2)Column for 1st floor	One Cubic Meter	0.36	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32

J	Plinth Beam	One Cubic Meter	16.02	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	85157.05
e	Lintal Band	One Cubic Meter	2.64	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	756.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	62.95	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	382279.42
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	537.94	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	103554.39
	(8)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	602.85	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	81444.91
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.80	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing verified tiles in floors.treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126845.67
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
19	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	790.35	33.60	Rupees Thirty Three And Sixty Paise Only	26555.71
					<b>Total</b>	<b>2344783.05</b>
					<b>Limited to</b>	<b>2344783.00</b>

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement

*Hanu*  
3-5-21  
Asst Executive Engineer  
Hatadihi

*Jag*  
3-5-21  
Block Development Officer  
Hatadihi

*06/05/2021*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....



**Bill of Quantity**

**Khaparakhai Project UPS, Mareigaon (Class Room-16.20 lakhs and Boundary-8.25 lakhs)**

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	138.29	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	25274.21
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	86.70	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	39435.95
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	37.45	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	167589.61
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:5) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	40.06	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	162606.86
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in <b>Superstructure</b> of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	82.61	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	338502.96
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a.	Column Base	One Cubic Meter	17.69	4678.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86315.40
b.	Column & Beam	One Cubic Meter	13.88	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	145182.20
c.	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32

d	Pilinth Beam	One Cubic Meter	14.74	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	69676.28
e	Lintal Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	759.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	58.36	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	354351.28
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	448.95	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	86038.82
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	496.25	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	67043.63
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28807.33
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126845.67
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aidrop staple and lower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60

17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	592.76	33.60	Rupees Thirty Three And Sixty Paise Only	19916.78
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					Total	2107016.34
					Limited to	2107016.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*H. K. S.*  
3.5.21  
Asst Executive Engineer  
Hatadihi

*Jas*  
3.9.21  
Block Development Officer  
Hatadihi

*[Signature]*  
06/05/2021  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

**Bill of Quantity**

55

**Hatakeswari Nodal UPS, Khetuali, Orail (Class Room-8.10 lakhs and Boundary-10.75 lakhs)**

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	135.59	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	24781.14
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	51.61	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	23472.99
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	28.58	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	127961.82
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	1.93	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	11233.39
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	38.02	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	146205.77
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	83.37	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	341593.18
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	17.69	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86280.89
b	Column & Beam	One Cubic Meter	11.01	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	115171.80
c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26

d	Plinth Beam	One Cubic Meter	15.43	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	72917.75
e	Lintel Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	7.39	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	66023.57
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	41.16	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	249928.89
10	18mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	437.89	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	84293.95
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	522.23	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	70553.42
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	82.24	150.60	Rupees One Hundred Fifty And Sbtly Paise Only	12385.89
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12822.32
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. in 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1.4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	50.48	1036.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no, for single & double leaf shutter, sidrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	266.00	86.30	Rupees Eighty Six And Thirty Paise Only	22955.80
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	20.90	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	3948.48
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	776.24	33.60	Rupees Thirty Three And Sixty Paise Only	26081.50
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					<b>Total</b>	<b>1630680.33</b>
					<b>Limited to</b>	<b>1630680.00</b>

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*Amur*  
3-5-21  
Asst Executive Engineer  
Hatadihi

*Jed*  
3-5-21  
Block Development Officer  
Hatadihi

*06/05/2021*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than  
/ equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

**Bill of Quantity**

56

**Bairagi Nodal UPS, Nandipada (Class Room-16.20 lakhs and Boundary-13.50 lakhs)**

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	187.22	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	34217.55
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	94.94	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	43182.84
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	45.21	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	202415.72
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	53.30	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	216369.52
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	115.90	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	474878.56
7	Fly ash Brick Masonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base:	One Cubic Meter	24.38	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	118929.57
b	Column & Beam	One Cubic Meter	16.77	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	175470.75

c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11890.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32
d	Plinth Beam	One Cubic Meter	21.06	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	98532.05
e	Lintel Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wire of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	67.23	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	408212.68
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	623.44	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	119818.85
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	701.83	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	94817.53
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.67
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement . 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	126645.67

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mitered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrip staple and tower bolt hinges duly welded to the frame with one coat of anti-corrosive red oxide zinc-chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	973.82	33.60	Rupees Thirty Three And Sixty Paise Only	32720.43
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
					<b>Total</b>	<b>2565566.42</b>
					<b>Limited to</b>	<b>2565566.00</b>

Approved 19 Items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*Hron*  
3-5-21  
Asst Executive Engineer  
Hatadihi

*Red*  
3-5-21  
Block Development Officer  
Hatadihi

*06/05/2021*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

## Bill of Quantity

57

BC UPS,Orali (Class Room-8.10 lakhs and Toilet-2.77 lakhs )

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	60.98	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	11145.97
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	43.39	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	19732.96
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	17.34	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	77637.14
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.55	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	14793.69
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	18.17	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	73740.28
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	23.48	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	96202.09
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	5.24	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	25572.27

b	Column & Beam	One Cubic Meter	6.34	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	66347.16
c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26
d	Plinth Beam	One Cubic Meter	3.74	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	17668.39
e	Lintal Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	10.08	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	90066.54
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	27.87	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	169254.38
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	130.87	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	25193.39
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	161.71	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	21847.06
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	95.26	150.80	Rupees One Hundred Fifty And Sixty Paise Only	14345.84
13	20mm. thick cement plaster grading in c.m. 1:4 including cost, conveyance and royalty of materials curing etc. complete.	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm,x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance,	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved qual	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90

16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	393.50	86.30	Rupees Eighty Six And Thirty Paise Only	33959.05
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	31.56	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	5962.21
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm Dia of 2mm thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	71.27	33.60	Rupees Thirty Three And Sixty Paise Only	2394.61
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					<b>Total</b>	<b>921098.99</b>
					<b>Limited to</b>	<b>921099.00</b>

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*Hiran*  
3.5.21  
Asst Executive Engineer  
Hatadihi

*Jas*  
3.5.21  
Block Development Officer  
Hatadihi

*06/05/2021*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words)  
excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

**Bill of Quantity**

**Baniapanka Nodal UPS, Padhlaripally (Class Room-8.10 lakhs , Toilet-2.77 lakhs and Boundary-10.75 lakhs)**

58

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	161.88	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	29585.65
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	60.34	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	27444.36
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	33.26	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	148928.50
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	2.55	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	14793.69
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	45.14	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	183256.81
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	91.28	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	374000.17
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	19.11	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	93216.49
b	Column & Beam	One Cubic Meter	12.35	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	129167.86

c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11890.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26
d	Plinth Beam	One Cubic Meter	16.61	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	78485.71
e	Lintel Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.38
g	Slab	One Cubic Meter	10.08	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	90066.54
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	46.13	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	280114.54
10	18mm (¾") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	468.34	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	94004.56
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	580.48	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	78423.51
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	95.26	150.60	Rupees One Hundred Fifty And Sixty Paise Only	14345.84
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete	One Square Meter	59.18	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	50.46	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.80
16	Supplying, fitting and fixing Ceramic Floor tytes 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	9.29	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	8315.38

17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	393.50	86.30	Rupees Eighty Six And Thirty Paise Only	33959.05
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	31.56	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	5962.21
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	847.50	33.60	Rupees Thirty Three And Sixty Paise Only	28476.11
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
<b>Total</b>						<b>1859467.56</b>
<b>Limited to</b>						<b>1859467.00</b>

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*[Signature]*  
Asst Executive Engineer  
Hatadihi

*[Signature]*  
Block Development Officer  
Hatadihi

*[Signature]*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

**Bill of Quantity**

59

**Daneipur UGUPS, Padhiarpally (Class Room-8.10 lakhs and Boundary-10.75 lakhs)**

Sl.	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	135.59	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	24781.14
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	51.61	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	23472.99
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	28.58	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	127961.82
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	1.93	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	11233.39
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	36.02	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	146205.77
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in <b>Superstructure</b> of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance $\pm$ 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	83.37	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	341593.18
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	2.04	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	8890.79
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	17.69	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86280.89
b	Column & Beam	One Cubic Meter	11.01	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	115171.80
c	(C-2)Column for 1st floor	One Cubic Meter	0.16	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	1823.26

d	Pinth Beam	One Cubic Meter	15.43	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	72917.75
e	Lintel Band	One Cubic Meter	1.50	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	12577.15
f	Chhaja	One Square Meter	8.20	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	6218.39
g	Slab	One Cubic Meter	7.39	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	66023.57
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 16 to 20 gauge and labour charges required for the work etc complete.	One Quintal	41.16	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	249928.89
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	437.89	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	84293.85
	(B)For parapet Both side	One Square Meter	24.71	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	4875.20
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	522.23	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	70553.42
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	82.24	150.60	Rupees One Hundred Fifty And Sixty Paise Only	12385.89
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	59.16	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	12622.32
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	50.48	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	52245.90

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mitered and electrically welded with fish-tail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	266.00	86.30	Rupees Eighty Six And Thirty Paise Only	22955.60
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	20.90	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	3948.48
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	776.24	33.60	Rupees Thirty Three And Sixty Paise Only	26081.50
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	290.84	70.00	Rupees Seventy Only	20358.78
					<b>Total</b>	<b>1630680.33</b>
					<b>Limited to</b>	<b>1630680.00</b>

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*Arun*  
25.5.21  
Asst Executive Engineer  
Hatadihi

*Jad*  
3.5.21  
Block Development Officer  
Hatadihi

*02/05/2021*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than  
/ equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....

Bill of Quantity

60

Sidheswar UP(ME) School, Padhiaripally (Class Room-16.20 lakhs and Boundary-8.25 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	138.29	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	25274.21
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	86.70	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	39435.95
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	37.45	4477.50	Rupees Four Thousand Four Hundred Seventy Seven And Fifty Paise Only	167669.61
4	CC (1:2:4) by using 12 mm-size cbhg chips including all cost etc complete	One Cubic Meter	2.97	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	17257.34
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 6% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	40.06	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	162606.86
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm <sup>2</sup> with dimensional tolerance ± 6% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	82.61	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	338502.96
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	5.00	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	21762.02
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a	Column Base	One Cubic Meter	17.69	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	86315.40
b	Column & Beam	One Cubic Meter	13.88	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	145182.20

c	(C-2)Column for 1st floor	One Cubic Meter	0.38	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4448.32
d	Plinth Beam	One Cubic Meter	14.74	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	69676.28
e	Lintel Band	One Cubic Meter	2.84	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	23817.38
f	Chhaja	One Square Meter	14.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10820.72
g	Slab	One Cubic Meter	16.74	8836.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	149636.32
9	Straightening bent up or colled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	58.36	8072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	354351.28
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	448.95	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	86038.82
	(B)For parapet Both side	One Square Meter	54.31	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	10715.86
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	498.25	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	67043.63
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	170.23	150.60	Rupees One Hundred Fifty And Sixty Paise Only	25636.08
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	134.12	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	28607.33
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm, Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	9.15	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	31597.87
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement . 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	122.33	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	128645.67

16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	532.00	86.30	Rupees Eighty Six And Thirty Paise Only	45911.60
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	41.81	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7896.96
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	592.76	33.60	Rupees Thirty Three And Sixty Paise Only	19916.78
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	574.98	70.00	Rupees Seventy Only	40248.89
<b>Total</b>						<b>2107016.34</b>
<b>Limited to</b>						<b>2107016.00</b>

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

*Amu*  
3-5-21  
Asst Executive Engineer  
Hatadihi

*Jad*  
3-5-21  
Block Development Officer  
Hatadihi

*06/05/2021*  
Executive Engineer  
DRDA, Keonjhar

My / our quoted rate is \_\_\_\_\_ % (both in figure and words) excess over / less than / equal to the above estimated cost.

**NOTES:**

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction: .....

No. of over writing: .....

No. of interpolation: .....