

①
Bill of Quantity

Gopinathjew Vidyamandir, Ambo (Drinking Water-1.528 , Science lab-17.47 lakhs and Boundary-11.05 lakhs)

SL	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	151.97	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	27775.25
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	104.67	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	47605.63
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	44.46	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	192741.60
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	4.96	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	28795.95
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	46.89	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	190352.29
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	110.99	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	454756.57
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.14	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	22363.43
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	20.73	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	101121.20

b	Column & Beam	One Cubic Meter	18.19	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	190299.42
c	(C-2)Column for 1st floor	One Cubic Meter	0.40	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4621.31
d	Plinth Beam	One Cubic Meter	18.63	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	88076.28
e	Lintal Band	One Cubic Meter	2.65	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	22224.51
f	Chhaja	One Square Meter	13.37	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10136.85
g	Slab	One Cubic Meter	18.51	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	165425.27
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	65.76	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	399339.20
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	490.11	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	94347.02
	(B)For parapet Both side	One Square Meter	55.86	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	11020.53
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	622.35	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	84079.09
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	197.30	150.60	Rupees One Hundred Fifty And Sixty Paise Only	29713.60
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	148.27	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	31625.85
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29

15	Supplying ,fitting and fixing verified tiles in floors,treads of steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	116.48	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	120588.80
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	518.00	86.30	Rupees Eighty Six And Thirty Paise Only	44703.40
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	39.30	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7423.15
18	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	740.92	33.60	Rupees Thirty Three And Sixty Paise Only	24894.86
19	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	589.03	70.00	Rupees Seventy Only	41231.93
					Total	2460543.27
					Limited to	2460543.00

Approved 19 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Hansa
3.5.21
Asst Executive Engineer
Hatadihi

Jal
3.5.21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Koonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Japidas Bidyamandir, Badarampas (Class Room-37.2 lakhs , Toilet-3.112lakhs, Drinking Water-1.528 , Science lab-17.47 lakhs and Boundary-11.05 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	299.53	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	54743.53
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	296.95	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	135062.19
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	106.89	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	463435.29
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	10.74	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	62381.89
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	119.97	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	486996.62
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	181.27	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	742734.69
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	14.26	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	62102.29
8.	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials.					
a.	Column Base	One Cubic Meter	34.89	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	170179.04
b.	Column & Beam	One Cubic Meter	44.32	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	463622.39

c	(C-2)Column for 1st floor	One Cubic Meter	1.13	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	13180.21
d	Plinth Beam	One Cubic Meter	30.96	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	146324.94
e	Lintal Band	One Cubic Meter	8.22	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	68873.62
f	Chhaja	One Square Meter	40.37	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	30622.98
g	Slab	One Cubic Meter	64.26	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	574220.81
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	170.73	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	1036745.08
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	908.47	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	174880.93
	(B)For parapet Both side	One Square Meter	155.41	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	30662.69
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1019.94	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	137793.93
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and skury treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	651.26	150.60	Rupees One Hundred Fifty And Sixty Paise Only	98079.74
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	490.86	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	104699.81
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	14.63	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	50556.59
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	425.49	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	440510.10

16	Supplying, fitting and fixing Ceramic Floor tyles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	GST cost in 12% & labour cess 1% will be add at the time of aggre	One Kilogram	1836.50	86.30	Rupees Eighty Six And Thirty Paise Only	158489.95
18	Painting two coats with any approved synthetic enamale paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	141.51	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	26731.22
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia. of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	815.97	33.60	Rupees Thirty Three And Sixty Paise Only	27416.74
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1828.81	70.00	Rupees Seventy Only	128016.76
					Total	5901072.97
					Limited to	5901072.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Huss
3-5-21
Asst Executive Engineer
Hatadihi

Jad
3-5-21
Block Development Officer
Hatadihi

02
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

3

Bill of Quantity

Barahi High School, Bancho (Class Room-37.2 lakhs, Toilet-3.112lakhs, Drinking Water-1.528, Science lab-17.47 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	208.93	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	38186.03
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	279.39	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	127073.25
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	90.39	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	391911.05
4	CC (1:2:4) by using 12 mm size cbhg chips including all cost etc complete	One Cubic Meter	10.74	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	62381.89
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	92.01	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	373497.67
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	107.27	4087.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	439529.28
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	14.26	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	62102.29
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	20.52	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	100118.96
b	Column & Beam	One Cubic Meter	38.10	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	398558.10

c	(C-2)Column for 1st floor	One Cubic Meter	1.13	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	13180.21
d	Plinth Beam	One Cubic Meter	17.62	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	83296.08
e	Lintel Band	One Cubic Meter	8.22	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	68873.62
f	Chhaja	One Square Meter	40.37	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	30622.98
g	Slab	One Cubic Meter	64.26	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	574220.81
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	151.82	6072.30	Rupees Six Thousand Two And Thirty Paise Only	921895.18
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	569.78	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	109683.61
	(B)For parapet Both side	One Square Meter	155.41	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	30862.69
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	617.71	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	83452.52
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	651.26	150.60	Rupees One Hundred Fifty And Sixty Paise Only	98079.74
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	490.86	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	104699.81
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. in 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	14.63	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	50556.59
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	425.49	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	440510.10

16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1836.50	86.30	Rupees Eighty Six And Thirty Paise Only	158489.95
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	141.51	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	26731.22
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	75.06	33.60	Rupees Thirty Three And Sixty Paise Only	2521.88
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1828.81	70.00	Rupees Seventy Only	128016.76
					Total	4930861.23
					Limited to	4930861.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Handwritten: 3-5-21
Asst Executive Engineer
Hatadihi

Handwritten: 3-5-21
Block Development Officer
Hatadihi

Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

(A)
Bill of Quantity

BP High School, Bangore (Class Room-24.80 lakhs , Drinking Water-1.528 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	85.21	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	15573.73
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	121.19	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	55120.14
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	39.44	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	170981.77
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	4.24	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	24620.67
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	34.61	4059.40	Rupees Four Thousand Forty Nine And Forty Paise Only	140509.63
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	41.98	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	171998.71
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	6.68	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	29100.71
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	8.91	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	43485.57

b	Column & Beam	One Cubic Meter	16.87	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	176513.96
c	(C-2)Column for 1st floor	One Cubic Meter	0.53	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	6161.75
d	Plinth Beam	One Cubic Meter	7.53	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	35580.89
e	Lintel Band	One Cubic Meter	3.83	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	32123.00
f	Chhaja	One Square Meter	16.89	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	14331.28
g	Slab	One Cubic Meter	28.17	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	251728.01
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	67.79	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	411641.35
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	240.82	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	48358.03
	(B)For parapet Both side	One Square Meter	72.81	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	14365.88
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	241.68	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	32651.28
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	293.04	150.60	Rupees One Hundred Fifty And Sixty Paise Only	44132.36
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	225.62	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	48125.12
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29

15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc. required for the work all complete as per direction of Engineer in-Charge (For New work Only)	One Square Meter	201.74	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	208861.92
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	784.00	86.30	Rupees Eighty Six And Thirty Paise Only	67659.20
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	60.20	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	11371.63
18	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	848.36	70.00	Rupees Seventy Only	59385.14
					Total	2137661.03
					Limited to	2137661.00

Approved 18 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.


Asst Executive Engineer
Hatadihi


Block Development Officer
Hatadihi


Executive Engineer
DRDA,Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

D.C

5

Bill of Quantity

Balibareil High School, Balibareil (Class Room-37.2 lakhs, Toilet-3.112lakhs, Drinking Water-1.528, Science lab-17.47 lakhs and Boundary-11.05 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	299.53	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	54743.53
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	296.95	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	135062.19
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	106.89	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	463435.29
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	10.74	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	62381.89
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	119.97	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	486996.62
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	181.27	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	742734.69
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	14.26	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	62102.29
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	34.89	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	170179.04
b	Column & Beam	One Cubic Meter	44.32	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	463622.39

c	(C-2)Column for 1st floor	One Cubic Meter	1.13	11890.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	13180.21
d	Plinth Beam	One Cubic Meter	30.96	4725.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	146324.84
e	Lintel Band	One Cubic Meter	8.22	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	68873.62
f	Chhaja	One Square Meter	40.37	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	30622.98
g	Slab	One Cubic Meter	84.26	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	574220.81
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, holsting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	170.73	5072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	1036745.08
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	908.47	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	174880.93
	(B)For parapet Both side	One Square Meter	155.41	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	30662.69
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1019.94	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	137793.93
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	651.26	150.60	Rupees One Hundred Fifty And Sixty Paise Only	98079.74
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	490.86	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	104899.81
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	14.63	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	50556.59
15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	425.49	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	440510.10

15	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1836.50	86.30	Rupees Eighty Six And Thirty Paise Only	158489.95
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	141.51	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	26731.22
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	815.97	33.60	Rupees Thirty Three And Sixty Paise Only	27416.74
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1828.81	70.00	Rupees Seventy Only	128016.75
					Total	5901072.97
					Limited to	5901072.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Hram
2-5-21
Asst Executive Engineer
Hatadihi

Per
3-5-21
Block Development Officer
Hatadihi

03
06/5/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

(6)

Bill of Quantity

TM Academy ,Danar (Class Room-49.60 lakhs ,Toilet-3.112lakhs, Drinking Water-1.528 , and Boundary-11.05 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	287.56	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	52557.35
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	270.59	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	123072.89
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	100.31	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	434922.90
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	9.09	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	52801.65
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	106.49	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	432284.39
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	166.97	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	684129.46
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	13.37	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	58201.43
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	33.61	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	163966.82
b	Column & Beam	One Cubic Meter	41.37	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	432625.48

c	(C-2)Column for 1st floor	One Cubic Meter	1.05	11890.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	12323.50
d	Plinth Beam	One Cubic Meter	29.69	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	140311.49
e	Lintel Band	One Cubic Meter	7.67	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	64246.00
f	Chhaja	One Square Meter	37.79	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	28662.57
g	Slab	One Cubic Meter	59.31	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	530023.63
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grille, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	159.82	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	970458.50
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	874.95	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	168428.74
	(B)For parapet Both side	One Square Meter	145.62	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	26731.75
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	946.43	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	127863.21
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	600.30	150.60	Rupees One Hundred Fifty And Sixty Paise Only	90405.89
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	451.24	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	98250.24
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	14.63	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	50556.59
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	403.48	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	417723.85

16	Supplying, fitting and fixing Ceramic Floor tyles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard roiled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtale hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1710.50	86.30	Rupees Eighty Six And Thirty Paise Only	147616.15
18	Painting two coats with any approved synthetic enamale paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	132.31	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	24993.89
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	815.97	33.60	Rupees Thirty Three And Sixty Paise Only	27416.74
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1696.72	70.00	Rupees Seventy Only	118770.28
					Total	5491554.31
					Limited to	5491554.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

[Signature]
Asst Executive Engineer
Hatadihi

[Signature]
3.5.21
Block Development Officer
Hatadihi

[Signature]
06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

D.C. ⑦
Bill of Quantity

Dhenka High School, Dhenka (Class Room-49.60 lakhs, Toilet-3.112 lakhs, Drinking Water-1.528, Science lab-17.47 lakhs and Boundary-11.05 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	348.94	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	63775.10
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	357.69	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	162689.58
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	128.27	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	556140.26
4	CC (1:2:4) by using 12 mm size cbhg chips including all cost etc complete	One Cubic Meter	14.05	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	81597.60
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	125.42	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	509137.72
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	203.95	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	835680.62
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost, etc complete.	One Cubic Meter	18.50	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	80564.86
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	39.98	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	195027.93

b	Column & Beam	One Cubic Meter	53.34	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	558060.60
c	(C-2)Column for 1st floor	One Cubic Meter	1.45	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	16944.81
d	Plinth Beam	One Cubic Meter	34.99	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	165358.92
e	Lintel Band	One Cubic Meter	10.32	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	86470.51
f	Chhaja	One Square Meter	51.15	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	36801.42
g	Slab	One Cubic Meter	77.82	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	695448.91
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, holsting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	206.67	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	1254947.81
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1026.38	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	197578.44
	(B)For parapet Both side	One Square Meter	201.48	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	39752.28
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1166.55	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	157600.89
12	8 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	797.61	150.60	Rupees One Hundred Fifty And Sixty Paise Only	120119.50
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	599.51	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	127676.09
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Bakustrade of size 32mm.x32mm. x2mm. @ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	21.95	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	75834.88

15	Supplying ,fitting and fixing verified tiles in floors,treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	519.96	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	538312.65
16	Supplying ,fitting and fixing Ceramic Floor tyles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrops staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	2228.50	86.30	Rupees Eighty Six And Thirty Paise Only	192319.55
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	171.61	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	32417.04
19	Supplying,fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	815.97	33.60	Rupees Thirty Three And Sixty Paise Only	27416.74
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	2285.75	70.00	Rupees Seventy Only	160002.21
					Total	6981885.84
					Limited to	6981885.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Asst Executive Engineer
3-5-21
 Asst Executive Engineer
 Hatadihi

3-5-21
 Block Development Officer
 Hatadihi

06/05/2021
 Executive Engineer
 DRDA,Keonjhar

My / our quoted rate is _____ % (both in figure and words)
 excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity - (B)
Detail Estimate

Dhanurjayapur UG High School (Class Room-24.80 lakhs , Toilet-3.112 lakhs, Drinking Water-1.528 , Science lab-17.47 lakhs)						
Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	173.14	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	31643.87
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	218.94	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	99580.50
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	72.34	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	313634.26
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	9.81	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	56976.92
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	62.85	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	255129.14
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	87.98	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	360475.50
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	11.82	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	51484.14
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	16.70	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	81482.29
b	Column & Beam	One Cubic Meter	30.25	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	316482.36

c	(C-2)Column for 1st floor	One Cubic Meter	0.92	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	10783.06
d	Pinth Beam	One Cubic Meter	14.12	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	66749.17
e	Lintal Band	One Cubic Meter	6.49	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninaty Five Paise Only	54347.51
f	Chhaja	One Square Meter	32.26	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	24470.14
g	Slab	One Cubic Meter	49.65	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	443720.89
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, holting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	119.96	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	728456.56
10	16mm (3/4") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	446.87	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	86023.08
	(B)For parapet Both side	One Square Meter	128.67	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	25386.41
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	522.64	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	70608.20
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	504.56	150.60	Rupees One Hundred Fifty And Sixty Paise Only	75987.14
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	373.89	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	79750.97
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	14.63	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	50558.59
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	318.22	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	329450.72

16	Supplying, fitting and fixing Ceramic Floor tyles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	1444.50	86.30	Rupees Eighty Six And Thirty Paise Only	124660.35
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	111.41	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	21045.41
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	75.06	33.60	Rupees Thirty Three And Sixty Paise Only	2521.88
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	1437.39	70.00	Rupees Seventy Only	100617.07
					Total	3874013.07
					Limited to	3874013.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

H. Shank
3-5-21
Asst Executive Engineer
Hatadihi

Just
3-5-21
Block Development Officer
Hatadihi

06/05/2021
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

Bill of Quantity

Gedma High School, Gedma (Drinking Water-1.528 , Science lab-17.47 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	61.38	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	11217.75
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	87.10	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	39616.69
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	27.96	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	121217.36
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	4.96	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	28795.95
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	18.93	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	76853.33
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance \pm 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	36.99	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	151551.16
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	5.14	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	22363.43
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	6.37	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	31061.12

b	Column & Beam	One Cubic Meter	11.97	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	125235.13
c	(C-2)Column for 1st floor	One Cubic Meter	0.40	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	4621.31
d	Plinth Beam	One Cubic Meter	5.30	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	25047.43
e	Lintal Band	One Cubic Meter	2.65	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	22224.51
f	Chhaja	One Square Meter	13.37	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	10138.85
g	Slab	One Cubic Meter	18.51	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	165425.27
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	46.85	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	284489.30
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	151.43	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	29149.70
	(B)For parapet Both side	One Square Meter	55.86	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	11020.53
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"/10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	220.12	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	29737.68
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	197.30	150.60	Rupes One Hundred Fifty And Sixty Paise Only	29713.60
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	148.27	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	31625.85
14	Supplying,fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification,buffering,polishing etc. with cost, conveyance,	One Running Meter	7.32	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	25278.29

5	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc	One Square Meter	116.48	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	120588.80
16	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	518.00	85.30	Rupees Eighty Six And Thirty Paise Only	44703.40
17	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	39.30	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	7423.15
18	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	589.03	70.00	Rupees Seventy Only	41231.93
					Total	1490331.53
					Limited to	1490331.00

Approved 18 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

Hiran
Asst Executive Engineer
Hatadihi

Prad
3.5.21
Block Development Officer
Hatadihi

08/05/2024
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

10

Bill of Quantity

Hatadihi High School, Hatadihi (Class Room-62.00 lakhs , Toilet-3.112lakhs, Drinking Water-1.528 , Science lab-17.47 lakhs and Boundary-11.05 lakhs)

Sl	Description of Items	Unit	Quantity	Rate	In words	Amount
1	2	3	4	5		6
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth and making it fit for laying concrete and depositing the excavated materials away from the work site with all leads and lifts including dewatering if necessary from foundation complete as directed by Engineer-in-Charge.	One Cubic Meter	384.74	182.77	Rupees One Hundred Eighty Two And Seventy Seven Paise Only	70317.26
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials with labour and T&P required for the work.	One Cubic Meter	418.14	454.83	Rupees Four Hundred Fifty Four And Eighty Three Paise Only	190182.33
3	Cement concrete of proportion (1:3:6) with 40mm & down graded size hand broken H.G. metal for foundation concrete approved quality from approved quarry including hoisting, lowering and laying concrete to the required level ramming, watering, curing etc. complete including cost, conveyance & royalty of materials with all labour charges.	One Cubic Meter	146.33	4335.60	Rupees Four Thousand Three Hundred Thirty Five And Sixty Paise Only	634417.05
4	CC (1:2:4) by using 12 mm size cbhg chipps including all cost etc complete	One Cubic Meter	14.98	5808.20	Rupees Five Thousand Eight Hundred Eight And Twenty Paise Only	87002.56
5	Brick work with Fly Ash Bricks in cement mortar (1:6) in F & P of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	154.58	4059.40	Rupees Four Thousand Fifty Nine And Forty Paise Only	627506.25
6	Brick work with Fly Ash Bricks in cement mortar (1:6) in Superstructure of size 9"x5"x3" having crushing strength not less than 75 kg/cm ² with dimensional tolerance ± 8% including splays cutting circular moulding chamfering and corbelling and similar such type of works with all necessary projections watering and curing after immersing the bricks in water at least for six hours before use including cost, conveyance & royalty of materials with labour charges etc complete in all respect.	One Cubic Meter	223.25	4097.38	Rupees Four Thousand Ninety Seven And Thirty Eight Paise Only	914734.40
7	Fly ash Brick Massonry(1:6) in 1st floor for parapet wall including all cost,etc complete.	One Cubic Meter	20.95	4354.38	Rupees Four Thousand Three Hundred Fifty Four And Thirty Eight Paise Only	91203.00
8	RCC M-20 work with cement concrete with crushed granite 20mm down grade course aggregate of approved quality mixing by concrete mixer including hoisting, lowering and laying the concrete in position to proper slope and level and compacting by Vibrators in layers .not exceeding 0.15m depth including watering, curing for required period 28 days, centering & shuttering and finishing exposed surface smooth providing grooves wherever necessary including cost, conveyance, royalty and other taxes of all materials					
a	Column Base	One Cubic Meter	43.80	4878.07	Rupees Four Thousand Eight Hundred Seventy Eight And Seven Paise Only	213684.61
b	Column & Beam	One Cubic Meter	61.19	10461.87	Rupees Ten Thousand Four Hundred Sixty One And Eighty Seven Paise Only	640136.34

c	(C-2)Column for 1st floor	One Cubic Meter	1.65	11690.06	Rupees Eleven Thousand Six Hundred Ninety And Six Paise Only	19341.96
d	Plinth Beam	One Cubic Meter	38.49	4726.51	Rupees Four Thousand Seven Hundred Twenty Six And Fifty One Paise Only	181905.83
e	Lintel Band	One Cubic Meter	12.05	8379.95	Rupees Eight Thousand Three Hundred Seventy Nine And Ninety Five Paise Only	100996.62
f	Chhaja	One Square Meter	59.27	758.51	Rupees Seven Hundred Fifty Eight And Fifty One Paise Only	44954.27
g	Slab	One Cubic Meter	92.42	8936.51	Rupees Eight Thousand Nine Hundred Thirty Six And Fifty One Paise Only	825948.82
9	Straightening bent up or coiled M.S. rod or HYSD steel (Fe-415), cutting, bending, cranking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grids, hoisting, lowering and placing in proper position as required for RCC works including cost, conveyance and taxes of M.S. rod or HYSD steel and binding wires of 18 to 20 gauge and labour charges required for the work etc complete.	One Quintal	238.52	6072.30	Rupees Six Thousand Seventy Two And Thirty Paise Only	1448386.42
10	16mm (5/8") thick cement plaster (1:6) finishing smooth to inside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1149.29	192.50	Rupees One Hundred Ninety Two And Fifty Paise Only	221238.96
	(B)For parapet Both side	One Square Meter	228.22	197.30	Rupees One Hundred Ninety Seven And Thirty Paise Only	45028.57
11	12mm thick cement plaster (1:6) finishing smooth to Outside rough surface of 9"10" thick brick walls after racking out the joint including watering and curing with cost, conveyance, royalties and taxes of all materials and cost of all labour charges required for the work etc complete.	One Square Meter	1261.62	135.10	Rupees One Hundred Thirty Five And Ten Paise Only	170445.20
12	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slurry treatment including punning including cost, conveyance & royalty of materials.	One Square Meter	944.30	150.60	Rupees One Hundred Fifty And Sixty Paise Only	142212.10
13	20mm. thick cement plaster grading in c.m. 1:4 including cost conveyance and royalty of materials curing etc. complete.	One Square Meter	716.48	213.30	Rupees Two Hundred Thirteen And Thirty Paise Only	152824.94
14	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	One Running Meter	21.95	3454.70	Rupees Three Thousand Four Hundred Fifty Four And Seventy Paise Only	75834.88
15	Supplying, fitting and fixing verified tiles in floors, treads or steps of size 600mm x 600mm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 course sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	627.23	1035.30	Rupees One Thousand Thirty Five And Thirty Paise Only	649372.03

16	Supplying, fitting and fixing Ceramic Floor tiles 30cmx30cm / 40cmx40cm of approved make conforming to IS: 13755 laid on 20mm thick cement mortar (1:4) (1 cement : 4 coarse sand) and filling joints with white cement of approved quality including cost of materials, labour T&P etc required for the work all complete as per direction of Engineer-in-Charge (For New work Only)	One Square Meter	11.15	895.09	Rupees Eight Hundred Ninety Five And Nine Paise Only	9978.46
17	Supplying, fitting and fixing steel angle iron door & window with steel angle iron frame manufactured from standard rolled steel angle section of 40mmx40mmx6mm size with corners of the frame duly mattered and electrically welded with fishtail hold fasts made out of MS flat size 200mmx50mmx30mm wide and 5mm thick welded to the frame @ 6 nos per frame with 10mm dia MS round bar to be welded at the day with MS hinges of size 100mm 14SWG thick @ 3 nos and 15mm size 1 no. for single & double leaf shutter, aldrop staple and tower bolt hinges duly welded to the frame with one coat of anti corrosive red oxide zinc chrome primer including cost, conveyance, taxes of all materials with all labour charges for the work.	One Kilogram	2620.50	86.30	Rupees Eighty Six And Thirty Paise Only	226149.15
18	Painting two coats with any approved synthetic enamel paint of approved quality shade and make over a coat of priming to new wood work/ iron work including cost of the primer and paint, sand papering polishing the surface with cost, conveyance, royalty, taxes with all labour charges.	One Square Meter	201.71	188.90	Rupees One Hundred Eighty Eight And Ninety Paise Only	38102.85
19	Supplying, fitting & fixing of GI pipe in hand railing using 50mm. Dia of 2mm. thick circular pipe etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect.	Per One Rmt	6.10	333.00	Rupees Three Hundred Thirty Three Only	2030.49
20	Finishing walls with water proofing cement paint to exterior surface of wall with approved shade with two coats to give an even shade including cost of paint and cost of all labour with T&P.	One Square Meter	815.97	33.60	Rupees Thirty Three And Sixty Paise Only	27416.74
21	Wall painting with two coats weather coat paint of approved shade on new work to give an even shade including cost of paint.	One Square Meter	2677.17	70.00	Rupees Seventy Only	187401.90
					Total	8038733.99
					Limited to	8038733.00

Approved 21 items only

GST cost in 12% & labour cess 1% will be add at the time of agreement.

[Signature]
Asst Executive Engineer
Hatadihi

[Signature]
3.5.21
Block Development Officer
Hatadihi

[Signature]
Executive Engineer
DRDA, Keonjhar

My / our quoted rate is _____ % (both in figure and words)
excess over / less than / equal to the above estimated cost.

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation: