

Name of the Work: - Construction of Compound wall at BM High School, Tando

Estimated Cost:Rs 29,00,000.00

BILL OF QUANTITY (BOQ)


Amount put to Tender	:	Rs. 24,01,082.83
EMD	:	Bid Declaration
Class of Contractor	:	C' & B' Class only
Cost of Tender Paper	:	Rs.6000.00
Date of sale of Tender Paper	:	
Date of Receipt of Tender Paper	:	
Date of Opening of Tender	:	
Date required for completion	:	4(Four) Calender Month

Sl. No	Description of Items	Quantity	Unit	Rate	Amount
1	Earthwork excavation of foundation and including rough dressing and levelling the bed etc complete as directed by E-I-C.	180.27	Cum	198.78	35834.07
2	Filling in foundation and plinth with sand well watered and rammed including all cost conveyance rayalty etc complete	37.55	Cum	461.96	17346.60
3	Cement Concrete (1:3:6) using 4cm size hg metal with all taxes of materials including cost carriage rayalty etc complete	37.55	Cum	4510.00	169350.50
4	RCC M-20 using 20mm and down graded chips with all taxes of materials including cost conveyance rayalty etc complete				
(i)	Column Base & footing	31.05	Cum	5087.39	157963.46
(ii)	Grade Beam	13.51	Cum	4872.97	65833.82
(iii)	Comumn & Beam	9.78	Cum	10933.43	106928.95
5	Providing m s reinforcement (HYSD bar(Fe-415) cutting, bending ,binding,tying and placing in proper position with all taxes of materils including cost conveyance etc complete	41.00	Qtl	8719.92	357516.72
6	Fly Ash Brick Masonary in Cm (1:6) for Foundation & Plinth with all taxes including all cost caarriage rayalty etc.complete	105.24	Cum	4261.70	448501.31
7	Fly Ash Brick Masonary in Cm (1:6) for Superstructure with all taxes including all cost caarriage rayalty etc.complete	115.20	Cum	4337.65	499697.28
8	12 mm thick cement plaster with cm(1:6) on outside brick masonry with all taxes of materials including all cost conveyance rayalty etc complete	569.96	Sqm	146.10	83271.16
9	16 mm thick cement plaster with cm(1:6) on inside wall surface with all taxes of materials including all cost conveyance rayalty etc complete	569.96	Sqm	207.83	118454.79


10	20 mm thick cement plaster with cm(1:6) on brick/stone masonry with all taxes of materials including all cost conveyance rayalty etc complete	480.76	Sqm	216.54	104103.77
11	Priming one coat of approved wall primer(water base) to receive the paint with taxes of all materials including all cost conveyance etc complete	1620.69	Sqm	70.50	114258.65
12	Finishing wall with approved weather coat 2 coats on outside wall surface with taxes of all materials including cost conveyance etc	1620.69	Sqm	75.29	122021.75
Total					2401082.83

n(1) numbers of Items

Rupees Twenty four lakh one thousand Eighty Two and Eighty Three paise
GST Cost in 18.0 %(9.0% CGST+ 9.0% SGST) will be added during the time of agreement.


Asst. Executive Engineer
Saharpada Block


Block Development Officer
Saharpada Block


Addl Executive Officer(Technical)
Zilla Parisad, Keonjhar

TO BE FILLED BY THE TENDERER

My /Our quoted rate is _____ % Excess / Less/ Equal
to the corresponding estimate rate.
(Write both in words and Figures)

Notes:-

- 1 The Contractor should not write anything except quoting of percentage, excess/ less / equal to the amount put to Tender and in any case any thing else regarding tender rate is mentioned, the Tender is liable for reiection
- 2 Strike out which are not applicable.
- 3 Percentage quoted by the contractor shall be accurately filled in figure and words, so that there is no discrepancy.

- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall taken as correct.
- 5 The percentage quated in the tender with out mentioning excess or less will be treated as excess.
- 6 The contractor should write percentage, excess or less upto two decimal point only. If he/her writes the percentage excess or less more than two decimal points, it will be treated as cancelled.

Signature of the Contractor