

BILL OF QUANTITY (BOQ)

NAME OF THE WORK: - Construction of Boundary wall at -Brajabandhu Bidyapitha High School. for the year 2020-21

Amount put to Tender : Rs. 9,72,281.00
EMD : Exempted vide letter no 5984 dt. 27.04.2021
of works deptt.
Class of Contractor : D' & C' class only
Cost of Tender Paper : Rs. 4,000.00
Date required for completion : 6(Six) calender Month

Sl. no.	Item of Work	Quantity	Unit	Rate	Amount
1	Earthwork in excavation of foundation in hard soil or gravelly soil except sheet rock requiring blasting to proper profile with all leads, lifts and delifts to proper section and profile including dressing and levelling the bed upto required depth . as per direction of Engineer-in-charge	108.56	cum	182.80	19845.00
2	Supplying, filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty and all taxces of materials cost of all labour with T&P etc. complete. as per direction of Engineer-in-charge	15.80	cum	366.84	5796.00
3	C.C (1:3:6) using 40 mm hg metal in foundation with 40 mm size hand Broken metal including cost, conveyance, royalty etc complete as per direction of Engineer-in-charge	15.82	Cum	4393.28	69502.00
4	RCC (1:1.5:3) with using 12 mm CBG chips etc compl.	32.96	Cum	6387.50	210532.00
5	Straightening bent up or coiled M.S. rod or HYSD steel (Fe- 415), cutting, bending, cracking, hooking, welding or jointing (if required), the M.S rod or HYSD steel and binding, tying the grills, hoisting, lowering and placing in proper position as requireas per direction of Engineer-in-charge	25.38	Qntl	6479.06	164439.00
6	Rigid & smooth centring and shuttering				
	(A) Column foundation & Plinth	152.93	Sqm	101.05	15454.00
	(B) Column & beam	82.05	Sqm	716.99	58829.00
7	Fly ash.Brick masonry in cement mortar (1;6) in F/P including cost ,conveyance etcas per direction of Engineer-in-charge .	14.66	Cum	4139.04	60678.00
8	Fly ash.Brick masonry in cement mortar (1;6) in Superstructure including cost ,conveyance etcas per direction of Engineer-in-charge .	53.75	Cum	4176.99	224513.00

	6 mm thick cement plaster in C.M.(1:6) in internal surface of wall including cost ,conveyance etc as per direction of Engineer-in-charge	525.71	Sqm	190.97	100395.00
0	Finishing wall with weather coat of approved shade on new work to give an even shade including cost of paint including all cost taxes etc compl.	525.71	sqm	72.85	38298.00
11	Construction of display board with painting	1.00	Nos	4000.00	4000.00
					972281.00

N.B : Labour Cess 1% will be added and recovered while preparing the bill for payment.

TOTAL 11 (Eleven) NOS ITEM ONLY

Approved for 11 (Eleven) items only


Assistant Engineer
Anandapur Block


Executive Engineer
DRDA Keonjhar

3
06/5/2024

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The Tenderer should quote the percentage up to one decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

**Executive Engineer
DRDA Keonjhar**


**Block Development Officer
Anandapur Block**