

BILL OF QUANTITY (BOQ)

NAME OF THE WORK: - Construction of Block level Mini Stadium(2 nos. of Galleries & Changing Room with Toilet at Banspal Block)

Amount put to Tender	:	Rs.2872194.00
EMD	:	1% of the Amount put to Tender
Class of Contractor	:	C' & B' class only
Cost of Tender Paper	:	Rs.6000.00
Date required for completion	:	6(Six) calender Month

1	Earth work in excavation of foundation in hard soil or gravelly soil within 50 m initial lead and initial lift, including dressing and levelling the bed etc. complete	121.50	Each cum	203.05	24670.00
2	Supplying and filling foundation and plinth with sand wall watered and rammed with cost conveyance and royalty, taxes of all materials and labour (T&P) etc. complete.	47.00	Each cum	780.23	36670.00
3	P.C.C. (1:3:6) using 40 mm & down size b.h.g.c.b chips including watering, curing with cost, direction of Engineer-in-Charge.	39.31	Each Cum	4742.96	186445.00
4	R.C.C. M20 using 20 mm & down size b.h.g.c.b chips including watering, curing with cost, conveyance, taxes and cost of all labour (T&P) etc. complete as per the direction of Engineer-in-Charge.				
A	Plinth beam	1.4	Each Cum	5580.27	7812.00
B	Lintel & Sill band(G.F)	1.40	Each Cum	8879.90	12431.00
C	Roof Slab(G.F)	5.72	Each Cum	9339.34	53421.00
5	Straightening, Cutting, Bending, binding of M.S rod/TOR steeland tying upthe grills and placing in position including cost of binding wire with all cost conveyance , taxes etc completed in all respect as per the direction of Engineer-in-Charge.(GF)	8.53	Each Qntl	8469.37	72243.00
6	Fly Ash Brick masonry with CM (1:6) in foundation and plinth including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.	49.22	Each Cum	4555.89	224240.00
7	Fly Ash Brick masonry with CM (1:6) in superstructure including watering, curing with cost, conveyance, royalty and taxes of all materials & labour (T&P) etc. complete as per the direction of Engineer-in-Charge.(G . F)	325.52	Each Cum	4594.21	1495507.00

8	12mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.(GF)	690.93	Each Sqmt	154.16	106513.00
9	16mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	121.54	Each Sqmt	218.22	26522.00
10	20mm thick Grading Plaster (1:4) overroof slabs including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.	43.63	Each Sqmt	241.35	10530.00
11	20mm thick C.P. (1:6) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.(GF)	18.62		230.34	4288.00
12	12mm thick C.P. (1:4) including watering, curing, conveyance, royalty & all taxes of materials & labour with T&P required for the work etc. complete as per direction of Engineer-in-Charge.(GF)	9.21	Each Sqmt	320.06	2947.00
13	C.C.(1:2:4) including punning using 12mm size H.G.C.B. chips including cost,conveyance, royalty and all taxes of materials and cost of all labour T&P etc	0.18	Each Cum	6256	1126.00
14	Fixing Vetrified tiles in flooring in treads of steps and landing on 25mm thick bed cement mortar (1:1) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles.	22.76	Each Sqmt	1313.93	29905.00
15	Fixing Vetrified tiles in dados skirting and riser of steps on 12 mm thick cement plaster 1:3 jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles.	3.96	Each Sqmt	1424.19	5639.00

16	Fixing Chequered tiles in flooring in treads of steps and landing on 25mm thick bed cement mortar (1:1) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles.	107.95	Each Sqmt	848.43	91588.00
17	Fixing Ceramic tiles in flooring in treads of steps and landing on 25mm thick bed cement mortar (1:1) jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles.	71.5	Each Sqmt	1042.32	74525.00
18	Fixing ceramic wall tiles in dados skirting and riser of steps on 12 mm thick cement plaster 1:3 jointed with neat cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles.	255.04	Each Sqmt	1114.15	284152.00
19	Finishing surface of walls with acrylic putty of approved make and finished smooth and even surface to receive painting including cost of staging charges of cost of all material taxes , labour T&p etc complete .	67.45	Each Sqmt	67.10	4525.00
20	Priming one coat with any approved primer of wall primer .	408.07	Each Sqmt	63.67	25981.00
21	finishing walls with plastic imulsdion paint of approved shade on new work two coats to give an even shade including cost of paint	408.07	Each Sqmt	84.47	34469.00
22	Supplying , fitting and fixing of M.S. grills,doors ,windows made out of stuctural steel flat etc. including cost, conveyance, taxes of all materials and labour (T&P) etc. complete as pre direction of engineer in charge	414.00	Per Kg	147.28	60973.00
23	Painting two coats with enmal paint on new wood work/iron work with all cost of material and labour, T&P etc.	24.39	Each Sqmt	203.54	4964.00
				Total	2882086.00

Total 23 (Twenty Three) nos of item only.

GST-18% will be added at the time of Agreement over the quoted amount.

Asst. Exe. Engineer
Banspal Block

B.D.O.
Banspal.

Addr. Exicutive Officer Tech.
Zilla Parishada Keonjhar

TO BE FILLED BY THE TENDERER

1) My/ Our quoted rate is (both in figure and words)

- Equal to Estimate Cost
- Excess in Percentage
- Less in Percentage

	in Figure	In words
	%	
	%	
	%	

Notes:-

- 1) The Tenderer should quote the percentage up to two decimal point only before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.


Block Development Officer
Banspal.