

TENDER SCHEDULE

Name of the work: -Constr. Of Toilet complex at GP High school Badamasinabilla		Amount put to tender- Rs. 11,80,954.00				
		Class of Contractor- DAL				
		Cost of Tender paper- Rs. 6000.00				
		Time of completion- 04 months				
Sl. No.	Description of Item	Unit	Quantity	Total Qunty.	Rate	Amount
			Toilet			
1	Earth work in hard soil or gravelling soil for excavation of foundation including dressing and levelling of beds and depositing the soil away from the work side with all lead & lift including cost of all labour, T & P, dewatering, shoring and shuttering for the work etc. complete & as per direction of Engineer in charge	Cum	58.25	58.25	210.36	12253.47
2	Supplying and Filling in foundation and plinth with sand , well watered and rammed with all leads and lifts, cost convenience and royalty and all taxes of materials , cost of labour, T & P, dewatering, required for the works etc, complete in all respect as directed by engineer-in-charge.	Cum	33.75	33.75	559.89	18896.29
3	Cement concrete of proportion (1:3:6) with using 40 MM size hbg metal free from weathered and skin with including cost, convenience, royalty and taxes of all materials, labour etc including curing, dewatering if required in all respect including centering and shuttering etc.complete & as per direction of Engineer in charge	Cum	14.50	14.50	5024.35	72853.08
4	Reinforcement cement concrete M20 graded with 20 mm graded nominal size aggregate mechanically mixed and vibrated in foundation and bed protection of specification for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the	cum	23.22	23.22	5855.65	135968.19
5	Reinforcement cement concrete (1:2:4) with 12 mm graded nominal size aggregate mechanically mixed and vibrated in foundation and bed protection of specification for road and Bridge work & Direction of the Eng in charge the work etc complete as direction by the	cum	3.56	3.56	6851.49	24391.30
6	Suppling, coiled M.S rod or HYSD steel (Fe-415), cutting, bending, cranking, hooking, olding or jointing (if required) reinforcement including labour charges for cutting, bending, binding and straightening and tying the grills and placing in position including cost of binding wire 18 to 20 gauge as per drawing and technical specification as directed by the engineering-in-charge.	Qtl	21.00	21.00	9975.59	209487.39
7	Rigid & smooth centering and Shuttering.					
	(a) Column and beam	Sqm	46.01	46.01	112.31	5167.38
	(b) Wall beam	Sqm	46.62	46.62	851.66	39704.39
	(c) Lintel	Sqm	63.40	63.40	277.68	17604.91
	© Roof slab	Sqm	60.62	60.62	493.18	29896.57

Sl. No.	Description of Item	Unit	Quantity	Total Qunty.	Rate	Amount
8	Fly ash brick(25cmx12cmx8cm) masonry in CM(1:6)for superstructre in foundation and plinth having a crushing strength of not less than 75 kg/sqcm including splays cutting, circular moulding, chamfering and curbing and watering, curing etc including cost, conveyance, royalty and all taxes of materials with cost. of labour, T& P etc. complete required for the work complete in all respect as directed by the engineering -in-charge.					
	Foundation	Cum	21.69	21.69	5200.01	112788.22
9	In superstructre .	Cum	34.16	34.16	5233.01	178759.62
10	12 mm thick cement plaster in C.M. (1:6) finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	208.06	208.06	157.38	32744.48
11	16 mm thick cement plaster in C.M. (1:6) finishing smooth to inner side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	96.86	96.86	223.30	21628.84
12	20 mm thick cement plaster in C.M. (1:4) grading finishing smooth to outer side brickwork after ranking out the joints including watering and curing with cost, conveyance, royalty of all materials , labour with T & P required for the work including all taxes etc. complete in all respect all floors as directed by engineering-in-charge.	Sqm	54.67	54.67	268.50	14678.90
13	Painting2 coat with approved paint over 1 coat of cement washing on as per the direction of Engineer- in-charge.	Sqm	163.63	163.63	18.53	3032.06
14	Painting2 coat with approved paint over 1 coat of wall priming on as per the direction of Engineer- in -charge.	Sqm	163.63	163.63	67.95	11118.66
15	Finishing out side wall surface with weather coat with 2 coat with any approved shade overhead coat of priming including cost of all material and labour (T&P) etc.as per direction of Engineer-in-Charge.	Sqm	96.86	96.86	85.07	8239.88
16	Finishing in side wall surface with plastic emulsion paint with 2 coat with any approved shade overhead coat of priming including cost of all material and labour (T&P) etc.as per direction of Engineer-in-Charge.	Sqm	213.22	213.22	91.97	19609.84
17	Finishing wall with wall putty	Sqm	116.36	116.36	98.05	11409.10
18	Fixing tiles in ceramics tile in floor over thick bed of cement mortar 1:1 including rubbing and , polishing excluding cost of tiles	Sqm	39.74	39.74	1171.07	46538.32

Sl. No.	Description of Item	Unit	Quantity	Total Qty.	Rate	Amount
19	Fixing tiles in dados and riser of steps on 12mm thick cement plaster (1:3) including rubbing and polishing excluding cost of tiles	Sqm	112.83	112.83	1236.48	139512.04
20	Fixing tiles in cheakers tile in floor over thick bed of cement mortar 1:1 including rubbing and polishing excluding cost of tiles	Sqm	11.91	11.91	1231.83	14671.10
						1180954.03
					Rs.	1180954.00


(Rupees Eleven Lakhs Eighty Thousand nine hundred fiftythree) only.

Tender schedule for the project:-Constr. Of Toilet complex at G.P. High school, Badamasinabila. Under Badamasinabila GP Under DMF Ghatgaon Block is approved for RS 11,80,954/- (Rupees Eleven Lakhs Eighty Thousand nine hundred fiftythree) only with 20 (twenty) items only.

G.S.T. cost in 18% (C.G.S.T 9% + S.G.S.T. 9%) will be add at the time of agreement.


Asst. Executive Engineer
Ghatgaon


Block Development Officer
Ghatgaon


Addl. Executive Officer (Tech.)
Zilla Parisada, Keonjhar.

My /our quoted rate is% Excess/Less/Eq to the corresponding estimate rate.

(Write both in words and figures)

NOTES:-

1. The contractor should not write anything except quoting of percentage, excess/less/equal to the amount to tender and in any case any thing else regarding tender rate is mentioned, the tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words, so that there is no discrepancy.
4. If any discrepancy is found in the found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only. If he/her write the percentage excess or less more than two decimal points it will be treated as cancelled.

Asst. Executive Engineer
Ghatgaon


Block Development Officer
Ghatgaon

Addl. Executive Officer (Tech.)
Zilla Parisada, Keonjhar.