

Bill of Quantity

Name of the Work :- Construction of One no. of Additional Class Room at Kamarnali Primery school

Amount Put to Tender :- Rs

Rs. 12,16,505.00

Class of Contractor :-

C' & 'D' Class Only

Cost of Tender Paper :-

Rs 6000.00

Date Required for Completion :-

4 Calender Month

1	Earth work excavation of foundation in Hard soil with in 50m initial lead & 1.5m Initial lift Including Rough dressing & Brecking clods etc complete. As per direction of Engineer-in -charge.	35.74	Cum	274.39	9807.00
2	Filling Foundation and Plinth with Sand and well watered & rammed including all cost, canvayance, royalty, taxes etc complete. As per direction of Engineer-in -charge.	43.37	Cum	651.34	28248.00
3	C.C(1:4:8) using 4cm size Hand brocken Hard Granite metal of approved quality free from wethered skin including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	14.82	Cum	5586.18	82808.00
4	RCC work of M20 Grade with 20mm and down grade black hard granite crusher brocken stone chips including all cost, canvayance, royalty, taxes, curing, hoisting and laying etc complete As per direction of Engineer-in -charge.	23.68	Cum	6367.35	150772.00
5	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor. As per direction of Engineer-in -charge.				
	a) Lintel beam	16.44	Sqm	320.49	5269.00
	b) Column & Beams	52.96	Sqm	1016.75	53849.00
	c) Roof slab and Chajja	75.73	Sqm	574.81	43533.00
6	Fly ash Brick work 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cmsq with dimensional tolerance + 8percent in CM (1:6) in Superstructure including conveyance, royalty and other taxes etc. complete.		Cum		
	Foundation & Plinth	23.00	Cum	6093.00	140116.00
	Superstructure	21.79	Cum	6131.32	133573.00

7	Supplying, fitting and Placing uncoated HYSD bar reinforcement complete as per drawing and technical specification. As per direction of Engineer-in -charge.	23.68	Qntl	10115.62	239526.00
8	20mm thick cement plaster in cement mortar(1:4) over roof slab including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	70.66	Sqm	332.76	23514.00
9	12mm thick cement plaster in cement mortar(1:6) including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	109.82	Sqm	197.32	21669.00
10	16mm thick cement plaster in cement mortar(1:6) including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	109.82	Sqm	281.88	30955.00
11	20mm thick cement plaster in cement mortar(1:6) over the stne or bricks masonry including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	18.85	Sqm	295.62	5572.00
12	6mm thick cement plaster in cement mortar(1:4) over RCC surface for finished smooth including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	78.63	Sqm	243.82	19171.00
13	Fixing of vetrified tiles and marbles in floors, treads of steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shade of the tile including rubbing and polishing complete. As per direction of Engineer-in -charge.	71.02	Sqm	1603.43	113881.00
14	Fixing of vetrified tiles and marbles in dados and risers of steps on 12mm thick cement plaster (1:3) with neat cement slurry mixed with pigment to match the shade of the tile including rubbing and polishing complete. As per direction of Engineer-in -charge.	4.77	Sqm	1771.27	8446.00
15	Cement washing one coat over plastered including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	317.11	Sqm	21.63	6859.00
16	Priming one coat over plastered with water bound cement including all cost, canvayance, royalty, taxes, curing etc complete. As per direction of Engineer-in -charge.	317.11	Sqm	81.06	25705.00
17	Wall painting 2 coats with Distemper paint of approved shade on new work to give an even shade including cost of paint As per direction of Engineer-in -charge.	188.45	Sqm	93.89	17693.00
18	Wall painting 2 coats with of approved shade weather coat on new work to give an even shade including cost of paint As per direction of Engineer-in -charge.	128.67	Sqm	97.88	12594.00

19	Manufacturing, supplying, fitting and fixing MS doors & windows & frame made out of 35mmx35mmx6mm size MS angle iron of approved design including cost, conveyance, taxes with all labour charges required for the work. As per direction of Engineer-in -charge.	376.00	Kg	100.00	37600.00
20	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges. As per direction of Engineer-in -charge.	20.35	Sqm	262.74	5345.00

Rs 12,16,505.00

(Rupees Twelve lakhs Sixteen thousand Five hundred Five) Only
 GST cost of 18% (CGST 9% + SGST 9% will be added at the time of Agreement
 Total 20 (Twenty) Nos Item Only



Assistant Executive Engineer
 Ghatagaon Block



Block Development Officer
 Ghatagaon Block

Approved for
 Total 20 (Twenty) Nos Item Only

Executive Engineer
 Zilla parisada Keonjhar

TO BE FILLED BY THE TENDERER

My /Our quoted rate is ----- %

(Excess/Less/Equal to the corresponding estimate rate)
 (Write both in words and Figures)

Signature of the Contractor/Tenderer
 with address.

NOTES:-

1. The Contractor should not write anything except quoting of percentage, excess/less/equal to the amount to Tender and in any case any thing else regarding tender rate is mentioned, the Tender is liable for rejection.
2. Strike out which are not applicable.
3. Percentage quoted by the contractor shall be accurately filled in figure and words, so that there is no discrepancy.
4. If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
5. The percentage quoted in the tender will out mentioning excess or less will be treated as excess.
6. The contractor should write percentage excess or less up to two decimal point only. If he/her writes the percentage excess or less more than two decimal points it will be treated as cancelled.



Assistant Executive Engineer
 Ghatagaon Block



Block Development Officer
 Ghatagaon Block

Executive Engineer
 DRDA, Keonjhar