

BOQ / TENDER SCHEDULE FOR " CONSTRUCTION OF ONE ACR , AT - PANCHAYATA HIGH SCHOOL SASANGA , SASANGA G.P UNDER HATADIHI BLOCK OF DIST- KEONJHAR. "

TENDER SCHEDULE

S.Ino	Items	Unit	Qty	Rate in Rs/P	Amount in Rs/P
1	Earthwork excavation in hard soil within 50 mtr initial lead & 1.5 mtr lift including bed dressing , levelling etc complete as per the direction of Engineer in charge.	1cum	78.50	₹ 270.90	₹ 21,264.00
2	Filling (F&P) with sand well water rammed etc complete as per direction of Engineer in charge.	1cum	65.97	₹ 1,191.45	₹ 78,601.00
3	P.C.C. (1:3:6) using 40 mm size h.g. Metal including cost of materials, conveyance , roylty all labour etc complete as per the direction of engineer in charge.	1cum	21.35	₹ 6,389.83	₹ 1,36,442.00
4	C.C (1:2:4) with using 12mm.size h.b.g. metal complete.	1cum	4.56	₹ 7,914.03	₹ 36,088.00
5	Rigid & smooth centering shuttering for casting of Mass concrete	1sqm	23.60	₹ 247.51	₹ 5,841.00
6	R.C.C. M20- grade using 20mm & down graded h.g. C.b. Chips as per direction of Engineer in charge.				
i	Base & footings	1cum	10.43	₹ 6,821.32	₹ 71,133.00
ii	Grade beam / Plinth band	1cum	4.00	₹ 6,949.45	₹ 27,798.00
iii(a)	Column & beam (G.F.)	1cum	8.00	₹ 15,964.29	₹ 1,27,714.00
iv(a)	Lintel(G.F.)	1cum	1.19	₹ 14,434.29	₹ 17,176.00
v(a)	Roof slab chajja(G.F)	1cum	9.48	₹ 13,927.30	₹ 1,32,090.00
7	Cost of steel including all & carriage including labour for cutting, bending & binding including cost of binding wire etc.as per direction of Engineer in charge (G.F.)	1Qntl	33.10	₹ 9,106.00	₹ 3,01,428.00
8	Fly ash Brick masonry in C.M. (1:6) for (F&P) including cost.conveynce . labour all complete in (F&P) qoyantity including as per direction of Engineer in charge.	1cum	6.50	₹ 5,730.39	₹ 37,248.00
9	Fly ash Brick masonry in C.M. (1:6) for Super Structure including cost.conveynce . labour all complete in as per direction of Engineer in charge.(GF)	1cum	19.20	₹ 5,763.39	₹ 1,10,657.00
10	6 mm thick cp in (1:4) cm over R.C.C. Surface including slurry treatment etc complete as per the direction of Engineer in charge.(G.F.)	1sqm	91.97	₹ 211.88	₹ 19,487.00
11	12 mm thick cp in (1:6) cm over brick work out side only including cost of materials , labour all complete as per the direction of Engineer in charge.(G.F.)	1sqm	102.00	₹ 193.25	₹ 19,712.00
12	16 mm thick cp in (1:6) cm over brick work in side side only including cost of materials , labour all complete as per the direction of Engineer in charge.(G.F.)	1sqm	104.30	₹ 277.20	₹ 28,912.00
13	12 mm thick cp in (1:4) cm with cement punning & bitumen painting over brick work (plinth) only including cost of materials , labour all complete as per the direction of Engineer in charge.	1sqm	26.00	₹ 213.12	₹ 5,541.00
14	20 mm thick cp in (1:4) cm with cement plater for grading only including cost of materials , labour all complete as per the direction of Engineer in charge.(G.F.)	1sqm	75.94	₹ 301.16	₹ 22,869.00
15	2.5 cm thick D.P.C. In plith including cost of materials labour all complete as the direction of Engineer in charge	1sqm	10.12	₹ 316.51	₹ 3,204.00
16	Providing vetrified floor tile of size 600 mm x600mm over 20 mm thick cement mortar(1:4) of approved quality as per the direction of engineer in charge.(G.F)	1sqm	63.00	₹ 1,268.75	₹ 79,931.00

gfg

17	Providing floor tile of size 300 mm x300mm over 20 mm thick cement mortar(1:4) of approved quality as per the direction of engineer in charge.(G.F)	lsqm	14.30	₹ 1,310.32	₹ 18,741.00
18	Providing Glazed tile of size 300 mm x300mm over 12 mm thick cement mortar(1:3) for wall area of toilets of approved quality as per the direction of engineer in charge.(G.F.)	lsqm	5.00	₹ 1,296.23	₹ 6,481.00
19	Priming 1coat any approved primer with wall cement primer water bound with cost & labor etc complete.(G.F.)	lsqm	298.27	₹ 78.21	₹ 23,328.00
20	Providing two coat weather coat over plaster surface (out side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(G.F.)	lsqm	165.30	₹ 99.64	₹ 16,470.00
21	Providing plastic emulison two coat over plaster surface (in side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(G.F.)	lsqm	132.97	₹ 107.559	₹ 14,302.00
22	Providing water based Putty two coat over plaster surface (in side wall) including cost of materials labour all complete as per the direction of Engineer in charge.(G.F.)	lsqm	132.97	₹ 89.858	₹ 11,948.00
23	Providing two coat enamel paint with one coat primer all complete. As per direction of Engineer in charge.(G.F.)	lsqm	20.90	₹ 260.66	₹ 5,448.00
24	Providing for stainless steel stair case hand railings eith 3nos horizontal bar with vertical cicular pipe including cost of materials labour all complete as per direction of Engineer in charge.(G.F.)	lmtr	15.24	₹ 3,592.04	₹ 54,757.00
25	Supply & fitting & fixing of Iron door & windows including cost , conveyance all complete (G F)	lkg	230.00	₹ 110.00	₹ 25,300.00
26	Supply & fitting & fixing of Iron grills for windowsincluding cost , conveyance all complete(G F)	lkg	36.00	₹ 100.00	₹ 3,600.00
27	Filling (F&P) with excavated earth well water rammed etc complete as per direction of Engineer in charge.	lcum	3.60	₹ 180.60	₹ 650.00

(Rupees fourteen lakh sixty four thousand one hundred sixty one) only.

₹ 14,64,161.00

Tender value (Excluding G.S.T. 18%)

TOTAL 27 (TWENTY SEVEN) NOS ITEM ONLY

Assistant Executive Engineer
Hatadihi Block

Block Development Officer
Hatadihi Block

TOTAL 27 (TWENTY SEVEN) NOS ITEM ONLY

Addl. Executive Officer (Technical)
Zilla Parishad, Keonjhar

TO BE FILLED BY THE TENDERER


1) My/ Our quoted rate is (both in figure and words)

	in Figure	In words
Equal to Estimate Cost	%	
Excess in Percentage	%	
Less in Percentage	%	

Notes:-

- 1) The Tenderer should quote the percentage up to two decimal point only.
- 2) The Tenderer should go through the special conditions in the DTCN for percentage rate contract before tendering .
- 3) The Tenderers should quote their percentage only inside the space provided for the purpose .
- 4) The percentage quoted at any other place will not be taken into consideration.

Addl. Executive Officer (Technical)
Zilla Parishad, Keonjhar


Block Development Officer
Hatadihi Block