

Tender Schedule

Name of the Work :- Construction of Six Nos. of Additional class room at Tarini Thakurani Degree mahavidyalaya, Ghatgaon

		Amount Put to Tender			Rs	6924833.00
		Class Of Contractor			" B "	
		Time of completion			6 months	
		Cost of Tender Paper			Rs	10000.00
SI no	Description of Item	Unit	G.Floor	Total Quantity	Rate	Amount in Rs.
1	Earth work excavation of foundation in Hard soil with in 50m initial lead & 1.5m Initial lift Including Rough dressing & Brecking clods etc complete as per direction of Engineer -in- charge.	Cum	126.64	126.64	274.39	34749.00
2	Filling Foundation and Plinth with Sand and well watered & rammed including all cost, canvayance, royalty, taxes etc complete as per direction of Engineer -in- charge.	Cum	157.26	157.26	595.27	93612.00
3	C.C(1:3:6) using 4cm size Hand brocken Hard Granite metal of approved quality free from wethered skin including all cost, canvayance, royalty, taxes, curing etc complete as per direction of Engineer -in- charge.	cum	43.45	43.45	6265.75	272247.00
4	Fly ash Brick work 25cm x 12cm x 8cm size having crushing strength not less than 75 Kg/cmsq with dimensional tolerance + 8percent in CM (1:6) in Superstructure including conveyance, royalty and other taxes etc. completeas per direction of Engineer -in- charge.					
	Foundation & Plinth	cum	43.51	43.51	6046.76	263095.00
	Superstructure	Cum	51.88	51.88	6085.09	315694.00
	Superstructure 1st Floor	Cum	57.14	57.14	6454.36	368802.00
	Superstructure 2nd Floor	Cum	13.90	13.90	6823.63	94848.00
5	RCC work of M20 Grade with 20mm and down grade black hard granite crusher brocken stone chips including all cost, canvayance, royalty, taxes, curing, hoisting and laying etc complete as per direction of Engineer -in- charge.					
	Ground Floor	cum	90.89	90.89	6290.32	571727.00
	1st Floor	cum	58.31	58.31	6409.25	373723.00
	2nd Floor	cum	0.94	0.94	6528.18	6136.00

SI no	Description of Item	Unit	G.Floor	Total Quantity	Rate	Amount in Rs.
6	Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor.					
	a) Column Base	cum	65.80	65.80	122.18	8039.00
	e) Lintel beam	cum	54.91	54.91	320.49	17598.00
	d) Column & Beams	cum	211.77	211.77	1016.75	215317.00
	e) Roof slab and Chajja	cum	298.94	298.94	574.81	171834.00
	1st Floor					
	a) Lintel beam	cum	44.70	44.70	362.78	16216.00
	b) Column & Beams	cum	186.22	186.22	1199.50	223371.00
	c) Roof slab and Chajja	cum	283.57	283.57	649.34	184133.00
7	Supplying,fitting and Placing uncoated HYSD bar reinforcement complete as per drawing and technical specification..etc comp as per direction of Engineer -in- charge.					
	Ground Floor	Qntl	90.89	90.89	9406.88	854991.00
	1st Floor	Qntl	52.48	52.48	9465.55	496752.00
	2nd Floor	Qntl	0.85	0.85	9498.18	8073.00
8	16mm thick cement plaster in cement mortar(1:6) including all cost, canvayance, royalty, taxes, curing etc complete as per direction of Engineer -in- charge.					
		Sqm	289.08	289.08	279.62	80833.00
	1st Floor	Sqm	288.26	288.26	302.38	87164.00
	2nd Floor	Sqm	40.65	40.65	302.38	12292.00
9	12mm thick cement plaster in cement mortar(1:6) including all cost, canvayance, royalty, taxes, curing etc complete as per direction of Engineer -in- charge.					
		Sqm	289.08	289.08	218.26	63095.00


Sl no	Description of Item	Unit	G.Floor	Total Quantity	Rate	Amount in Rs.
	1st Floor	Sqm	288.26	288.26	224.85	64815.00
	2nd Floor	Sqm	40.65	40.65	233.51	9492.00
10	6 mm thick cement plaster in cement mortar (1:4) to RCC surface finished smooth including deep chipping and slury treatment including punning including cost, conveyance & royalty of materials ..etc comp as per direction of Engineer -in- charge.	Sqm	299.82	299.82	272.48	81695.00
	1st Floor	Sqm	286.26	286.26	248.22	71055.00
11	20mm thick cement plaster in cement mortar(1:4) including all cost, conveyance, royalty, taxes, curing etc complete as per direction of Engineer -in- charge.	Sqm	26.91	26.91	362.05	9743.00
	1st Floor	Sqm	26.91	26.91	384.82	10356.00
12	20mm thick cement plaster in cement mortar(1:6) including all cost, conveyance, royalty, taxes, curing etc complete as per direction of Engineer -in- charge.	Sqm	31.27	31.27	326.90	10222.00
13	Fixing of vetrified tiles and marbles in floors, treads of steps and landing on 25mm thick bed of cement mortar (1:1) jointed with neat cement slurry mixed with pigment to match the shade of the tile including rubbing and polishing complete as per direction of Engineer-in-charge.	Sqm	232.52	232.52	1588.82	369432.00
	1st Floor	Sqm	231.96	231.96	1880.24	436140.00
14	Fixing of vetrified tiles and marbles in dados and risers of steps on 12mm thick cement plaster (1:3) with neat cement slurry mixed with pigment to match the shade of the tile including rubbing and polishing complete	Sqm	15.63	15.63	1761.09	27526.00
	1st Floor	Sqm	10.34	10.34	1793.37	18543.00
15	supplying fitting and fixing chequered tile in floors on 25mm thick bed of cement mortar (1:3) as per direction of Engineer-in-charge.	Sqm	45.75	45.75	1306.29	59763.00
16	Fixing tiles in dados and riser of steps on 12mm thick cement plaster (1:3) including rubbing and polishing excluding cost of tiles	Sqm	14.40	14.40	1306.29	18811.00

SI no	Description of Item	Unit	G.Floor	Total Quantity	Rate	Amount in Rs.
17	Painting two coats with enamel paint over priming one coats with ready mixed zinc chromate yellow primer of approved brand on wood work including labour & material charges as per direction of Engineer -in- charge.	Sqm	105.35	105.35	295.90	31173.00
	1st Floor	Sqm	105.35	105.35	302.53	31872.00
18	Wallpriming one coat over plastered including all cost, canvayance, royalty, taxes, curing etc complete as per direction of Engineer -in- charge.	Sqm	909.26	909.26	90.90	82652.00
	1st Floor	Sqm	862.78	862.78	92.87	80126.00
19	2nd Floor	Sqm	81.30	81.30	94.83	7710.00
20	Finishing with wall putty over plastered with water bound cement including all cost, canvayance, royalty, taxes, curing etc complete.	Sqm	59.93	59.93	120.79	7239.00
	1st Floor	Sqm	59.93	59.93	122.73	7355.00
21	Wall painting 2 coats with plastic emulsion paint of approved shade on new work to give an even shade inculding cost of paint	Sqm	588.91	588.91	117.03	68920.00
	1st Floor	Sqm	574.52	574.52	119.16	68460.00
	2nd Floor	Sqm	40.65	40.65	121.27	4930.00
22	Wall painting 2 coats with of approved shade weather coat on new work to give an even shade inculding cost of paint as per direction of Engineer -in- charge.	Sqm	320.36	320.36	107.47	34429.00
	1st Floor	Sqm	288.26	288.26	109.14	31461.00
	2nd Floor	Sqm	40.65	40.65	111.06	4515.00

23	Manufacturing, supplying, fitting and fixing MS doors & windows & frame made out of 35mmx35mmx6mm size MS angle iron of approved design including cost, conveyance, taxes with all labour charges required for the work.	Kg	3187.50	3187.50	105.00	334688.00
24	Supplying, fitting & fixing of stainless steel of 304 grade in hand railing using 50mm. Dia of 2mm. thick circular pipe with Balustrade of size 32mm.x32mm. x2mm.@ 0.90m.C/C and stainless square pipe bracing of size 32mm.x32mm.x2mm. In 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials labour T & P etc. required for the completion in all respect as per direction of Engineer -in- charge.	rmt	36.58	36.58	2935.17	107369.00
					Rs	6924833.00

(Rupees Sixtynine Lakhs Twentyfour Thousand Eight Hundred Thirtythree) only

Total 24 (Twentyfour) nos item only.
GST Cost of 18% (CGST 9% + SGST 9%) will be added at the time of aggrement


Assistant Executive Engineer
Ghatagaon Block


Block Development Officer
Ghatagaon Block

Approved for
Total 24 (Twentyfour) nos item only.

Execitive Engineer
Zilla Parisada Keonjhar

TO BE FILLED BY THE TENDERER


My / Our quoted rate is%


(Excess / Less to the corresponding estimate rate)
(Write both in figures and words)

Signature of Tenderer

Notes:

- 1 The contractor should not write any thing excepting quoting of percentage, excess/less/equal to the amount to tender and in any case anything else regarding tender rate is mentioned, the tender is liable for rejection.
- 2 Strike out which is not applicable.
- 3 Percentage quoted by the contractor should be accurately filled in figure and words, so that there is no discrepancy.
- 4 If any discrepancy is found in the percentage quoted in words and figures then the percentage quoted by the contractor in words shall be taken as correct.
- 5 The percentage quoted in the tender should be mention excess or less clearly, if not , it will treat as excess.
- 6 The contractor should write percentage excess or less up to two decimal point only. If he/she writes the percentage excess or less more than two decimal points , it will treat as cancelled.


Assistant Executive Engineer
Ghatagaon Block


Block Development Officer
Ghatagaon Block

Addl. Executive Officer
(Technical)
Zilla Parishad , Keonjhar